



THE CITY RECORD

Official Journal of The City of New York

THE CITY RECORD U.S.P.S. 0114-660
Printed on paper containing 30% post-consumer material

VOLUME CXLV NUMBER 80

WEDNESDAY, APRIL 25, 2018

Price: \$4.00

TABLE OF CONTENTS

PUBLIC HEARINGS AND MEETINGS

Borough President - Brooklyn	1989
City Council	1990
City Planning Commission	1990
Comptroller	2017
Consumer Affairs	2018
Board of Education Retirement System	2018
Housing Authority	2018
Housing Preservation and Development	2018
Information Technology and Telecommunications	2019
Landmarks Preservation Commission	2019
Mayor's Office of Contract Services	2021
Board of Standards and Appeals	2021
Transportation	2021

PROPERTY DISPOSITION

Citywide Administrative Services	2023
Office of Citywide Procurement	2023
Police	2023

PROCUREMENT

Administration for Children's Services	2024
Office of Procurement	2024
Citywide Administrative Services	2024
Office of Citywide Procurement	2024
Education	2024
Contracts and Purchasing	2024
Environmental Protection	2025
Purchasing Management	2025
Human Resources Administration	2025
Parks and Recreation	2025

CONTRACT AWARD HEARINGS

Environmental Protection	2026
--------------------------	------

SPECIAL MATERIALS

Transportation	2026
Changes in Personnel	2027

LATE NOTICE

Citywide Administrative Services	2028
Office of Citywide Procurement	2028
Housing Authority	2028
Procurement	2028

THE CITY RECORD

BILL DE BLASIO

Mayor

LISETTE CAMILO

Commissioner, Department of Citywide
Administrative Services

ELI BLACHMAN

Editor, The City Record

Published Monday through Friday except legal holidays by the New York City Department of Citywide Administrative Services under Authority of Section 1066 of the New York City Charter.

Subscription \$500 a year, \$4.00 daily (\$5.00 by mail). Periodicals Postage Paid at New York, N.Y. POSTMASTER: Send address changes to THE CITY RECORD, 1 Centre Street, 17th Floor, New York, N.Y. 10007-1602

Editorial Office/Subscription Changes:
The City Record, 1 Centre Street, 17th Floor,
New York, N.Y. 10007-1602 (212) 386-0055

Visit The New City Record Online (CROL) at www.nyc.gov/cityrecord for a searchable database of all notices published in the City Record.

PUBLIC HEARINGS AND MEETINGS

See Also: Procurement; Agency Rules

BOROUGH PRESIDENT - BROOKLYN

■ PUBLIC HEARINGS

NOTICE IS HEREBY GIVEN that, pursuant to Section 201 of the New York City Charter, the Brooklyn borough president will hold a public hearing on the following matters in the Courtroom of Brooklyn Borough Hall, 209 Joralemon Street, Brooklyn, NY 11201, commencing at 6:00 P.M., on April 30, 2018.

Calendar Item 1 — 80 Flatbush Avenue Rezoning (180216 ZMK, 180217 ZRK, 180218 ZSK)

Applications submitted by the New York City Educational Construction Fund (ECF) and 80 Flatbush Avenue, LLC, pursuant to Sections 197-c and 201 of the New York City Charter, for a zoning map and text amendments intended to facilitate the redevelopment of a block in Downtown Brooklyn. The zoning map amendment would change a property, bounded by Flatbush Avenue, Schermerhorn Street, State Street, and Third Avenue, and located within the Special Downtown Brooklyn District (SDBD), from a C6-2 to a C6-9 district. The zoning text amendments would designate the project a Mandatory Inclusionary Housing (MIH) area, amend SDBD regulations to set the maximum permitted floor area for a C6-9 district to a Floor Area Ratio (FAR) of 18.0 for commercial and community facility use, and 12.0 FAR for residential use, make the C6-9 district subject to Tower Regulations in New York City Zoning Resolution (ZR) Section 101-223, and establish a new special permit modifying ZR Section 74-752. Pursuant to this permit, the City Planning Commission (CPC) would allow modifications of certain regulations as necessary, to facilitate an ECF project within a C6-9 district within the SDBD, in order to achieve the massing of the development site, as proposed in the application documents.

The requested special permit, pursuant to ZR Section 74-752, would permit modifications for the applicants' project per the following:

- Ground-Floor use regulations in order to permit the proposed configuration of the residential and school lobbies on Flatbush Avenue and State Street, which will contain significant retail frontage
- MIH requirements so as to allow Phase I construction of the proposed school without affordable housing, which would be constructed in Phase II of the development
- Minimum street wall height regulations along Flatbush Avenue to allow the configuration of building volumes on the development site, and provide larger floorplates, as well as an outdoor terrace for the proposed schools
- Tower lot coverage requirements in order to permit a maximum lot coverage of 56.7 percent in a tower taller than 150 feet
- Off-Street accessory parking regulations in order to waive the requirement to provide an off-street parking facility, due to the project's location in a Transit Zone

f. Loading berth requirements, to reduce the number of loading berths required in Phase I of the project

Such actions are intended to facilitate the creation of a new, mixed commercial, community facility, and residential development that will replace the existing Khalil Gibran International Academy (KGIA) public high school building with a new facility in a larger space, as well as a new elementary school that would share an auditorium and gymnasium with KGIA. In addition to school uses, the proposed development would provide residential space comprising of approximately 700 units of market-rate housing and 200 units of affordable housing; 201,000 sq. ft. of commercial office space, 42,200 sq. ft. of retail space, and 10,300 sq. ft. of non-school cultural space (within the existing KGIA building). The project is proposed to proceed in two phases in order to permit continued occupancy by KGIA until its new facility is complete. The first phase will result in the completion of the two schools and a mixed-use building fronting Flatbush Avenue and State Street; the second phase will be developed along Third Avenue, with segments of the existing KGIA building to remain at the corner of Schermerhorn and State Streets.

Accessibility questions: Inna Guzenfeld (718) 802-3754, iguzenfeld@brooklynbp.nyc.gov, by: Friday, April 27, 2018, 12:00 P.M.



a16-30

CITY COUNCIL

PUBLIC HEARINGS

NOTICE IS HEREBY GIVEN that the council has scheduled the following public hearings on the matters indicated below:

The Subcommittee on Zoning and Franchises will hold a public hearing on the following matter, in the Council Committee Room, 16th Floor, 250 Broadway, New York, NY 10007, commencing at 9:30 A.M., on Tuesday, May 1, 2018:

QUEENS CB - 2 PIATTO 20185176 TCQ

Application, pursuant to Section 20-226 of the Administrative Code of the City of New York concerning the petition of Piatto LLC, d/b/a Piatto, for a new revocable consent to establish, maintain, operate and use an unenclosed sidewalk café, located at 1-50 50th Avenue.

The Subcommittee on Landmarks, Public Siting and Maritime Uses will hold a public hearing in the Council Committee Room, 16th Floor, 250 Broadway, New York, NY 10007, commencing at 12:00 P.M., on Tuesday, May 1, 2018.

The Subcommittee on Planning, Dispositions and Concessions, will hold a public hearing on the following matters in the Council Committee Room, 16th Floor, 250 Broadway, New York, NY 10007, commencing at 2:00 P.M., on Tuesday, May 1, 2018:

MANHATTAN CB - 10 BETHANY PLACE 20185271 HAM

Application submitted by the New York City Department of Housing Preservation and Development, pursuant to Section 577 of Article XI of the Private Housing Finance Law for approval of a new real property tax exemption for property, located at Block 2047, Lots 7 and 10, and termination of the prior exemption, Community District 10, Council District 9.

BROOKLYN CB - 16 CSH 20185329 HAK

Application submitted by the New York City Department of Housing Preservation and Development, pursuant to Section 577 of Article XI of the Private Housing Finance Law for approval of a new real property tax exemption for property, located at Block 1499, Lot 13 and Block 1502, Lot 18, Community District 16, Borough of Brooklyn, Council District 41.

MANHATTAN CB - 3 TWO BUILDINGS TENANTS UNITED HDFC 20185330 HAM

Application submitted by the New York City Department of Housing Preservation and Development, pursuant to Section 696 of Article 16 of the General Municipal Law for approval of an urban development action area project, a real property tax exemption for the Disposition Area or Exemption Area, pursuant to Section 577 of Article XI of the Private Housing Finance Law, waiver of the area designation requirement and waiver of Sections 197-c and 197-d of the New York City Charter for property, located at 280 East 3rd Street (Block 372, Lot 12) and 230 East 4th Street (Block 399, Lot 24), in Community District 3, Borough of Manhattan, Council District 2.

Accessibility questions: Land Use Division - (212) 482-5154, by: Thursday, April 26, 2018, 3:00 P.M.



a25-m1

CITY PLANNING COMMISSION

PUBLIC HEARINGS

NOTICE IS HEREBY GIVEN that resolutions have been adopted by the City Planning Commission, scheduling a public hearing on the following matters to be held at NYC City Planning Commission Hearing Room, Lower Concourse, 120 Broadway, New York, NY, on Wednesday, May 9, 2018, at 10:00 A.M.

BOROUGH OF MANHATTAN Nos. 1-6 SPECIAL INWOOD DISTRICT REZONING No. 1

CD 12 C 180204 ZMM IN THE MATTER OF an application submitted by NYC Economic Development Corporation, pursuant to Section 197-c and 201 of the New York City Charter for the amendment of the Zoning Map, Section Nos. 1b, 1d, 3a and 3c:

- 1. eliminating from within an existing R7-2 District a C1-3 District bounded by West 207th Street, a line 100 feet northwesterly of Ninth Avenue, West 206th Street, and a line 100 feet southeasterly of Tenth Avenue;
2. eliminating from within an existing R7-2 District a C1-4 District bounded by:
a. Payson Avenue, a line 100 feet northwesterly of Dyckman Street, a line 100 feet northwesterly of Broadway, West 204th Street, Broadway, Academy Street, a line 100 feet southeasterly of Broadway, a line 200 feet northeasterly of Dyckman Street, Broadway, and Dyckman Street;
b. Cooper Street, a line 150 feet northeasterly of 207th Street, a line 100 feet northwesterly of Broadway, Isham Street, Broadway, West 213th Street, a line 100 feet southeasterly of Broadway, Isham Street, a line 100 feet southeasterly of Broadway, a line 150 feet northeasterly of West 20th Street, Tenth Avenue, a line 100 feet southwesterly of West 207th Street, Broadway, the northeasterly boundary line of a Park (Dyckman House Park), a line midway between Cooper Street and Broadway, and a line 100 feet southwesterly of West 207th Street;
c. a line 100 feet northwesterly of Broadway, West 215th Street, Broadway, and a northeasterly boundary line of a Park;
d. a line 100 feet northwesterly of Sherman Avenue, a line midway between Dyckman Street and Thayer Street, Nagle Avenue, and Thayer Street;
e. a line 100 feet northwesterly of Nagle Avenue, a line midway between Dyckman Street and Thayer Street, Sherman Avenue, and Thayer Street;
f. Sherman Avenue, West 204th Street, a line 100 feet southeasterly of Sherman Avenue, and Academy Street; and
g. Tenth Avenue, a line midway between West 205th Street and West 206th Street, a line 100 feet southeasterly of Tenth Avenue, and a line midway between West 203rd Street and West 204th Street;
2. changing from an R7-2 District to an R7A District property, bounded by:
a. Staff Street, a line 100 feet southwesterly of Dyckman Street, Seaman Avenue, and Riverside Drive;
b. the northeasterly centerline prolongation of Staff Street, the southwesterly and southeasterly boundary lines of a Park (Inwood Hill Park), the southeasterly boundary lines of a Park (Isham Park) and its north easterly prolongation, West 218th Street, a line 125 feet northwesterly of Broadway, West 215th Street, Broadway, West 213th Street, a line 100 feet northwesterly of Tenth Avenue, Sherman Avenue, Isham Street, a line 100 feet southeasterly of Sherman Avenue, a line 150 feet northwesterly of West 207th Street, a line 150 feet southeasterly of Sherman Avenue, a line 100 feet northeasterly of West 207th Street, a line 125 feet northwesterly of Broadway, West 207th Street, a line 100 feet southeasterly of Cooper Street, a line 100 feet northeasterly of West 204th Street, a northwesterly boundary line of a Park (Dyckman House Park) and its southwesterly prolongation, West 204th Street, a line 100 feet southeasterly of Cooper Street, Academy Street, a line 125 feet northwesterly of Broadway, and Dyckman Street;

- c. Broadway, a line midway between Dyckman Street and Thayer Street, Nagle Avenue, and Thayer Street;
 - d. a line midway between Vermilyea Avenue and Broadway, a line 100 feet southwesterly of West 207th Street, Tenth Avenue, Nagle Avenue, and a line 200 feet northeasterly of Dyckman Street; and
 - e. a line 100 feet southeasterly of Tenth Avenue, West 206th Street, a line 100 feet northwesterly of Ninth Avenue, and a line midway between West 203rd Street and West 204th Street;
3. changing from a C4-4 District to an R7A District property, bounded by a line midway between Broadway and Vermilyea Avenue, a line 200 feet northeasterly of Dyckman Street, Nagle Avenue, and a line 100 feet northeasterly of Dyckman Street;
 4. changing from a C8-3 District to an R7A District property, bounded by:
 - a. Staff Street, Dyckman Street, Seaman Avenue, and a line 100 feet southwesterly of Dyckman Street;
 - b. a line 100 feet northwesterly of Tenth Avenue, a line 300 feet northeasterly of Isham Street, and Sherman Avenue;
 - c. a line 125 feet northwesterly of Broadway, West 218th Street, Broadway, and West 215th Street; and
 - d. a line 100 feet southeasterly of Sherman Avenue, Isham Street, a line 150 feet southeasterly of Sherman Avenue, and a line 150 feet northeasterly of West 207th Street;
 5. changing from an M1-1 District to an R7A District property, bounded by a line 100 feet southeasterly of Tenth Avenue, a line midway between West 203rd Street and West 204th Street, a line 100 feet northwesterly of Ninth Avenue, West 203rd Street, a line 300 feet southeasterly of Tenth Avenue, and West 202nd Street;
 6. changing from an R7-2 District to an R7D District property, bounded by:
 - a. a line 125 feet northwesterly of Broadway, Academy Street, a line 100 feet southeasterly of Cooper Street, West 204th Street, the northwesterly boundary lines of a Park (Dyckman House Park), a line 100 feet southeasterly of Cooper Street, a line 100 feet southwesterly of West 207th Street, a line midway between Broadway and Vermilyea Avenue, a line 150 feet southwesterly of Academy Street, Broadway, and Cumming Street; and
 - b. a line midway between Broadway and Vermilyea Avenue, a line 100 feet northeasterly of West 207th Street, Post Avenue, and a line 100 feet southwesterly of West 207th Street;
 7. changing from a C8-3 District to an R7D District property, bounded by a line 100 feet northwesterly of Broadway, West 218th Street, Broadway, and West 215th Street;
 8. changing from an M1-1 District to an R8 District property, bounded by the northeasterly street line of former West 208th Street*, the U.S. Pierhead and Bulkhead Line, West 207th Street, and a line 100 feet southeasterly of Ninth Avenue;
 9. changing from an M3-1 District to an R8 District property, bounded by:
 - a. West 207th Street, the U.S. Pierhead and Bulkhead Line, West 206th Street, and a line 100 feet southeasterly of Ninth Avenue; and
 - b. West 205th Street, the U.S. Pierhead and Bulkhead Line, West 204th Street, and Ninth Avenue;
 10. changing from an R7-2 District to an R8A District property, bounded by:
 - a. a line 100 feet southeasterly of Cooper Street, West 207th Street, a line 125 feet northwesterly of Broadway, a line 100 feet northeasterly of West 207th Street, a line midway between Broadway and Vermilyea Avenue and its northeasterly prolongation, and a line 100 feet southwesterly of West 207th Street; and
 - b. Post Avenue, a line 100 feet northeasterly of West 207th Street, Tenth Avenue, West 207th Street, a line 100 feet northwesterly of Ninth Avenue, West 206th Street, a line 100 feet southeasterly of Tenth Avenue, a line midway between West 203rd Street and West 204th Street, Tenth Avenue, and a line 100 feet southwesterly of West 207th Street;
 11. changing from an M1-1 District to an R8A District property, bounded by:
 - a. Tenth Avenue, a line midway between West 203rd Street and West 204th Street, a line 100 feet southeasterly of Tenth Avenue, and West 203rd Street;
 - b. a line 100 feet northwesterly of Ninth Avenue, West 206th Street, Ninth Avenue, and West 203rd Street; and
 - c. a line passing through a point at angle 35 degrees to the northeasterly street line of West 207th Street distant 180 feet southeasterly (as measured along the street line) from the point of intersection of the northeasterly street line of West 207th Street and the southeasterly street line of Tenth Avenue, a line 100 feet northwesterly of Ninth Avenue, West 207th Street, and a line 180 feet southeasterly of Tenth Avenue;
12. changing from an M3-1 District to an R8A District property, bounded by Ninth Avenue, West 206th Street, a line 100 feet southeasterly of Ninth Avenue, and West 205th Street;
 13. changing from an M1-1 District to an R9A District property, bounded by:
 - a. Tenth Avenue, West 203rd Street, a line 100 feet southeasterly of Tenth Avenue, West 202nd Street, a line 150 feet southeasterly of Tenth Avenue, and West 201st Street; and
 - b. a line 100 feet northwesterly of Ninth Avenue, a line 100 feet northeasterly of West 207th Street, Ninth Avenue, the northeasterly Street line of former West 208th Street*, a line 100 feet southeasterly of Ninth Avenue, West 207th Street, Ninth Avenue, and West 206th Street;
 14. changing from an M3-1 District to an R9A District property, bounded by Ninth Avenue, West 207th Street, a line 100 feet southeasterly of Ninth Avenue, and West 206th Street;
 15. changing from an R7-2 District to a C4-4D District property, bounded by:
 - a. a line 125 feet northwesterly of Broadway, Cumming Street, Broadway, a line 150 feet southwesterly of Academy Street, a line midway between Vermilyea Avenue and Broadway, a line 200 feet northeasterly of Dyckman Street, Broadway, and Dyckman Street; and
 - b. a line 150 feet southeasterly of Sherman Avenue, a line 150 feet northeasterly of West 207th Street, Tenth Avenue, and a line 100 feet northeasterly of West 207th Street;
 16. changing from a C4-4 District to a C4-4D District property, bounded by:
 - a. Broadway, a line 200 feet northeasterly of Dyckman Street, a line midway between Vermilyea Avenue and Broadway, and a line midway between Thayer Street and Dyckman Street; and
 - b. a line midway between Post Avenue and Nagle Avenue and its southwesterly prolongation, a line 100 feet northeasterly of Dyckman Street, Nagle Avenue, and a line midway between Thayer Street and Dyckman Avenue;
 17. changing from a C8-3 District to a C4-4D District property, bounded by:
 - a. Broadway, West 218th Street, Tenth Avenue, and West 214th Street; and
 - b. a line 100 feet northwesterly of Tenth Avenue, West 213th Street, Tenth Avenue, a line 150 feet northeasterly of West 207th Street, a line 150 feet southeasterly of Sherman Avenue, Isham Street, Sherman Avenue, and a line 300 feet northeasterly of Isham Street;
 18. changing from a C8-4 District to a C4-4D District property, bounded by Broadway, West 214th Street, Tenth Avenue, and West 213th Street;
 19. changing from a C4-4 District to a C4-5D District property, bounded by a line midway between Vermilyea Avenue and Broadway and its southwesterly prolongation, a line 100 feet northeasterly of Dyckman Street, a line midway between Post Avenue and Nagle Avenue and its southwesterly prolongation, and a line midway between Thayer Street and Dyckman Street;
 20. changing from an M1-1 District to a C6-2 District property, bounded by Broadway, a line midway between West 218th Street and West 219th Street, a line 100 feet northwesterly of Ninth Avenue, West 219th Street, Ninth Avenue, and West 218th Street;
 21. changing from an M3-1 District to a C6-2 District property, bounded by Ninth Avenue, the southeasterly centerline prolongation of West 220th Street, a line 110 feet southeasterly of Ninth Avenue, a line 50 feet southwesterly of the southeasterly centerline prolongation of West 220th Street, the U.S. Pierhead and Bulkhead Line, and the southeasterly centerline prolongation of West 118th Street;
 22. changing from an M2-1 District to an M1-4 District property, bounded by Broadway, the U.S. Pierhead and Bulkhead Line, the southeasterly centerline prolongation of West 220th Street, and Ninth Avenue;

23. changing from an M3-1 District to an M1-4 District property, bounded by the southeasterly centerline prolongation of West 220th Street, the U.S. Pierhead and Bulkhead Line, a line 50 feet southwesterly of the southeasterly centerline prolongation of West 220th Street, and a line 110 feet southeasterly of Ninth Avenue;
24. changing from an M1-1 District to an M1-5 District property, bounded by Broadway, Ninth Avenue, West 219th Street, a line 100 feet northwesterly of Ninth Avenue, and a line midway between West 218th Street and West 219th Street;
25. changing from an M3-1 District to an M2-4 District property, bounded by Ninth Avenue, West 204th Street, the U.S. Pierhead and Bulkhead Line, and West 202nd Street;
26. establishing within a proposed R7A District a C2-4 District bounded by:
- Staff Street, Dyckman Street, Payson Avenue, a line 100 feet northeasterly of Dyckman Street, a line 125 feet northwesterly of Broadway, Dyckman Street, Seaman Avenue, and a line 100 feet southwesterly of Dyckman Street;
 - a line 100 feet northwesterly of Sherman Avenue, a line midway between Thayer Street and Dyckman Street, a line 100 feet southeasterly of Sherman Avenue, and Thayer Street;
 - a line 100 feet northwesterly of Nagle Avenue, a line midway between Thayer Street and Dyckman Street, Nagle Avenue, and Thayer Street;
 - a line 100 feet northwesterly of Sherman Avenue, a line 250 feet northeasterly of Dyckman Street, a line 100 feet southeasterly of Sherman Avenue, and a line 100 feet northeasterly of Dyckman Street;
 - Vermilyea Avenue, Academy Street, a line 100 feet northwesterly of Vermilyea Avenue, a line 100 feet northeasterly of Academy Street, a line 100 feet southeasterly of Vermilyea Avenue, and a line 100 feet southwesterly of Academy Street;
 - a line 100 feet northwesterly of Sherman Avenue, a line 100 feet northeasterly of Academy Street, Sherman Avenue, a line 100 feet southwesterly of West 204th Street, a line 100 feet northwesterly of Sherman Avenue, West 204th Street, Sherman Avenue, a line 100 feet southwesterly of West 207th Street, a line 100 feet southeasterly of Sherman Avenue, and Academy Street;
 - a line 100 feet northwesterly of Post Avenue, a line 100 feet northeasterly of West 204th Street, Post Avenue, and West 204th Street;
 - a line 100 feet northwesterly of Nagle Avenue, Academy Street, Nagle Avenue, and a line 100 feet southwesterly of Academy Street;
 - Cooper Street, a line 150 feet northeasterly of West 207th Street, a line 100 feet northwesterly of Broadway, a line 100 feet northeasterly of Isham Street, Broadway, West 213th Street, a line 100 feet southeasterly of Broadway, West 211th Street, Broadway, Isham Street, a line 100 feet southeasterly of Broadway, a line 150 feet northeasterly of West 207th Street, a line 100 feet northwesterly of Sherman Avenue, a line 100 feet southwesterly of Isham Street, Sherman Avenue, Isham Street, a line 100 feet southeasterly of Sherman Avenue, a line 150 feet northeasterly of West 207th Street, a line 100 feet southeasterly of Sherman Avenue, a line 100 feet northeasterly of West 207th Street, a line 125 feet northwesterly of Broadway, West 207th Street, a line 100 feet southeasterly of Cooper Street, and a line 100 feet southwesterly of West 207th Street;
 - a line 100 feet northwesterly of Sherman Avenue, a line 175 feet northeasterly of Isham Street, Sherman Avenue, and Isham Street;
 - a line 100 feet northwesterly of Broadway, West 215th Street, Broadway, and a northeasterly boundary line of a Park;
 - Indian Road, West 218th Street a line 150 feet southeasterly of Indian Road, and a line 100 feet southwesterly of West 218th Street;
 - a line 100 feet southeasterly of Tenth Avenue, West 206th Street, a line 100 feet northwesterly of Ninth Avenue, and a line midway between West 205th Street and West 206th Street; and
 - a line 100 feet southeasterly of Tenth Avenue, a line midway between West 204th Street and West 205th Street, a line 100 feet northwesterly of Ninth Avenue, and a line midway between West 203rd Street and West 204th Street;
27. establishing within a proposed R7D District a C2-4 District bounded by:
- a line 125 feet northwesterly of Broadway, Academy Street, a line 100 feet southeasterly of Cooper Street, West 204th Street, Broadway, Academy Street, a line 100 feet southeasterly of Broadway, a line 150 feet southwesterly of Academy Street, Broadway, and Cumming Street;
 - a line 100 feet southeasterly of Broadway, a line 100 feet southwesterly of West 207th Street, a line midway between Vermilyea Avenue and Broadway, and Academy Street;
 - a line 100 feet southeasterly of Cooper Street, a line 100 feet northwesterly of West 207th Street Broadway, and the northeasterly boundary line of a Park (Dyckman House Park);
 - a line midway between Vermilyea Avenue and Broadway, a line 100 feet northeasterly of West 207th Street, Post Avenue, and a line 100 feet southwesterly of West 207th Street; and
 - a line 100 feet northwesterly of Broadway, West 218th Street, Broadway, and West 215th Street;
28. establishing within a proposed R8 District a C2-4 District bounded by:
- a line 100 feet southeasterly of Ninth Avenue, the southwesterly street line of former West 208th Street*, the U.S. Pierhead and Bulkhead Line, and West 206th Street; and
 - Ninth Avenue, West 205th Street, the U.S. Pierhead and Bulkhead Line, and West 204th Street;
29. establishing within a proposed R8A District a C2-4 District bounded by:
- a line 100 feet southeasterly of Cooper Street, West 207th Street, a line 125 feet northwesterly of Broadway, a line 100 feet northeasterly of West 207th Street, a line midway between Vermilyea Avenue and Broadway, and a line 100 feet southwesterly of West 207th Street;
 - Post Avenue, a line 100 feet northeasterly of West 207th Street, Tenth Avenue, and a line 100 feet southwesterly of West 207th Street;
 - a line 100 feet southeasterly of Tenth Avenue, West 207th Street, a line 180 feet southeasterly of Tenth Avenue, a line passing through a point at angle 35 degrees to the northeasterly street line of West 207th Street distant 180 feet southeasterly (as measured along the street line) from the point of intersection of the northeasterly street line of West 207th Street and the southeasterly street line of Tenth Avenue, a line 100 feet northwesterly of Ninth Avenue, and West 206th Street;
 - a line midway between West 205th Street and West 206th Street, a line 100 feet southeasterly of Tenth Avenue, West 203rd Street, and Tenth Avenue; and
 - a line 100 feet northwesterly of Ninth Avenue, West 206th Street, a line 100 feet southeasterly of Ninth Avenue, West 205th Street, Ninth Avenue, and West 203rd Street;
30. establishing within a proposed R9A District a C2-4 District bounded by:
- a line 100 feet northwesterly of Ninth Avenue, a line 100 feet northeasterly of 207th Street, Ninth Avenue, the southwesterly street line of former West 208th Street*, a line 100 feet southeasterly of Ninth Avenue, and West 206th Street; and
 - Tenth Avenue, West 203rd Street, a line 100 feet southeasterly of Tenth Avenue, a line midway between West 201st Street and West 202nd Street, a line 150 feet southeasterly of Tenth Avenue, and West 201st Street and its northwesterly centerline prolongation;
31. establishing a Special Inwood District (IN) bounded by a line 125 feet northwesterly of Broadway, Academy Street, a line 100 feet southeasterly of Cooper Street, West 204th Street, Broadway, the northeasterly boundary line of a Park (Dyckman House Park) and its southeasterly prolongation, a line 100 feet southeasterly of Cooper Street, West 207th Street, a line 125 feet northwesterly of Broadway, a line 100 feet northwesterly of West 207th Street, a line 150 feet southeasterly of Sherman Avenue, Isham Street, Sherman Avenue, a line 300 feet northeasterly of Isham Street, a line 100 feet northwesterly of Tenth Avenue, West 213th Street, Broadway, West 215th Street, a line midway between Park Terrace East and Broadway, West 218th Street, Broadway, the U.S. Pierhead and Bulkhead Line, West 218th Street and its southeasterly centerline prolongation, Tenth Avenue, West 207th Street, a line 180 feet southeasterly of Tenth Avenue, a line passing through a point at angle 35 degrees to the northeasterly street line of West 207th Street distant 180 feet southeasterly (as measured along the street line) from the point of intersection of the northeasterly street line of West 207th Street and the southeasterly street line of

Tenth Avenue, a line 100 feet northwesterly of Ninth Avenue, a line 100 feet northeasterly of West 207th Street, Ninth Avenue, the northeasterly street line of former West 208th Street*, the U.S. Pierhead and Bulkhead Line, West 206th Street, a line 100 feet southeasterly of Ninth Avenue, West 205th Street, the U.S. Pierhead and Bulkhead Line, the former centerline of Academy Street*, West 201st Street, Tenth Avenue, a line 100 feet southwesterly of West 207th Street, a line midway between Vermilyea Avenue and Broadway, a line 100 feet northeasterly of Dyckman Street, Nagle Avenue, a line 100 feet southwesterly of Dyckman Street, Broadway, and Dyckman Street;

Borough of Manhattan, Community District 12, as shown on a diagram (for illustrative purposes only) dated January 16, 2018.

*Note: West 208th Street between Ninth Avenue and the U.S. Pierhead and Bulkhead Line and Academy Street between West 201st Street and the U.S. Pierhead and Bulkhead Line are proposed to be demapped under a concurrent related application (C 180073 MMM) for an amendment of the City Map.

No. 2

CD 12 C 180204(A) ZMM
IN THE MATTER OF an application submitted by NYC Economic Development Corporation, pursuant to Section 197-c and 201 of the New York City Charter for the amendment of the Zoning Map, Section Nos. 1b, 1d, 3a and 3c:

1. eliminating from within an existing R7-2 District a C1-3 District bounded by West 207th Street, a line 100 feet northwesterly of Ninth Avenue, West 206th Street, and a line 100 feet southeasterly of Tenth Avenue;
2. eliminating from within an existing R7-2 District a C1-4 District bounded by:
 - a. Payson Avenue, a line 100 feet northwesterly of Dyckman Street, a line 100 feet northwesterly of Broadway, West 204th Street, Broadway, Academy Street, a line 100 feet southeasterly of Broadway, a line 200 feet northeasterly of Dyckman Street, Broadway, and Dyckman Street;
 - b. Cooper Street, a line 150 feet northeasterly of 207th Street, a line 100 feet northwesterly of Broadway, Isham Street, Broadway, West 213th Street, a line 100 feet southeasterly of Broadway, Isham Street, a line 100 feet southeasterly of Broadway, a line 150 feet northeasterly of West 20th Street, Tenth Avenue, a line 100 feet southwesterly of West 207th Street, Broadway, the northeasterly boundary line of a Park (Dyckman House Park), a line midway between Cooper Street and Broadway, and a line 100 feet southwesterly of West 207th Street;
 - c. a line 100 feet northwesterly of Broadway, West 215th Street, Broadway, and a northeasterly boundary line of a Park;
 - d. a line 100 feet northwesterly of Sherman Avenue, a line midway between Dyckman Street and Thayer Street, Nagle Avenue, and Thayer Street;
 - e. a line 100 feet northwesterly of Nagle Avenue, a line midway between Dyckman Street and Thayer Street, Sherman Avenue, and Thayer Street;
 - f. Sherman Avenue, West 204th Street, a line 100 feet southeasterly of Sherman Avenue, and Academy Street; and
 - g. Tenth Avenue, a line midway between West 205th Street and West 206th Street, a line 100 feet southeasterly of Tenth Avenue, and a line midway between West 203rd Street and West 204th Street;
3. changing from an R7-2 District to an R7A District property, bounded by:
 - a. Staff Street, a line 100 feet southwesterly of Dyckman Street, Seaman Avenue, and Riverside Drive;
 - b. the northeasterly centerline prolongation of Staff Street, the southwesterly and southeasterly boundary lines of a Park (Inwood Hill Park), the southeasterly boundary lines of a Park (Isham Park) and its north easterly prolongation, West 218th Street, a line 125 feet northwesterly of Broadway, West 215th Street, Broadway, West 213th Street, a line 100 feet northwesterly of Tenth Avenue, Sherman Avenue, Isham Street, a line 100 feet southeasterly of Sherman Avenue, a line 150 feet northeasterly of West 207th Street, a line 150 feet southeasterly of Sherman Avenue, a line 100 feet northeasterly of West 207th Street, a line 125 feet northwesterly of Broadway, West 207th Street, a line 100 feet southeasterly of Cooper Street, a line 100 feet northeasterly of West 204th Street, a northwesterly boundary line of a Park (Dyckman House Park) and its southwesterly prolongation, West 204th Street, a line 100 feet southeasterly of Cooper Street, Academy Street, a line 125 feet northwesterly of Broadway, and Dyckman Street;
4. changing from a C4-4 District to an R7A District property, bounded by a line midway between Broadway and Vermilyea Avenue, a line 200 feet northeasterly of Dyckman Street, Nagle Avenue, and a line 100 feet northeasterly of Dyckman Street;
5. changing from a C8-3 District to an R7A District property, bounded by:
 - a. a line 100 feet northwesterly of Tenth Avenue, a line 300 feet northeasterly of Isham Street, and Sherman Avenue;
 - b. a line 125 feet northwesterly of Broadway, West 218th Street, Broadway, and West 215th Street; and
 - c. a line 100 feet southeasterly of Sherman Avenue, Isham Street, a line 150 feet southeasterly of Sherman Avenue, and a line 150 feet northeasterly of West 207th Street;
6. changing from an M1-1 District to an R7A District property, bounded by a line 100 feet southeasterly of Tenth Avenue, a line midway between West 203rd Street and West 204th Street, a line 100 feet northwesterly of Ninth Avenue, and West 203rd Street;
7. changing from a C8-3 District to an R7D District property, bounded by a line 100 feet northwesterly of Broadway, West 218th Street, Broadway, and West 215th Street;
8. changing from an M1-1 District to an R8 District property, bounded by the northeasterly street line of former West 208th Street*, the U.S. Pierhead and Bulkhead Line, West 207th Street, and a line 100 feet southeasterly of Ninth Avenue;
9. changing from an M3-1 District to an R8 District property, bounded by:
 - a. West 207th Street, the U.S. Pierhead and Bulkhead Line, West 206th Street, and a line 100 feet southeasterly of Ninth Avenue; and
 - b. West 205th Street, the U.S. Pierhead and Bulkhead Line, West 204th Street, and Ninth Avenue;
10. changing from an R7-2 District to an R8A District property, bounded by Post Avenue, a line 100 feet northeasterly of West 207th Street, Tenth Avenue, West 207th Street, a line 100 feet northwesterly of Ninth Avenue, West 206th Street, a line 100 feet southeasterly of Tenth Avenue, a line midway between West 203rd Street and West 204th Street, Tenth Avenue, and a line 100 feet southwesterly of West 207th Street;
11. changing from an M1-1 District to an R8A District property, bounded by:
 - a. Tenth Avenue, a line midway between West 203rd Street and West 204th Street, a line 100 feet southeasterly of Tenth Avenue, and West 203rd Street;
 - b. a line 100 feet northwesterly of Ninth Avenue, West 206th Street, Ninth Avenue, and West 203rd Street; and
 - c. a line passing through a point at angle 35 degrees to the northeasterly street line of West 207th Street distant 180 feet southeasterly (as measured along the street line) from the point of intersection of the northeasterly street line of West 207th Street and the southeasterly street line of Tenth Avenue, a line 100 feet northwesterly of Ninth Avenue, West 207th Street, and a line 180 feet southeasterly of Tenth Avenue;
12. changing from an M3-1 District to an R8A District property, bounded by Ninth Avenue, West 206th Street, a line 100 feet southeasterly of Ninth Avenue, and West 205th Street;
13. changing from an M1-1 District to an R9A District property, bounded by a line 100 feet northwesterly of Ninth Avenue, a line 100 feet northeasterly of West 207th Street, Ninth Avenue, the northeasterly Street line of former West 208th Street*, a line 100 feet southeasterly of Ninth Avenue, West 207th Street, Ninth Avenue, and West 206th Street;
14. changing from an M3-1 District to an R9A District property, bounded by Ninth Avenue, West 207th Street, a line 100 feet southeasterly of Ninth Avenue, and West 206th Street;
15. changing from a C8-3 District to a C4-4A District property, bounded by Staff Street, Dyckman Street, Seaman Avenue, and a line 100 feet southwesterly of Dyckman Street;

16. changing from an R7-2 District to a C4-4D District property, bounded by:
- a line 125 feet northwesterly of Broadway, Cumming Street, Broadway, a line 150 feet southwesterly of Academy Street, a line midway between Vermilyea Avenue and Broadway, a line 200 feet northeasterly of Dyckman Street, Broadway, and Dyckman Street;
 - a line 100 feet southeasterly of Cooper Street, West 207th Street, a line 125 feet northwesterly of Broadway, a line 100 feet northeasterly of West 207th Street, a line midway between Broadway and Vermilyea Avenue and its northeasterly prolongation, and a line 100 feet southwesterly of West 207th Street; and
 - a line 150 feet southeasterly of Sherman Avenue, a line 150 feet northeasterly of West 207th Street, Tenth Avenue, and a line 100 feet northeasterly of West 207th Street;
17. changing from a C4-4 District to a C4-4D District property, bounded by:
- Broadway, a line 200 feet northeasterly of Dyckman Street, a line midway between Vermilyea Avenue and Broadway, and a line midway between Thayer Street and Dyckman Street; and
 - a line midway between Post Avenue and Nagle Avenue and its southwesterly prolongation, a line 100 feet northeasterly of Dyckman Street, Nagle Avenue, and a line midway between Thayer Street and Dyckman Avenue;
18. changing from a C8-3 District to a C4-4D District property, bounded by:
- Broadway, West 218th Street, Tenth Avenue, and West 214th Street; and
 - a line 100 feet northwesterly of Tenth Avenue, West 213th Street, Tenth Avenue, a line 150 feet northeasterly of West 207th Street, a line 150 feet southeasterly of Sherman Avenue, Isham Street, Sherman Avenue, and a line 300 feet northeasterly of Isham Street;
19. changing from an R7-2 District to a C4-5D District property, bounded by:
- a line 100 feet northwesterly of Broadway, Academy Street, a line 100 feet southeasterly of Cooper Street, West 204th Street, the northwesterly boundary lines of a Park (Dyckman House Park), a line 100 feet southeasterly of Cooper Street, a line 100 feet southwesterly of West 207th Street, a line midway between Broadway and Vermilyea Avenue, a line 150 feet southwesterly of Academy Street, Broadway, and Cumming Street; and
 - a line midway between Broadway and Vermilyea Avenue, a line 100 feet northeasterly of West 207th Street, Post Avenue, and a line 100 feet southwesterly of West 207th Street;
20. changing from a C4-4 District to a C4-5D District property, bounded by a line midway between Vermilyea Avenue and Broadway and its southwesterly prolongation, a line 100 feet northeasterly of Dyckman Street, a line midway between Post Avenue and Nagle Avenue and its southwesterly prolongation, and a line midway between Thayer Street and Dyckman Street;
21. changing from an M1-1 District to a C6-2 District property, bounded by Broadway, a line midway between West 218th Street and West 219th Street, a line 100 feet northwesterly of Ninth Avenue, West 219th Street, Ninth Avenue, and West 218th Street;
22. changing from an M2-1 District to a C6-2 District property, bounded by Ninth Avenue, the south easterly centerline prolongation of West 218th Street, the U.S. Pierhead and Bulkhead Line, and the southeasterly prolongation of a line 22 feet northeasterly of the southwesterly street line of West 218th Street;
23. changing from an M3-1 District to a C6-2 District property, bounded by Ninth Avenue, the southeasterly centerline prolongation of West 220th Street, a line 110 feet southeasterly of Ninth Avenue, a line 50 feet southwesterly of the southeasterly centerline prolongation of West 220th Street, the U.S. Pierhead and Bulkhead Line, and the southeasterly centerline prolongation of West 118th Street;
24. changing from a C8-4 District to a C6-2A District property, bounded by Broadway, West 214th Street, Tenth Avenue, and West 213th Street;
25. changing from an M2-1 District to an M1-4 District property, bounded by Broadway, the U.S. Pierhead and Bulkhead Line, the southeasterly centerline prolongation of West 220th Street, and Ninth Avenue;
26. changing from an M3-1 District to an M1-4 District property, bounded by the southeasterly centerline prolongation of West 220th Street, the U.S. Pierhead and Bulkhead Line, a line 50 feet southwesterly of the southeasterly centerline prolongation of West 220th Street, and a line 110 feet southeasterly of Ninth Avenue;
27. changing from an M1-1 District to an M1-5 District property, bounded by Broadway, Ninth Avenue, West 219th Street, a line 100 feet northwesterly of Ninth Avenue, and a line midway between West 218th Street and West 219th Street;
28. changing from an M3-1 District to an M2-4 District property, bounded by Ninth Avenue, West 204th Street, the U.S. Pierhead and Bulkhead Line, and West 202nd Street;
29. changing from an M1-1 District to an M1-4/R7A District property, bounded by a line 100 feet southeasterly of Tenth Avenue, West 203rd Street, a line 300 feet southeasterly of Tenth Avenue, and West 202nd Street;
30. changing from an M1-1 District to an M1-4/R9A District property, bounded by Tenth Avenue, West 203rd Street, a line 100 feet southeasterly of Tenth Avenue, West 202nd Street, a line 150 feet southeasterly of Tenth Avenue, and West 201st Street;
31. establishing within a proposed R7A District a C2-4 District bounded by:
- Payson Avenue, a line 100 feet northeasterly of Dyckman Street, a line 125 feet northwesterly of Broadway, and Dyckman Street;
 - a line 100 feet northwesterly of Sherman Avenue, a line midway between Thayer Street and Dyckman Street, a line 100 feet southeasterly of Sherman Avenue, and Thayer Street;
 - a line 100 feet northwesterly of Nagle Avenue, a line midway between Thayer Street and Dyckman Street, Nagle Avenue, and Thayer Street;
 - a line 100 feet northwesterly of Sherman Avenue, a line 250 feet northeasterly of Dyckman Street, a line 100 feet southeasterly of Sherman Avenue, and a line 100 feet northeasterly of Dyckman Street;
 - Vermilyea Avenue, Academy Street, a line 100 feet northwesterly of Vermilyea Avenue, a line 100 feet northeasterly of Academy Street, a line 100 feet southeasterly of Vermilyea Avenue, and a line 100 feet southwesterly of Academy Street;
 - a line 100 feet northwesterly of Sherman Avenue, a line 100 feet southeasterly of Academy Street, Sherman Avenue, a line 100 feet southwesterly of West 204th Street, a line 100 feet northwesterly of Sherman Avenue, West 204th Street, Sherman Avenue, a line 100 feet southwesterly of West 207th Street, a line 100 feet southeasterly of Sherman Avenue, and Academy Street;
 - a line 100 feet northwesterly of Post Avenue, a line 100 feet northeasterly of West 204th Street, Post Avenue, and West 204th Street;
 - a line 100 feet northwesterly of Nagle Avenue, Academy Street, Nagle Avenue, and a line 100 feet southwesterly of Academy Street;
 - Cooper Street, a line 150 feet northeasterly of West 207th Street, a line 100 feet northwesterly of Broadway, a line 100 feet northeasterly of Isham Street, Broadway, West 213th Street, a line 100 feet southeasterly of Broadway, West 211th Street, Broadway, Isham Street, a line 100 feet southeasterly of Broadway, a line 150 feet northeasterly of West 207th Street, a line 100 feet northwesterly of Sherman Avenue, a line 100 feet southwesterly of Isham Street, Sherman Avenue, Isham Street, a line 100 feet southeasterly of Sherman Avenue, a line 150 feet southeasterly of Sherman Avenue, a line 100 feet northeasterly of West 207th Street, a line 125 feet northwesterly of Broadway, West 207th Street, a line 100 feet southeasterly of Cooper Street, and a line 100 feet southwesterly of West 207th Street;
 - a line 100 feet northwesterly of Sherman Avenue, a line 175 feet northeasterly of Isham Street, Sherman Avenue, and Isham Street;
 - a line 100 feet northwesterly of Broadway, West 215th Street, Broadway, and a northeasterly boundary line of a Park;
 - Indian Road, West 218th Street a line 150 feet southeasterly of Indian Road, and a line 100 feet southwesterly of West 218th Street;
 - a line 100 feet southeasterly of Tenth Avenue, West 206th Street, a line 100 feet northwesterly of Ninth Avenue, and a line midway between West 205th Street and west 206th Street; and
 - a line 100 feet southeasterly of Tenth Avenue, a line midway

- between West 204th Street and West 205th Street, a line 100 feet northwesterly of Ninth Avenue, and a line midway between West 203rd Street and West 204th Street;
- 32. establishing within a proposed R7D District a C2-4 District bounded by a line 100 feet northwesterly of Broadway, West 218th Street, Broadway, and West 215th Street;
- 33. establishing within a proposed R8 District a C2-4 District bounded by:
 - a. a line 100 feet southeasterly of Ninth Avenue, the southwesterly street line of former West 208th Street*, the U.S. Pierhead and Bulkhead Line, and West 206th Street; and
 - b. Ninth Avenue, West 205th Street, the U.S. Pierhead and Bulkhead Line, and West 204th Street;
- 34. establishing within a proposed R8A District a C2-4 District bounded by:
 - a. Post Avenue, a line 100 feet northeasterly of West 207th Street, Tenth Avenue, and a line 100 feet southwesterly of West 207th Street;
 - b. a line 100 feet southeasterly of Tenth Avenue, West 207th Street, a line 180 feet southeasterly of Tenth Avenue, a line passing through a point at angle 35 degrees to the northeasterly street line of West 207th Street distant 180 feet southeasterly (as measured along the street line) from the point of intersection of the northeasterly street line of West 207th Street and the southeasterly street line of Tenth Avenue, a line 100 feet northwesterly of Ninth Avenue, and West 206th Street;
 - c. a line midway between West 205th Street and West 206th Street, a line 100 feet southeasterly of Tenth Avenue, West 203rd Street, and Tenth Avenue; and
 - d. a line 100 feet northwesterly of Ninth Avenue, West 206th Street, a line 100 feet southeasterly of Ninth Avenue, West 205th Street, Ninth Avenue, and West 203rd Street;
- 35. establishing within a proposed R9A District a C2-4 District bounded by a line 100 feet northwesterly of Ninth Avenue, a line 100 feet northeasterly of 207th Street, Ninth Avenue, the southwesterly street line of former West 208th Street*, a line 100 feet southeasterly of Ninth Avenue, and West 206th Street; and
- 36. establishing a Special Inwood District (IN) bounded by a line 125 feet northwesterly of Broadway, Academy Street, a line 100 feet southeasterly of Cooper Street, West 207th Street, West 204th Street, Broadway, the northeasterly boundary line of a Park (Dyckman House Park) and its southeasterly prolongation, a line 100 feet southeasterly of Cooper Street, West 207th Street, a line 125 feet northwesterly of Broadway, a line 100 feet northeasterly of West 207th Street, a line 150 feet southeasterly of Sherman Avenue, Isham Street, Sherman Avenue, a line 300 feet northeasterly of Isham Street, a line 100 feet northwesterly of Tenth Avenue, West 213th Street, Broadway, West 215th Street, a line midway between Park Terrace East and Broadway, West 218th Street, Broadway, the U.S. Pierhead and Bulkhead Line, the southeasterly prolongation of a line 22 feet northeasterly of the southwesterly street line of West 218th Street, Tenth Avenue, West 207th Street, a line 180 feet southeasterly of Tenth Avenue, a line passing through a point at angle 35 degrees to the northeasterly street line of West 207th Street distant 180 feet southeasterly (as measured along the street line) from the point of intersection of the northeasterly street line of West 207th Street and the southeasterly street line of Tenth Avenue, a line 100 feet northwesterly of Ninth Avenue, a line 100 feet northeasterly of West 207th Street, Ninth Avenue, the northeasterly street line of former West 208th Street*, the U.S. Pierhead and Bulkhead Line, West 206th Street, a line 100 feet southeasterly of Ninth Avenue, West 205th Street, the U.S. Pierhead and Bulkhead Line, the centerline of former Academy Street, West 201st Street, Tenth Avenue, a line 100 feet southwesterly of West 207th Street, a line midway between Vermilyea Avenue and Broadway, a line 100 feet northeasterly of Dyckman Street, Nagle Avenue, a line 100 feet southwesterly of Dyckman Street, Broadway, and Dyckman Street;

Borough of Manhattan, Community District 12, as shown on a diagram (for illustrative purposes only) dated April 18, 2018.

*Note: West 208th Street between Ninth Avenue and the U.S. Pierhead and Bulkhead Line is proposed to be demapped under a concurrent related application (C 180073 MMM) for an amendment of the City Map.

No. 3

CD 12 IN THE MATTER OF an application submitted by the New York City Economic Development Corporation, pursuant to Section 201 of the New York City Charter, for an amendment of the Zoning Resolution of the City of New York establishing the Special Inwood District (Article

N 180205 ZRM

XIV, Chapter 2), and modifying related Sections, including Appendix F, for the purpose of establishing a Mandatory Inclusionary Housing area.

Matter underlined is new, to be added; Matter ~~struck out~~ is to be deleted; Matter within # # is defined in Section 12-10; * * * indicates where unchanged text appears in the Zoning Resolution

ARTICLE I - GENERAL PROVISIONS

Chapter 1 - Title, Establishments of Controls and Interpretations of Regulations

* * *

11-122 Districts established

* * *

Establishment of the Special Hunts Point District

In order to carry out the special purposes of this Resolution as set forth in Article X, Chapter 8, the #Special Hunts Point District# is hereby established.

Establishment of the Special Inwood District

In order to carry out the special purposes of this Resolution as set forth in Article XIV, Chapter 2, the #Special Inwood District# is hereby established.

Establishment of Special Limited Commercial District

In order to carry out the special purposes of this Resolution as set forth in Article VIII, Chapter 3, the #Special Limited Commercial District# is hereby established.

* * *

Chapter 2 - Construction of Language and Definitions

* * *

12-10 DEFINITIONS

* * *

Special Hunts Point District

The "Special Hunts Point District" is a Special Purpose District designated by the letters "HP" in which special regulations set forth in Article X, Chapter 8, apply.

Special Inwood District

The "Special Inwood District" is a Special Purpose District designated by the letters "IN" in which special regulations set forth in Article XIV, Chapter 2, apply.

Special Limited Commercial District

The "Special Limited Commercial District" is a Special Purpose District designated by the letters "LC" in which special regulations set forth in Article VIII, Chapter 3, apply.

* * *

Chapter 4 - Sidewalk Cafe Regulations

* * *

14-44 Special Zoning Districts Where Certain Sidewalk Cafes Are Permitted

* * *

Manhattan	#Enclosed Sidewalk Cafe#	#Unenclosed Sidewalk Cafe#
Hudson Square District	Yes	Yes
<u>Inwood District</u>	<u>No</u>	<u>Yes</u>
Limited Commercial District	No	No ¹

* * *

ARTICLE II - RESIDENCE DISTRICT REGULATIONS

Chapter 3 - Residential Bulk Regulations in Residence Districts

23-00 APPLICABILITY AND GENERAL PURPOSES

23-01 Applicability of This Chapter

* * *

Special regulations applying to #large-scale residential developments# or #residential uses# in #large-scale community facility developments# are set forth in Article VII, Chapter 8.

Special regulations applying only in Special Purpose Districts are set forth in Articles VIII, IX, X, XI, XII and XIII and XIV.

* * *

**23-011
Quality Housing Program**

* * *

(c) In the districts indicated without a letter suffix, the optional Quality Housing #bulk# regulations permitted as an alternative, pursuant to paragraph (b) of this Section, shall not apply to:

* * *

(2) Special Purpose Districts

However, such optional Quality Housing #bulk# regulations are permitted as an alternative to apply in the following Special Purpose Districts:

* * *

#Special Grand Concourse Preservation District#;
#Special Inwood District#;
#Special Harlem River Waterfront District#;

* * *

Chapter 4 - Bulk Regulations for Community Facilities in Residence Districts

**24-00
APPLICABILITY, GENERAL PURPOSES AND DEFINITIONS**

**24-01
Applicability of This Chapter**

* * *

Special regulations applying to #large-scale community facility developments# or to #community facility uses# in #large-scale residential developments# are set forth in Article VII, Chapter 8.

Special regulations applying only in Special Purpose Districts are set forth in Articles VIII, IX, X, XI, XII and XIII and XIV.

* * *

ARTICLE III - COMMERCIAL DISTRICT REGULATIONS

Chapter 3 - Bulk Regulations for Commercial or Community Facility Buildings in Commercial Districts

**33-00
APPLICABILITY, GENERAL PURPOSES AND DEFINITIONS**

**33-01
Applicability of This Chapter**

* * *

Special regulations applying to #large-scale residential developments#, #community facility uses# in #large-scale residential developments# or #large-scale community facility developments# are set forth in Article VII, Chapter 8.

Special regulations applying only in Special Purpose Districts are set forth in Articles VIII, IX, X, XI, XII, and XIII and XIV.

* * *

Chapter 4 - Bulk Regulations for Residential Buildings in Commercial Districts

**34-00
APPLICABILITY AND DEFINITIONS**

**34-01
Applicability of This Chapter**

* * *

Existing #buildings or other structures# that do not comply with one or more of the applicable #bulk# regulations are #noncomplying buildings or other structures# and are subject to the regulations set forth in Article V, Chapter 4.

Special regulations applying only in Special Purpose Districts are set forth in Articles VIII, IX, X, XI, XII, and XIII and XIV.

* * *

Chapter 5 - Bulk Regulations for Mixed Buildings in Commercial Districts

**35-00
APPLICABILITY AND DEFINITIONS**

**35-01
Applicability of This Chapter**

* * *

Existing #buildings or other structures# that do not comply with one or more of the applicable #bulk# regulations are #noncomplying buildings or other structures# and are subject to the regulations set forth in Article V, Chapter 4.

Special regulations applying only in Special Purpose Districts are set forth in Articles VIII, IX, X, XI, XII, and XIII and XIV.

* * *

Chapter 7 - Special Urban Design Regulations

**37-00
GENERAL PURPOSES**

Special urban design regulations are set forth in this Chapter to improve the quality of the streetscape and to promote a lively and engaging pedestrian experience along commercial streets in various neighborhoods.

The provisions of this Chapter shall apply as follows:

* * *

(c) Section 37-30, inclusive, sets forth special streetscape provisions that apply in conjunction with provisions specified in the supplemental use provisions of Article III, Chapter 2, special provisions for certain areas in Article VI, or in Special Purpose Districts in Articles VIII through XIII and XIV;

* * *

**ARTICLE IV - MANUFACTURING DISTRICT REGULATIONS
Chapter 3 - Bulk Regulations**

**43-00
APPLICABILITY AND GENERAL PROVISIONS**

**43-01
Applicability of This Chapter**

* * *

Special regulations applying to #large-scale community facility developments# are set forth in Article VII, Chapter 8.

Special regulations applying only in Special Purpose Districts are set forth in Articles VIII, IX, X, XI, XII, and XIII and XIV.

* * *

ARTICLE VI - SPECIAL REGULATIONS APPLICABLE TO CERTAIN AREAS

Chapter 2 - Special Regulations Applying in the Waterfront Area

* * *

**62-10
GENERAL PROVISIONS**

* * *

**62-13
Applicability of District Regulations**

* * *

The regulations of this Chapter shall apply in the #Special St. George District# + following Special Purpose Districts except as specifically modified within the North Waterfront Subdistrict Special Purpose District provisions:

#Special Inwood District#
#Special St. George District#;

* * *

**62-90
WATERFRONT ACCESS PLANS**

* * *

**62-94
Borough of Manhattan**

The following Waterfront Access Plans are hereby established within the Borough of Manhattan. All applicable provisions of Article VI, Chapter 2 remain in effect within the areas delineated by such plans, except as expressly set forth otherwise in the plans:

M-1: Inwood, in the #Special Inwood District# as set forth in Section 142-60 (Inwood Waterfront Access Plan)

* * *

ARTICLE XIV - SPECIAL PURPOSE DISTRICTS

Chapter 2 - Special Inwood District

**142-00
GENERAL PURPOSES**

The "Special Inwood District" established in this Resolution is designed to promote and protect public health, safety and general welfare. These general goals include, among others, the following specific purposes:

- (a) to create a lively and attractive built environment that will provide amenities and services for the use and enjoyment of area residents, workers and visitors;
- (b) to encourage well-designed development that complements and enhances the built character of the neighborhood;
- (c) to enhance neighborhood economic diversity by broadening the range of housing choices for residents of varied incomes;
- (d) to maintain and establish physical and visual public access to and along the waterfront;
- (e) to promote the pedestrian orientation of ground floor uses in appropriate locations, and thus safeguard a traditional quality of higher density areas of the City;
- (f) to take advantage of the waterfront along the Harlem River, Sherman Creek, and the North Cove and create a public open space network;
- (g) to focus higher-density development in appropriate locations along wide, mixed-use corridors with good access to transit;
- (h) to provide flexibility of architectural design within limits established to assure adequate access of light and air to streets and public access areas, and thus encourage more attractive and economic building forms; and
- (i) to promote the most desirable use of land and development in accordance with the District Plan for the Inwood waterfront, and thus conserve and enhance the value of land and buildings, and thereby protect the City's tax revenues.

**142-01
General Provisions**

The provisions of this Chapter shall apply within the Special Inwood District. The regulations of all other Chapters of this Resolution are applicable, except as superseded, supplemented or modified by the provisions of this Chapter. In the event of a conflict between the provisions of this Chapter and other regulations of this Resolution, the provisions of this Chapter shall control. However, in flood zones, in the event of a conflict between the provisions of this Chapter and the provisions of Article VI, Chapter 4 (Special Regulations Applying in Flood Hazard Areas), the provisions of Article VI, Chapter 4, shall control.

**142-02
District Plan and Maps**

The regulations of this Chapter are designed to implement the Special Inwood District Plan. The District Plan, including Map 1 (Subdistricts and Subareas) and Map 2 (Ground Floor Use and Curb Cut Regulations), is set forth in the Appendix to this Chapter and is hereby incorporated as part of this Resolution for the purpose of specifying locations where the special regulations and requirements set forth in this Chapter apply. In order to carry out the purposes and provisions of this Chapter, district maps are located in the Appendix to this Chapter and are hereby incorporated and made an integral part of this Resolution. They are incorporated for the purpose of specifying locations where special regulations and requirements, as set forth in the text of this Chapter, apply.

- Map 1. Special Inwood District - Subdistricts and Subareas
- Map 2. Special Inwood District - Ground Floor Use and Curb Cut Regulations
- Map 3. Waterfront Access Plan: Parcel Designation
- Map 4. Waterfront Access Plan: Public Access Areas
- Map 5. Waterfront Access Plan: Visual Corridors

**142-03
Subdistricts and Subareas**

In order to carry out the provisions of this Chapter, five subdistricts are established, as follows:

- Sherman Creek Subdistrict A
- Tip of Manhattan Subdistrict B
- Commercial "U" Subdistrict C
- Upland Area Subdistrict D
- Infrastructure Zone Subdistrict E

In each of these subdistricts, certain special regulations apply which do not apply within the remainder of the Special Inwood District. Within certain subdistricts, subareas are established, as follows:

- Within Sherman Creek Subdistrict A:
 - Subarea A1
 - Subarea A2
 - Subarea A3

Within Tip of Manhattan Subdistrict B:

- Subarea B1
- Subarea B2
- Subarea B3
- Subarea B4

The location and boundaries of subdistricts and subareas are outlined on Map 1 (Special Inwood District - Subdistricts and Subareas) in the Appendix to this Chapter.

**142-04
Applicability**

**142-041
Applicability of the Quality Housing Program**

In the Special Inwood District, any buildings containing residences, or any building containing long-term care facilities or philanthropic or non-profit institutions with sleeping accommodations, shall be developed or enlarged in accordance with the Quality Housing Program and the regulations of Article II, Chapter 8 shall apply. The bulk regulations of this Chapter shall be considered the applicable bulk regulations for Quality Housing buildings.

**142-042
Applicability of the Inclusionary Housing Program**

For the purposes of applying the Inclusionary Housing Program provisions set forth in Section 23-154 and 23-90, Mandatory Inclusionary Housing areas within the Special Inwood District are shown in APPENDIX F of this Resolution.

**142-05
Modification of Use and Bulk Regulations for Zoning Lots Fronting on Former West 208th Street**

Where the lot line of a zoning lot coincides with the former boundary of West 208th Street, as shown on Map 1 in the Appendix to this Chapter, such lot line shall be considered a street line for the purpose of applying all use and bulk regulations of this Resolution.

**142-06
Development over a Street in Subarea A1**

In Subarea A1, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, when a volume above a street, or portion thereof, has been eliminated, discontinued or closed, such volume may, at the option of an owner of a zoning lot adjoining such volume, be considered part of the adjoining zoning lot, and a development or enlargement may be located within such volume that is part of or connected to a building on the adjoining zoning lot utilizing floor area generated by the adjoining zoning lot, provided that the street below the volume is provided with lighting in accordance with Department of Transportation standards. In no event shall such volume contribute to the amount of lot area of any zoning lot for the purposes of generating floor area.

**142-07
Shoreline boundary**

For the purposes of this Chapter, the shoreline shall be as shown on a survey available on the Department of City Planning website

**142-10
SPECIAL USE REGULATIONS**

The underlying use regulations are modified by the provisions of this Section, inclusive.

**142-11
Permitted Uses**

Physical culture or health establishments shall be permitted as-of-right in C2-4, C4-4D, C4-5D, C6-2, M1-4 and M1-5 Districts. For the purposes of applying the underlying regulations to such use, a physical culture or health establishment shall be considered a Use Group 9 use and shall be within parking requirement category B.

In Subarea B1, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, commercial or public utility vehicle storage, open or enclosed, including accessory motor fuel pumps, as listed in Use Group 16C, shall be a permitted use.

In Subareas B2 and B3, as shown on Map 1, all uses listed in Use Groups 3 and 4 shall be permitted uses, and Use Group 6A food stores, including supermarkets, grocery stores, or delicatessen stores, shall not be limited to floor area per establishment.

**142-112
Special provisions for transient hotels**

The development or enlargement of a building containing a transient hotel, as listed in Section 32-14 (Use Group 5), or the

#conversion# or change of #use# within an existing #building# to a #transient hotel#, shall only be allowed in C2 Districts, subject to the locational criteria set forth in the double-asterisked footnote of Use Group 5 in Section 32-14, and in C4, C6 or M1 Districts:

- (a) upon certification by the Chairperson of the City Planning Commission to the Commissioner of Buildings that the residential development goal, as set forth in this Section, has been met, or
- (b) where such residential development goal has not been met, by special permit by the City Planning Commission. To permit such a #transient hotel#, the Commission shall find that:
 - (1) sufficient sites are available in the area to meet the residential development goal; or
 - (2) a harmonious mix of #residential# and non-#residential# uses has been established in the area, and the #transient hotel# is consistent with the character of the surrounding area.

The Commission may prescribe additional conditions and safeguards to minimize adverse effects on the character of the surrounding area.

For the purpose of applying the provisions of this Section, the residential development goal shall be met when at least 3,860 #dwelling units# within the #Special Inwood District# have received temporary or final certificates of occupancy subsequent to [date of adoption].

142-113 Regulations for manufacturing uses in Subareas B2 and B3

In Subareas B2 and B3, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, the #manufacturing uses# permitted in M1 Districts shall be subject to the modifications set forth in Section 123-22 (Modification of Use Groups 16, 17 and 18), inclusive.

142-12 Location of Uses

In C2 Districts mapped within R7 or R8 Districts, for #buildings# constructed after [date of adoption], the underlying provisions of Section 32-421 (Limitation on floors occupied by commercial uses) shall be modified to permit #commercial uses# listed in Use Groups 6, 7, 8, 9 or 14 on the second #story# of a #building# occupied on one or more of its upper #stories# by #residential uses# or by #community facility uses#, and provided no #commercial uses# are located directly over any #dwelling units#.

In C4 or C6 Districts, the underlying provisions of Section 32-422 (Location of floors occupied by commercial uses) shall be modified for #mixed buildings# to permit #dwelling units# on the same #story# as a #commercial use# provided no access exists between such #uses# at any level containing #dwelling units#, and provided no #commercial uses# are located directly over any #dwelling units#. However, such #commercial uses# may be located over #dwelling units# by authorization of the City Planning Commission upon a finding that sufficient separation of #residential uses# from #commercial uses# exists within the #building#.

In Subareas A1, B2 and B3, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, no #uses# listed in Use Group 6A, 6C or 10A shall be permitted above the ground floor level.

142-13 Enclosure Requirements in Subdistrict E

In Subdistrict E, #commercial# and #manufacturing# activities and storage #uses# shall not be subject to the provisions of Section 42-41 (Enclosure of Commercial and Manufacturing Activities) or Section 42-42 (Enclosure or Screening of Storage).

142-14 Ground Floor Level Requirements

For the purposes of applying the special #ground floor level# streetscape provisions set forth in Section 37-30 to this Chapter, any portion of a #ground floor level street# frontage along #streets# designated on Map 2 (Ground Floor Use and Curb Cut Regulations) in the Appendix to this Chapter shall be considered #primary street frontages#, and shall consist of Type 1 and Type 2 #primary street frontages#. A #ground floor level street# frontage along any other #street# shall be considered a #secondary street frontage#. For the purposes of this Section, defined terms shall include those in Sections 12-10 and 37-311.

The provisions of this Section shall apply to #developments# or #ground floor level enlargements#.

- (a) Along #primary street frontages#
 - (1) Type 1 #primary street frontages#

For #buildings#, or portions thereof, with Type 1 #primary

street frontage#, #uses# on the #ground floor level#, to the minimum depth set forth in Section 37-32 (Ground Floor Depth Requirements for Certain Uses), shall be limited to non-#residential uses#, except for Type 1 lobbies and entrances and exits to #accessory# parking spaces provided in accordance with the applicable provisions of Section 37-33 (Maximum Width of Certain Uses). Group parking facilities located on the #ground floor level# shall be wrapped by #floor area# in accordance with the provisions of paragraph (a) of Section 37-35 (Parking Wrap and Screening Requirements). #Ground floor level street walls# shall be glazed in accordance with the provisions set forth in Section 37-34 (Minimum Transparency Requirements), except that in M1 Districts in Subdistrict B, where the #ground floor level# is occupied by #uses# in Use Groups 16, 17 or 18, up to 50 percent of the #ground floor level street wall# width may be exempt from such regulations.

- (2) Type 2 #primary street frontages#

For #buildings#, or portions thereof, with Type 2 #primary street frontage#, all #uses# permitted by the underlying district shall be permitted on the #ground floor level#, provided that group parking facilities located on the #ground floor level# shall be wrapped by #floor area# in accordance with the provisions of paragraph (a) of Section 37-35.

However, in Subarea A1 or B1, as shown on Map 1, for #buildings# containing predominantly commercial or public utility vehicle storage, including #accessory# fuel pumps, as listed in Use Group 16C, the screening provisions of Paragraph (b) of Section 37-35 may be utilized as an alternative to such wrapping requirement and any transparency requirements need not apply.

- (b) Along #secondary street frontages#

For #buildings#, or portions thereof, with #secondary street frontage#, all #uses# permitted by the underlying district shall be permitted on the #ground floor level#, provided that any off-street parking spaces on the #ground floor level# shall be wrapped or screened in accordance with Section 37-35. Entrances and exits to accessory parking facilities shall be subject to the provisions of Paragraph (b) of Section 37-33.

- (c) For blank walls

In #Commercial Districts# or #Manufacturing Districts#, any #street wall# width exceeding 50 feet with no transparent elements on the #ground floor level# shall provide planting or wall treatment in accordance with the provisions of Section 142-141 (Special Streetscape Provisions for Blank Walls).

The level of the finished floor of such ground floor shall be located not higher than five feet above nor lower than five feet below the as-built level of the adjoining #street#.

In C4-5D Districts, and in C2 Districts mapped within R7D Districts, the provisions of Section 32-434 (Ground floor use in C4-5D and C6-3D Districts and in certain C2 Districts) shall not apply. In lieu thereof, the provisions of this Section shall apply.

142-141 Special Streetscape Provisions for Blank Walls

Where visual mitigation elements are required on a blank wall along the #ground floor level street wall#, pursuant to the provisions of Section 142-14 (Ground Floor Level Requirements), at least 75 percent of the linear footage of any such blank wall shall be treated by any of the following visual mitigation elements, or both.

- (a) Planting

When planting is provided as a visual mitigation element, any combination of perennials, annuals, decorative grasses or shrubs shall be provided in planting beds, raised planting beds or planter boxes in front of the #street wall#. Each foot in width of a planting bed, raised planting bed or planter box, as measured parallel to the #street wall#, shall satisfy one linear foot of frontage mitigation requirement. Such planting bed shall extend to a depth of at least three feet, inclusive of any structure containing the planted material. Any individual planted area shall have a width of at least five feet, and the height of such planting, inclusive of any structure containing the planted materials, shall be at least three feet.

At least 25 percent of such #street wall# width shall be planted in accordance with the provisions of this paragraph.

- (b) Wall treatment

When a wall treatment is provided as a visual mitigation element, permitted signs, graphic or sculptural art, rustication, decorative screening or latticework, or living plant material, shall be provided along the #street wall#. Each linear foot of wall treatment shall constitute one linear foot of frontage mitigation

requirement. Such wall treatment shall extend to a height of at least 10 feet, as measured from the level of the adjoining sidewalk or grade, and have a minimum width of 10 feet, as measured parallel to the #street wall#.

142-20 SPECIAL FLOOR AREA REGULATIONS

The underlying #floor area# regulations are modified by the provisions of this Section, inclusive.

142-21 Floor Area Regulations on Waterfront Blocks

On #waterfront blocks#, the provisions of Section 62-31 (Bulk Computations on Waterfront Zoning Lots) shall be modified so that #lot area# that is seaward of the #shoreline# shall not be included for the purpose of determining allowable #floor area# or to satisfy any other #bulk# regulation.

142-22 Floor Area Regulations in Subareas A2, A3 and B1

In Subareas A2, A3 and B1, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, the #floor area# regulations shall be modified as follows:

For #zoning lots# without a #shoreline#, or for #zoning lots# with a #shoreline# length of 100 feet or less, the maximum #residential floor area ratio# shall be 4.6. For #zoning lots# with a #shoreline# length of more than 100 feet, the maximum #residential floor area ratio# shall be as set forth in Paragraph (d) of Section 23-154 (Inclusionary Housing) for the particular district.

For #zoning lots# that are divided by zoning district boundary lines, #floor area# may be distributed within a #zoning lot# without regard to zoning district boundary lines. #Accessory# parking located below a height of 33 feet shall be exempt from the definition of #floor area#.

142-23 Floor Area Regulations in Subarea B2 and B3

In Subarea B2, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, all permitted #uses# shall have a permitted #floor area ratio# of 2.0. In Subarea B3, as shown on Map 1, the base #floor area ratio# shall be 5.0, and may be increased only in accordance with the provisions of this Section.

The Chairperson of the City Planning Commission shall allow, by certification, a transfer of #floor area# from a #zoning lot# located in Subarea B2 to a #zoning lot# located in Subarea B3 provided that the provisions of this Section are met. For the purpose of this Section, a “granting lot” shall mean a #zoning lot# within Subarea B2 that transfers #floor area#, pursuant to this Section, and a “receiving lot” shall mean a #zoning lot# within Subarea B3 that receives additional #floor area#, pursuant to this Section.

Such certification for a transfer of #floor area# shall be subject to the following conditions:

- the maximum amount of #floor area# that may be transferred from a granting lot shall be based on a #floor area ratio# of 2.0, less the total #floor area# of all existing #buildings# on the granting lot and any previously transferred #floor area#;
- each transfer, once completed, shall irrevocably reduce the amount of #floor area# that may be #developed# or #enlarged# on the granting lot by the amount of #floor area# transferred;
- for #developments# or #enlargements#, which in the aggregate for both the granting lot and the receiving lot, involve an increase in the #floor area# of more than 20,000 square feet of the amount existing on [date of adoption], a waterfront certification, pursuant to Section 62-811 (Waterfront public access and visual corridors) has been granted; and
- prior to the issuance of a building permit, as set forth in this Section, the owners of the granting lot and the receiving lot shall submit to the Chairperson a copy of the transfer instrument legally sufficient in both form and content to effect such a transfer. Notice of the restrictions upon further #development# or #enlargement# of the granting lot and the receiving lot shall be filed by the owners of the respective lots in the Office of the Register of the City of New York (County of New York). Proof of recordation shall be submitted to the Chairperson.

Both the transfer instrument and the notices of restrictions shall specify the total amount of #floor area# transferred and shall specify, by #block# and lot and numbers, the granting lot and the receiving lot that are a party to such transfer.

An application filed with the Chairperson for certification, pursuant to this Section shall be made jointly by the owners of the granting lot and the receiving lot, and shall include site plans and zoning calculations for the granting lot and receiving lot showing the additional #floor

area# associated with the transfer, and any such other information as may be required by the Chairperson.

The Chairperson shall certify to the Department of Buildings that a #development# is in compliance with the provisions of this Section only after the transfer instrument and notice of restrictions required by this Section have been executed and recorded with proof of recordation provided to the Chairperson. Such certification shall be a precondition to the filing for or issuing of any building permit allowing more than the basic maximum #floor area ratio# for such #development#.

A separate application shall be filed for each transfer of #floor area# to any #zoning lot#, pursuant to this Section.

142-30 SPECIAL YARD REGULATIONS

The underlying #yard# regulations are modified by the provisions of this Section.

In Subareas A1 and B3, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, no #rear yard equivalents# are required for #through lots# or #through lot# portions of a #zoning lot#.

In Subdistrict D, no #rear yard# is required along any portion of a #rear lot line# that is coincident with a #lot line# of the rail yard for the Metropolitan Transportation Authority located east of Tenth Avenue between West 207th Street and West 215th Street.

A #waterfront yard#, as defined in Section 62-11 (Definitions), shall be provided on any portion of a #zoning lot#, located within 40 feet of the #shoreline#. Any other #yard# regulations shall be inapplicable within such portion of a #zoning lot#.

142-40 SPECIAL HEIGHT AND SETBACK REGULATIONS

In Subareas A1, B2 and in Subdistrict E, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, the height and setback regulations of the underlying districts shall apply.

In Subareas A2, A3, B1, B3 and B4, the height and setback regulations of Sections 142-41 through 142-47 shall apply, and all heights shall be measured from the #base plane#.

In Subdistricts C and D, the height and setback regulations of the underlying districts are modified by Sections 142-48 (Special Regulations for Certain Sites in Subdistrict C) and 142-49 (Height and Setback for Certain Sites in Subdistricts C and D), as applicable.

142-41 Permitted Obstructions in Subareas A2, A3, B1, B3 and B4

In Subareas A2, A3, B1, B3 and B4, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, the provisions of Section 33-42 (Permitted Obstructions) shall apply to all #buildings#. In addition, along all #street# frontages, dormers may penetrate a maximum base height in accordance with the provisions of Paragraph (c)(1) of Section 23-621 (Permitted obstructions in certain districts), and balconies shall be permitted in conjunction with #residential uses# as set forth in Section 23-132 (Balconies in R6 through R10 Districts).

142-42 Height and Setback for Zoning Lots in Subareas A2, A3 and B1 With 100 Feet or Less of Shoreline

In Subareas A2, A3 and B1, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, for #zoning lots# that do not have a #shoreline# or that have a #shoreline# with a length of 100 feet or less, the height and setback regulations for R7A Districts set forth in Sections 23-662 (Maximum height of buildings and setback regulations) and 23-664 (Modified height and setback regulations for certain Inclusionary Housing buildings or affordable independent residences for seniors), as applicable, shall apply.

The #street wall# location requirements of Paragraph (b) of Section 35-651 shall apply to #street# frontages along and within 50 feet of Ninth Avenue, and the #street wall# requirements of Paragraphs (a)(1) and (2) of Section 35-651 shall apply along all other #street# frontages of the #zoning lot#. The #street wall# articulation provisions of Paragraph (e) of Section 35-651 shall apply along all #street# frontages.

142-43 Height and Setback for Zoning Lots in Subarea A2 With More Than 100 Feet of Shoreline

In Subarea A2, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, for #zoning lots# that have a #shoreline# with a length of more than 100 feet, the following height and setback regulations shall apply:

(a) #Street wall# location

The #street wall# location requirements of paragraph (b) of Section 35-651 shall apply to #street# frontages along and within 50 feet of Ninth Avenue, and the #street wall# requirements of Paragraphs (a)(1) and (2) of Section 35-651 shall apply along all other #street# frontages of the #zoning lot#. For the purposes of applying such regulations, all #street walls# shall extend to at least the minimum base height set forth in Paragraph (b) of this Section, or the height of the #building#, whichever is less. The #street wall# articulation provisions of Paragraph (e) of Section 35-651 shall apply along all #street# frontages.

(b) Base height and setbacks

The minimum base height shall be 60 feet on all #street# frontages. Within R9A Districts, or C1 or C2 Districts mapped within R9A Districts, the maximum base height shall be 105 feet. Within R8 Districts, or C1 or C2 Districts mapped within R8 Districts, the maximum base height before setback shall be 105 feet if the #building's# maximum overall height does not exceed 155 feet, or 85 feet if a #building# is developed with a tower in accordance with the regulations of Paragraph (e) of this Section.

At a height not lower than the minimum base height nor higher than the maximum base height specified for the applicable district, a setback with a minimum depth of 10 feet shall be provided from the #street wall# of the base. The provisions of Paragraphs (c)(2) through (c)(4) of Section 23-662 (Maximum height of buildings and setback regulations) shall apply to such setbacks.

(c) Within 70 feet of the #shoreline#

Within 70 feet of the #shoreline#, the height of a #building# along 30 percent of the length of a #zoning lot#, as measured parallel to Ninth Avenue, shall be limited to a maximum height of 30 feet, and the height along the remaining 70 percent may rise to a maximum height of 85 feet.

(d) Maximum #building# height

The maximum #building# height shall be 155 feet, except where towers are provided in accordance with Paragraph (e) of this Section.

(e) Optional tower regulations

For #zoning lots# that have a #lot area# of more than one acre, a "tower" shall be permitted above a height of 125 feet, provided that:

- (1) the gross area of any #story# shall not exceed 9,000 square feet, except that any dormers provided within the setback area shall not be included in such gross area;
- (2) the gross area of any #story# above 205 feet shall not exceed 90 percent of the gross area of the highest #story# that is located entirely below a height of 205 feet;
- (3) no portion of such tower shall be located within 80 feet of the #shoreline#;
- (4) the width of such tower shall not exceed 100 feet, as measured parallel to Ninth Avenue. Such width shall be measured in plan and shall include the total width of the combined #lot coverage# of all #stories# above 125 feet; and
- (5) The maximum height of such tower shall not exceed 245 feet.

#Zoning lots# with a #lot area# in excess of 1.5 acres may contain a second tower, provided that the heights of the two towers differ by at least 50 feet from each other, and provided that the combined width of the towers does not exceed 140 feet, as measured parallel to Ninth Avenue. Such width shall be measured in plan and shall include the total width of the combined #lot coverage# of all #stories# above 125 feet.

142-44

Height and Setback for Zoning Lots in Subarea A3 With More Than 100 Feet of Shoreline

In Subarea A3, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, for #zoning lots# that have a #shoreline# with a length of more than 100 feet, the height and setback regulations of this Section shall apply:

(a) Base along West 207th Street and Ninth Avenue

Along the West 207th Street and Ninth Avenue frontages, all #buildings# shall have a minimum base height of 60 feet, or the height of the #building#, whichever is less, and a maximum base height of 105 feet. The #street wall# location requirements of Paragraph (a)(1) and (2) of Section 35-651 shall apply along both #streets#. The boundary of any easement required for a #street# or sidewalk widening, pursuant to Section 142-64 shall be considered the #street line# for the purpose of this Section.

At a height not lower than the minimum base height nor higher than the maximum base height, a setback with a minimum depth of 10 feet shall be provided from the #street wall# of the base. The provisions of Paragraphs (c)(2) through (c)(4) of Section 23-662 (Maximum height of buildings and setback regulations) shall apply to such setbacks.

(b) Within 70 feet of the #shoreline#

Within 70 feet of the #shoreline#, the maximum #building# height shall be 85 feet.

(c) Within 30 feet of former West 208th Street

Within 30 feet of Former West 208th Street, as shown on Map 1 in the Appendix to this Chapter, the height of a #building# along 30 percent of the length of a #zoning lot#, as measured along the former extent of West 208th Street, shall not exceed 30 feet, and the height of the remaining 70 percent may rise to a maximum height of 85 feet.

(d) Maximum #building# height

Within the portion of the #zoning lot# that is beyond 100 feet of West 207th Street, the maximum #building# height shall be limited to 145 feet. Within the portion of the #zoning lot# that is within 100 feet of West 207th Street, the maximum #building# height shall be 175 feet, except where towers are provided in accordance with Paragraph (e) of this Section.

(e) Optional tower regulations

For #zoning lots# that have a #lot area# of more than one acre, a "tower" shall be permitted above a height of 175 feet, provided that:

- (1) the gross area of any #story# shall not exceed 10,000 square feet, except that any dormers provided within the setback area shall not be included in such gross area;
- (2) the gross area of any #story# above 255 feet shall not exceed 90 percent of the gross area of the highest #story# that is located entirely below a height of 255 feet; and
- (3) The maximum height of such tower shall not exceed 295 feet.

142-45

Height and Setback for Zoning Lots in Subarea B1 With More Than 100 Feet of Shoreline

In Subarea B1, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, for #zoning lots# that have a #shoreline# with a length of more than 100 feet, the height and setback regulations of Section 142-43 (Height and Setback for Sites in Subarea A2 With More Than 100 Feet of Shoreline) shall apply, except that Paragraph (e) of such Section shall be modified to allow the gross area of any #story# in a tower to be up to 10,000 square feet and to rise to a height of 265 feet, provided that the gross area of any #story# above 225 feet shall not exceed 90 percent of the gross area of the highest #story# that is located entirely below 225 feet. All #visual corridors# established by Section 142-60 (INWOOD WATERFRONT ACCESS PLAN) shall be treated as a #street line# for the purposes of applying all height and setback regulations.

142-46

Height and Setback in Subarea B3

In Subarea B3, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, the maximum #building# height shall be 125 feet within 10 feet of a #street line#. Beyond 10 feet of a #street line#, the maximum #building# height shall be 265 feet.

142-47

Height and Setback in Subarea B4

In Subarea B4, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, the height of a #building# within 10 feet of a #street line# shall not exceed 125 feet. Portions of #buildings# located beyond 10 feet of a #street line# may rise to a maximum height of 210 feet. Any #development# or #enlargement# with frontage on West 218th Street must provide a sidewalk widening with a minimum depth of five feet along such frontage. The boundary of such sidewalk widening shall be considered the #street line# for the purpose of this Section.

142-48

Special Regulations for Certain Sites in Subdistrict C

In Subdistrict C, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, for #zoning lots# which share a #side lot line# with an adjacent #zoning lot# that is #developed# with a #building# constructed prior to December 15, 1961 that contains #residences# with #legally required windows# facing and located within 15 feet of the shared #side lot line#, the underlying height and setback provisions shall be modified by the provisions of this Section.

The #street wall# location provisions of Paragraph (b)(1) of Section 35-651 shall apply except that where an adjoining #zoning lot# contains #residences# with #legally required windows# facing and within 15 feet of a shared #side lot line#, the #street wall# of a #building# need not extend along the entire #street# frontage of such a #zoning lot# if an open area is provided above the level of the first #story# or a height of 15 feet, whichever is lower, along the entire shared #side lot line#. Where such an open area is provided, the #street# frontage of such open area may be excluded for the purpose of applying the #street wall# location provisions of Paragraph (b)(2) of Section 35-651.

In addition, where an open area with a depth of at least 15 feet, as measured perpendicular from the shared #side lot line#, and is provided in the form of a recess, #court# or other open area is provided along shared #side lot line#, and such open area is provided adjacent to all portions of a #building# on an adjoining #zoning lot# that contain #legally required windows# facing and located within 15 feet of the shared #side lot line#, the maximum height for the #building# set forth in Section 23-662, 23-664, 35-652 or 35-654, as applicable, may be increased by 10 feet; and the maximum number of #stories#, if applicable, may be increased by one.

#Zoning lots# may apply the regulations of this Section along multiple #side lot lines# where applicable, but in no case shall the permitted #building# height be increased by more than one #story# or 10 feet, whichever is lower.

142-49 Height and Setback for Certain Zoning Lots in Subdistricts C and D

In Subdistrict D, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, for portions of #zoning lots# that are located within 30 feet of West 201st Street, the underlying height and setback regulations of Section 23-66 (Height and Setback Requirements for Quality Housing Buildings) shall be modified to limit maximum #building# height to 85 feet.

In Subdistricts C and D, for portions of #zoning lots# located within 100 feet of a #street# that contains an elevated rail line, the underlying height and setback regulations shall be modified as follows:

- the minimum required base height shall be 25 feet;
- the maximum permitted #building# height shall be 165 feet and the maximum number of #stories# shall be 16; and
- along the frontage of a #street# that contains an elevated rail line, the #street wall# location regulations of paragraph (a)(1) of Section 35-651 shall apply.

142-50 SPECIAL OFF-STREET PARKING AND LOADING REGULATIONS

The underlying off-street parking and loading regulations are modified by the provisions of this Section, inclusive.

142-51 Required Accessory Parking Spaces for Residences

The requirements of Sections 25-23 (Requirements Where Group Parking Facilities Are Provided) are modified to require #accessory residential# off-street parking spaces for a minimum of 20 percent of new #residences#. The number of #accessory# off-street parking spaces required may be reduced or waived as set forth in the underlying district regulations.

142-52 Required Accessory Parking Spaces for Commercial or Community Facility Uses in Certain Districts

No #accessory# parking is required for new #commercial# or #community facility uses# in #mixed buildings# in C2-4, C4-4D, or C4-5D Districts.

142-53 Public Use of Accessory Parking

All required or permitted #accessory# off-street parking spaces may be made available for public use. However, any such space shall be made available to the occupant of a #residence# to which it is #accessory# within 30 days after written request for such space is made to the landlord.

142-54 Accessory Parking on a Roof in Subarea A1

In Subarea A1, the underlying off-street parking regulations of Section 44-11 (General Provisions) are modified to permit #accessory# parking to be located on the roof of any #story# of a #building#.

142-55 Curb Cuts

For #zoning lots# with frontage along both a #street# specified as a Type 1 or Type 2 primary street on Map 2 (Ground Floor Use and Curb Cut Regulations) in the Appendix to this Chapter, and along a frontage that is not specified on Map 2, no curb cuts accessing off-street parking facilities or loading berths shall be permitted for along the primary

street frontage.

142-60 INWOOD WATERFRONT ACCESS PLAN

The provisions of Article VI, Chapter 2, (Special Regulations Applying in the Waterfront Area), shall apply, except as superseded, supplemented or modified by the provisions of this Section, inclusive.

Map 3 (Waterfront Access Plan: Parcel Designation), Map 4 (Waterfront Access Plan: Public Access Areas), and Map 5 (Waterfront Access Plan: Visual Corridors) in the Appendix to this Chapter show the boundaries of the area comprising the Inwood Waterfront Access Plan, boundaries of parcels within the Plan, and the location of certain features mandated or permitted by the Plan.

The Plan has been divided into parcels consisting of tax blocks and lots and other lands as established on [date of adoption], as follows:

- Parcel 1: block 2215, lots 877 and 885; and block 2197, lots 67, 71, 74 and 174
- Parcel 2/3: block 2197, lot 47 and 75
- Parcel 4: block 2188, lot 1
- Parcel 5: block 2187, lots 1, 5, 7 and 20
- Parcel 6: block 2185, lots 25, 36 and 51
- Parcel 7: block 2185, lots 1 and 10
- Parcel 8: block 2184, lots 20 and 40

Within the #Special Inwood District#, the parcels of land designated in this Section need not be contiguous for the area to be considered to be a Waterfront Access Plan, pursuant to Section 62-911.

For the purposes of this Section, inclusive, defined terms shall include those listed in Section 12-10 (DEFINITIONS) and Section 62-11 (Definitions).

142-61 Lot area and waterfront public access area requirements

For the purposes of determining requirements for #waterfront public access areas#, #lot area# shall not include any portion of a #zoning# lot that is seaward of the #shoreline. For the purposes of determining the applicability of #waterfront public access area# requirements, pursuant to Section 62-52, all #zoning lots# with portions located within 40 feet of the #shoreline# shall be considered #waterfront zoning lots#.

On Parcel 1, as shown on Map 3 (Waterfront Access Plan: Parcel Designation) in the Appendix to this Chapter, for the purposes of calculating the total #waterfront public access area# requirements on a "granting lot," as described in Section 142-23 (Floor Regulations in Subarea B2 and B3), #lot area# shall be the combined #lot area# of all "granting lots" and all "receiving lots."

142-62 Tip of Manhattan, Subdistrict B

In Tip of Manhattan Subdistrict B, for Parcels 1, 2 & 3, as shown on Map 3 (Waterfront Access Plan: Parcel Designation) in the Appendix to this Chapter, the following regulations shall apply.

- Applicability of #waterfront public access area requirements# to Use Group 16

In Subarea B1, as shown on Map 1, #developments# of #buildings# containing exclusively commercial or public utility vehicle storage, including #accessory# fuel pumps, as listed in Use Group 16C, shall be exempted from #waterfront public access area# requirements#.
- #Shore public walkways#
 - the minimum width of a #shore public walkway# set forth in Section 62-53 (Shore Public Walkways) shall be reduced to 20 feet;
 - the minimum width of the screening buffer shall be five feet;
 - on Parcel 1, no #shore public walkway# shall be required.
- #Upland connections#

On Parcel 2/3, #upland connections# shall be provided along the shared boundary between Parcels 1 and Parcel 2/3, and within 100 feet south of the prolongation of the southerly #street line# of West 219th Street.
- #Supplemental public access areas#
 - on Parcel 1, #supplemental public access area# shall be bounded by Ninth Avenue to the west, the shared boundary of Parcels 1 and 2 to the south, and the stabilized shore to the east. Section 62-571 (Location and area requirements for supplemental public access areas) shall not apply to such #supplemental public access area#;
 - on Parcel 2/3, #supplemental public access area# shall be located at the intersection of the #upland connection# and the #shore public walkway#. Section 62-571 shall be modified to allow the longest side of such #supplemental public access

area# to adjoin the #upland connection# provided that the maximum depth measured perpendicular to the #upland connection# does not exceed 1.5 times the width measured parallel to the #upland connection#.

(e) #Visual corridors#

#Visual corridors# shall be provided at three locations as shown on Map 5 (Waterfront Access Plan: Visual Corridors) in the Appendix to this Chapter:

- (1) within the prolongation of the #street lines# of West 220th Street;
(2) within the prolongation of the #street lines# of Ninth Avenue;
(3) within the area between the prolongation of the centerline of West 218th Street and a line parallel to and 50 feet north of such centerline.

142-63 Sherman Creek Subdistrict A

In the Sherman Creek Subdistrict A, Parcels 4, 5, 6, 7 and 8, as shown on Map 3 (Waterfront Access Plan: Parcel Designation) in the Appendix to this Chapter, the following regulations shall apply.

(a) #Shore public walkways#

- (1) #Waterfront zoning lots# that have a #shoreline# measuring more than 100 feet shall provide a #shore public walkway# as required by Section 62-53 (Requirements for Shore Public Walkways).
(2) #Zoning lots# within or partially within 40 feet of the #shoreline# that do not #abut# the #shoreline#, or that contain a #shoreline# measuring 100 feet or less shall provide either:
(i) a #shore public walkway#, located partly on the #zoning lot# and partly on an adjoining #waterfront zoning lot#; or
(ii) a #shore public walkway# on any portion of the #zoning lot# within 40 feet of the #shoreline#.

Where the #zoning lot# does not include the #shoreline#, the design of the #shore public walkway# shall be compatible with the future improvement of public access areas on the land between the #zoning lot# and the #shoreline#.

- (3) The primary circulation path required, pursuant to Section 62-62 shall be provided at a minimum elevation of 7.5 feet above the #shoreline#, except that such requirement need not include portions of a circulation path that slope downward to meet the elevation of an existing publicly accessible sidewalk.

(b) #Supplemental public access areas#

On Parcel 4, no #supplemental public access area# shall be required.

142-64 Special Regulations on Parcel 4

- (a) Section 62-811 (Waterfront public access and visual corridors) shall not apply to Parcel 4, as shown on Map 3 (Waterfront Access Plan: Parcel Designation) in the Appendix to this Chapter. In lieu thereof, the following regulations shall apply. Required Certification

No excavation or building permit shall be issued for any #development# on Parcel 4 until the Chairperson of the City Planning Commission has certified to the Department of Buildings, that:

- (1) a site plan has been submitted showing compliance with the provisions of Sections 62-50 (GENERAL REQUIREMENTS FOR VISUAL CORRIDORS AND WATERFRONT PUBLIC ACCESS AREAS) and 62-60 (DESIGN REQUIREMENTS FOR

WATERFRONT PUBLIC ACCESS AREAS) as modified by Section 142-60 (INWOOD WATERFRONT ACCESS PLAN);

- (2) the Chairperson has certified that an easement, the requirements for which shall be determined in consultation with the Department of Transportation, has been provided to enlarge the adjoining mapped #streets#, an instrument creating such easement has been recorded in the Office of the City Register, and a certified copy of such easement has been submitted to the Department of City Planning; and
(3) an acceptable restrictive declaration is executed and filed, pursuant to Section 62-74 (Requirements for Recordation).


(b) Buildout of Adjoining #Streets#

No certificate of occupancy for any #development# on Parcel 4 shall be issued until the Department of Buildings has been furnished with a certification by the Department of Transportation that adjoining mapped #streets# have been built out to Department of Transportation standards.


Within 45 days of receipt of a complete application, the Chairperson shall either certify that the proposed #development# complies with the requirements of this Section or disapprove such application, citing the nature of any failure to comply. Failure to certify or disapprove such application within the 45 day period will release the Department of Buildings or the Department of Business Services from any obligation to withhold the excavation or building permit and authorize such agency to determine compliance with the provisions of this Section.

APPENDIX Special Inwood District Plan


Map 1. Special Inwood District – Subdistricts and Subareas




Map 2. Special Inwood District – Ground Floor Use and Curb Cut Regulations



Map 3. Waterfront Access Plan: Parcel Designation




Map 4. Waterfront Access Plan: Public Access Areas



Public Access Areas

- Parcel line
- - - - - Shore Public Walkway - 20-ft minimum required
- ==== Shore Public Walkway - 40-ft minimum required, or as modified by Section 142-63(a)
- Supplemental Public Access Area
- Upland Connection (Designated Location)
- Upland Connection (Flexible Zone)

Map 5. Waterfront Access Plan: Visual Corridors




Visual Corridors

— Parcel line
➔ Visual Corridor

**APPENDIX F
 Inclusionary Housing Designated Areas and Mandatory
 Inclusionary Housing Areas**

MANHATTAN

**Manhattan Community District 12
 Map 1 – (date of adoption)**



■ Mandatory Inclusionary Housing Program see section 23-154(d)(3)
 Area 1 - [date of adoption] MIH Program Option 1 and Option 2
 ▨ Excluded Area

Portion of Community District 12, Manhattan

No. 4

CD 12 **N 180205(A) ZRM**
IN THE MATTER OF an application submitted by the New York City
 Economic Development Corporation, pursuant to Section 201 of the
 New York City Charter, for an amendment of the Zoning Resolution of
 the City of New York establishing the Special Inwood District (Article
 XIV, Chapter 2), and modifying related Sections, including Appendix
 F, for the purpose of establishing a Mandatory Inclusionary Housing
 area.

Matter underlined is new, to be added;
 Matter ~~struck out~~ is to be deleted;
 Matter within # # is defined in Section 12-10;
 *** indicates where unchanged text appears in the Zoning Resolution

ARTICLE I - GENERAL PROVISIONS

**Chapter 1 - Title, Establishments of Controls and
 Interpretations of Regulations**

**11-122
 Districts established**

- Establishment of the Special Hunts Point District
- In order to carry out the special purposes of this Resolution as set forth in Article X, Chapter 8, the #Special Hunts Point District# is hereby established.
- Establishment of the Special Inwood District
- In order to carry out the special purposes of this Resolution as set forth in Article XIV, Chapter 2, the #Special Inwood District# is hereby established.
- Establishment of Special Limited Commercial District
- In order to carry out the special purposes of this Resolution as set forth in Article VIII, Chapter 3, the #Special Limited Commercial District# is hereby established.

* * *

Chapter 2 - Construction of Language and Definitions

* * *

**12-10
DEFINITIONS**

* * *

Special Hunts Point District

The "Special Hunts Point District" is a Special Purpose District designated by the letters "HP" in which special regulations set forth in Article X, Chapter 8, apply.

Special Inwood District

The "Special Inwood District" is a Special Purpose District designated by the letters "IN" in which special regulations set forth in Article XIV, Chapter 2, apply.

Special Limited Commercial District

The "Special Limited Commercial District" is a Special Purpose District designated by the letters "LC" in which special regulations set forth in Article VIII, Chapter 3, apply.

* * *

Chapter 4 - Sidewalk Cafe Regulations

* * *

**14-44
Special Zoning Districts Where Certain Sidewalk Cafes Are Permitted**

* * *

Manhattan	#Enclosed Sidewalk Cafe#	#Unenclosed Sidewalk Cafe#

* * *

Hudson Square District	Yes	Yes
<u>Inwood District</u>	No	Yes
Limited Commercial District	No	No ¹

* * *

ARTICLE II - RESIDENCE DISTRICT REGULATIONS

Chapter 3 - Residential Bulk Regulations in Residence Districts

**23-00
APPLICABILITY AND GENERAL PURPOSES**

**23-01
Applicability of This Chapter**

* * *

Special regulations applying to #large-scale residential developments# or #residential uses# in #large-scale community facility developments# are set forth in Article VII, Chapter 8.

Special regulations applying only in Special Purpose Districts are set forth in Articles VIII, IX, X, XI, XII and XIII and XIV.

* * *

**23-011
Quality Housing Program**

* * *

(d) In the districts indicated without a letter suffix, the optional Quality Housing #bulk# regulations permitted as an alternative, pursuant to Paragraph (b) of this Section, shall not apply to:

* * *

(3) Special Purpose Districts

However, such optional Quality Housing #bulk# regulations are permitted as an alternative to apply in the following Special Purpose Districts:

* * *

- #Special Grand Concourse Preservation District#;
- #Special Inwood District#;
- #Special Harlem River Waterfront District#;

* * *

Chapter 4 - Bulk Regulations for Community Facilities in Residence Districts

**24-00
APPLICABILITY, GENERAL PURPOSES AND DEFINITIONS**

**24-01
Applicability of This Chapter**

* * *

Special regulations applying to #large-scale community facility developments# or to #community facility uses# in #large-scale residential developments# are set forth in Article VII, Chapter 8.

Special regulations applying only in Special Purpose Districts are set forth in Articles VIII, IX, X, XI, XII and XIII and XIV.

* * *

ARTICLE III - COMMERCIAL DISTRICT REGULATIONS

Chapter 3 - Bulk Regulations for Commercial or Community Facility Buildings in Commercial Districts

**33-00
APPLICABILITY, GENERAL PURPOSES AND DEFINITIONS**

**33-01
Applicability of This Chapter**

* * *

Special regulations applying to #large-scale residential developments#, #community facility uses# in #large-scale residential developments# or #large-scale community facility developments# are set forth in Article VII, Chapter 8.

Special regulations applying only in Special Purpose Districts are set forth in Articles VIII, IX, X, XI, XII, and XIII and XIV.

* * *

Chapter 4 - Bulk Regulations for Residential Buildings in Commercial Districts

**34-00
APPLICABILITY AND DEFINITIONS**

**34-01
Applicability of This Chapter**

* * *

Existing #buildings or other structures# that do not comply with one or more of the applicable #bulk# regulations are #noncomplying buildings or other structures# and are subject to the regulations set forth in Article V, Chapter 4.

Special regulations applying only in Special Purpose Districts are set forth in Articles VIII, IX, X, XI, XII, and XIII and XIV.

* * *

Chapter 5 - Bulk Regulations for Mixed Buildings in Commercial Districts

**35-00
APPLICABILITY AND DEFINITIONS**

**35-01
Applicability of This Chapter**

* * *

Existing #buildings or other structures# that do not comply with one or more of the applicable #bulk# regulations are #noncomplying buildings or other structures# and are subject to the regulations set forth in Article V, Chapter 4.

Special regulations applying only in Special Purpose Districts are set forth in Articles VIII, IX, X, XI, XII, and XIII and XIV.

* * *

Chapter 7 - Special Urban Design Regulations

**37-00
GENERAL PURPOSES**

Special urban design regulations are set forth in this Chapter to improve the quality of the streetscape and to promote a lively and engaging pedestrian experience along commercial streets in various neighborhoods.

The provisions of this Chapter shall apply as follows:

* * *

(c) Section 37-30, inclusive, sets forth special streetscape provisions that apply in conjunction with provisions specified in the supplemental use provisions of Article III, Chapter 2, special provisions for certain areas in Article VI, or in Special Purpose Districts in Articles VIII through XIV and XIV;

* * *

ARTICLE IV - MANUFACTURING DISTRICT REGULATIONS

Chapter 3 - Bulk Regulations

**43-00
APPLICABILITY AND GENERAL PROVISIONS**

**43-01
Applicability of This Chapter**

Special regulations applying to #large-scale community facility developments# are set forth in Article VII, Chapter 8.

Special regulations applying only in Special Purpose Districts are set forth in Articles VIII, IX, X, XI, XII, and XIII and XIV.

ARTICLE VI – SPECIAL REGULATIONS APPLICABLE TO CERTAIN AREAS

Chapter 2 - Special Regulations Applying in the Waterfront Area

**62-10
GENERAL PROVISIONS**

**62-13
Applicability of District Regulations**

The regulations of this Chapter shall apply in the #Special St. George District# + following Special Purpose Districts except as specifically modified within the North Waterfront Subdistrict Special Purpose District provisions:

#Special Inwood District#

#Special St. George District#.

**62-90
WATERFRONT ACCESS PLANS**

**62-94
Borough of Manhattan**

The following Waterfront Access Plans are hereby established within the Borough of Manhattan. All applicable provisions of Article VI, Chapter 2 remain in effect within the areas delineated by such plans, except as expressly set forth otherwise in the plans:

M-1: Inwood, in the #Special Inwood District# as set forth in Section 142-60 (Inwood Waterfront Access Plan)

ARTICLE XIV – SPECIAL PURPOSE DISTRICTS

Chapter 2 - Special Inwood District

**142-00
GENERAL PURPOSES**

The "Special Inwood District" established in this Resolution is designed to promote and protect public health, safety and general welfare. These general goals include, among others, the following specific purposes:

- (j) to create a lively and attractive built environment that will provide amenities and services for the use and enjoyment of area residents, workers and visitors;
- (k) to encourage well-designed #development# that complements and enhances the built character of the neighborhood;
- (l) to enhance neighborhood economic diversity by broadening the range of housing choices for residents of varied incomes;
- (m) to maintain and establish physical and visual public access to and along the waterfront;
- (n) to promote the pedestrian orientation of ground floor uses in appropriate locations, and thus safeguard a traditional quality of higher density areas of the City;
- (o) to take advantage of the waterfront along the Harlem River, Sherman Creek, and the North Cove and create a public open space network;
- (p) to focus higher-density development in appropriate locations along wide, mixed-use corridors with good access to transit;
- (q) to provide flexibility of architectural design within limits established to assure adequate access of light and air to streets and public access areas, and thus encourage more attractive and economic building forms; and
- (r) to promote the most desirable use of land and development in accordance with the District Plan for the Inwood waterfront, and thus conserve and enhance the value of land and buildings, and thereby protect the City's tax revenues.

**142-01
General Provisions**

The provisions of this Chapter shall apply within the #Special Inwood District#. The regulations of all other Chapters of this Resolution

are applicable, except as superseded, supplemented or modified by the provisions of this Chapter. In the event of a conflict between the provisions of this Chapter and other regulations of this Resolution, the provisions of this Chapter shall control. However, in #flood zones#, in the event of a conflict between the provisions of this Chapter and the provisions of Article VI, Chapter 4 (Special Regulations Applying in Flood Hazard Areas), the provisions of Article VI, Chapter 4, shall control.

**142-02
District Plan and Maps**

The regulations of this Chapter are designed to implement the #Special Inwood District# Plan. The District Plan, including Map 1 (Special Inwood District – Subdistricts and Subareas), Map 2 (Special Inwood District – Ground Floor Use and Curb Cut Regulations) and Map 3 (Special Inwood District – Transit Easement Zones) is set forth in the Appendix to this Chapter and is hereby incorporated as part of this Resolution for the purpose of specifying locations where the special regulations and requirements set forth in this Chapter apply. In order to carry out the purposes and provisions of this Chapter, district maps are located in the Appendix to this Chapter and are hereby incorporated and made an integral part of this Resolution. They are incorporated for the purpose of specifying locations where special regulations and requirements, as set forth in the text of this Chapter, apply.

- Map 1. Special Inwood District – Subdistricts and Subareas
- Map 2. Special Inwood District – Ground Floor Use and Curb Cut Regulations
- Map 3. Special Inwood District – Transit Easement Zones
- Map 4. Waterfront Access Plan: Parcel Designation
- Map 5. Waterfront Access Plan: Public Access Areas
- Map 6. Waterfront Access Plan: Visual Corridors

**142-03
Subdistricts and Subareas**

In order to carry out the provisions of this Chapter, five subdistricts are established, as follows:

- Sherman Creek Subdistrict A
- Tip of Manhattan Subdistrict B
- Commercial "U" Subdistrict C
- Upland Area Subdistrict D
- Infrastructure Zone Subdistrict E

In each of these subdistricts, certain special regulations apply which do not apply within the remainder of the #Special Inwood District#. Within certain subdistricts, subareas are established, as follows:

- Within Sherman Creek Subdistrict A:
 - Subarea A1
 - Subarea A2
 - Subarea A3
- Within Tip of Manhattan Subdistrict B:
 - Subarea B1
 - Subarea B2
 - Subarea B3
 - Subarea B4

The location and boundaries of subdistricts and subareas are outlined on Map 1 (Special Inwood District - Subdistricts and Subareas) in the Appendix to this Chapter.

**142-04
Applicability**

**142-041
Applicability of the Quality Housing Program**

In the #Special Inwood District#, any #building# containing #residences#, or any #building# containing #long-term care facilities# or philanthropic or non-profit institutions with sleeping accommodations, shall be #developed# or #enlarged# in accordance with the Quality Housing Program and the regulations of Article II, Chapter 8 shall apply. The #bulk# regulations of this Chapter shall be considered the applicable #bulk# regulations for #Quality Housing buildings#.

**142-042
Applicability of the Inclusionary Housing Program**

For the purposes of applying the Inclusionary Housing Program provisions set forth in Section 23-154 and 23-90, #Mandatory Inclusionary Housing areas# within the #Special Inwood District# are shown in APPENDIX F of this Resolution.

**142-043
Applicability of Article XII, Chapter 3**

In M1 Districts paired with a #Residence District#, the special #use#, #bulk# and parking and loading provisions of Article XII, Chapter 3 (Special Mixed Use District) shall apply, except where modified by the provisions of this Chapter, and shall supplement or supersede the provisions of the designated #Residence# or M1 District, as applicable.

142-05

Modification of Use and Bulk Regulations for Zoning Lots Fronting on Former West 208th Street

Where the #lot line# of a #zoning lot# coincides with the former boundary of West 208th Street, as shown on Map 1 in the Appendix to this Chapter, such #lot line# shall be considered a #street line# for the purpose of applying all #use# and #bulk# regulations of this Resolution.

142-06

Development over a Street in Subarea A1

In Subarea A1, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, when a volume above a #street#, or portion thereof, has been eliminated, discontinued or closed, such volume may, at the option of an owner of a #zoning lot# adjoining such volume, be considered part of the adjoining #zoning lot#, and a #development# or #enlargement# may be located within such volume that is part of or connected to a #building# on the adjoining #zoning lot# utilizing #floor area# generated by the adjoining #zoning lot#, provided that the #street# below the volume is provided with lighting in accordance with Department of Transportation standards. In no event shall such volume contribute to the amount of #lot area# of any #zoning lot# for the purposes of generating #floor area#.

142-07

Shoreline boundary

For the purposes of this Chapter, the #shoreline# shall be as shown on a survey available on the Department of City Planning website

142-08

Off-street Relocation of Subway Station Entrances

For all #developments# or #enlargements# involving ground floor level construction on a #zoning lot# that is wholly or partially located within a Transit Easement Zone, as shown on Map 3 (Special Inwood District – Transit Easement Zones) in the Appendix to this Chapter, a transit easement volume may be required on such #zoning lot# for public access between the #street# and the adjacent above- or below-grade subway station.

(a) Transit Easement

Prior to filing any application with the Department of Buildings for an excavation permit, foundation permit, new building permit or alteration permit for a #development# or #enlargement#, the owner of the #zoning lot# shall file an application with the Metropolitan Transportation Authority (MTA) and the Chairperson of the City Planning Commission requesting a certification as to whether or not a transit easement volume is required on the #zoning lot#.

Within 60 days of receipt of such application, the MTA and the Chairperson shall jointly certify whether or not a transit easement volume is required on the #zoning lot#. Failure to certify within the 60-day period will release the owner from any obligation to provide a transit easement volume on such #zoning lot#.

When the MTA and the Chairperson indicate that a transit easement volume is required, the MTA shall, in consultation with the owner of the #zoning lot# and the Chairperson, determine the appropriate type of transit easement and reasonable dimensions for such transit easement volume.

The owner shall submit a site plan showing a proposed location of such transit easement volume that would provide access between the #street# and the adjacent subway station and be compatible with the proposed #development# or #enlargement# on the #zoning lot# for joint approval and final certification by the MTA and the Chairperson. The MTA and the Chairperson shall comment on such site plan within 45 days of its receipt and may, within such 45-day period or following its expiration, permit the granting of an excavation permit while the location and size of the transit easement volume is being finalized. Upon joint approval of a site plan by the MTA and the Chairperson, copies of such certification shall be forwarded by the Chairperson to the Department of Buildings.

Legally enforceable instruments, running with the land, creating a transit easement volume, and setting forth the obligations of either the MTA or the owner and developer, their successors and assigns, to design and construct the improvement, shall be executed and recorded in a form acceptable to the MTA and the Chairperson. The execution and recording of such instruments shall be a precondition to the issuance of any foundation permit,

new building permit, or alteration permit by the Department of Buildings allowing such #development# or #enlargement#.

(b) Construction and Maintenance

Where a transit easement volume is required, pursuant to this Section, transit access improvements within such volume shall be constructed and maintained either by the MTA or the owner of the #zoning lot# with the #development# or #enlargement#.

(1) Where such mass transit improvement is constructed and maintained by the owner of the #development# or #enlargement#:

- (i) a transit access improvement shall be provided in accordance with standards set forth by the MTA;
- (ii) such improvement shall be accessible to the public at all times, except as otherwise approved by the MTA;
- (iii) such improvement shall include #signs# to announce accessibility to the public. Such #signs# shall be exempt from the maximum #surface area# of non-illuminated signs# permitted by Section 32-642 (Non-illuminated signs); and
- (iv) no temporary certificate of occupancy shall be granted by the Department of Buildings for the #building# until the Chairperson of the City Planning Commission, acting in consultation with the MTA, has certified that the improvement is substantially complete and usable by the public.

(2) Where such mass transit improvement is constructed and maintained by the MTA:

- (i) Where the construction of the improvement is not contemporaneous with the construction of the #development# or #enlargement#, any underground walls constructed along the #front lot line# adjacent to a below-grade subway station shall include a knockout panel, not less than 12 feet wide, below #curb level# down to the bottom of the easement. The actual location and size of such knockout panel shall be determined through consultation with the MTA.
- (ii) Temporary construction access shall be granted to the MTA on portions of the #zoning lot# outside of the transit easement volume, as necessary, to enable construction within and connection to the transit easement volume.
- (iii) In the event that the MTA has approved of obstructions associated with the #development# or #enlargement# within the transit easement volume, such as building columns or footings, such construction and maintenance shall exclude any such obstructions within the transit easement volume.

(c) Additional modifications

Where a transit easement volume is required, pursuant to paragraph (a) of this Section, the Chairperson of the City Planning Commission shall certify the following modifications in conjunction with such transit easement volume certification:

- (1) the edge of the transit easement volume facing the #street# shall be considered a #street wall# for the purposes of applying the #street wall# location provisions set forth in Section 142-40 (SPECIAL HEIGHT AND SETBACK REGULATIONS), inclusive, irrespective of whether such volume is incorporated into a #building#;
- (2) for #zoning lots# adjacent to a below-grade subway station, the maximum height for the #building# set forth in Section 142-40, inclusive, shall be increased by 10 feet, and the maximum number of #stories#, if applicable, shall be increased by one, except where the provisions of Section 142-48 (Special Regulations for Certain Sites in Subdistrict C) are being utilized;
- (3) the floor space contained within any transit easement volume required, pursuant to this Section shall be excluded from the definition of #floor area#; and
- (4) the street frontage of such transit easement volume shall be excluded for the purpose of applying the provisions of Section 142-14 (Ground Floor Level Requirements).

(d) Temporary Use

Any easement volume required on a #zoning lot#, pursuant to paragraph (a) of this Section may be temporarily used for any permitted #commercial# or #community facility uses# until such time as required by the MTA for transit access improvements. The floor space allocated to such temporary #uses# within the transit easement volume shall continue to be exempt from the definition of #floor area# and shall not be included for the purpose

of calculating #accessory# off-street parking, bicycle parking, or loading berths.

Improvements or construction of a temporary nature within the easement volume for such temporary #uses# shall be removed by the owner of the #building# or portion of the #zoning lot# within which the easement volume is located prior to the time at which public #use# of the easement area is required, except as otherwise specified by the MTA. A minimum notice of six months in writing shall be given by the MTA to the owner of the #building# or portion of the #zoning lot# in order to vacate the occupants of such temporary #uses#.

(e) Termination of an easement volume

In the event that the MTA and the City Planning Commission jointly notify the Department of Buildings and the owner in writing that a transit easement volume is not required on a #zoning lot# in its final construction plans, the restrictions imposed on such #zoning lot# by the provisions of this Section shall lapse, following receipt of notification thereof by the owner, and the owner shall have the right to record an instrument reciting the consent of the MTA to the extinguishment of the easement volume.

On any #zoning lot# which has been #developed# or #enlarged# in accordance with the provisions of this Section and on which termination of transit easement has been certified, pursuant to this paragraph, any floor space in a previously required transit easement volume shall continue to be exempt from the definition of #floor area# and shall not be included for the purpose of calculating requirements for #accessory# off-street parking, bicycle parking or loading berths. However, where such previously required volume is located within a #building#, the ground floor space shall be subject to the provisions of Section 142-14.

**142-10
SPECIAL USE REGULATIONS**

The underlying #use# regulations are modified by the provisions of this Section, inclusive. In M1-4/R7A and M1-4/R9A Districts, the #use# regulations of Article XII, Chapter 3 of the #Special Mixed Use District# shall apply, except where modified by the provisions of this Section.

**142-11
Permitted Uses**

#Physical culture or health establishments# shall be permitted as-of-right in C2-4, C4-4D, C4-5D, C6-2, M1-4 and M1-5 Districts. For the purposes of applying the underlying regulations to such #use#, a #physical culture or health establishment# shall be considered a Use Group 9 #use# and shall be within parking requirement category B.

In Subarea B1, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, commercial or public utility vehicle storage, open or enclosed, including #accessory# motor fuel pumps, as listed in Use Group 16C, shall be a permitted #use#.

In Subareas B2 and B3, as shown on Map 1, all #uses# listed in Use Groups 3 and 4 shall be permitted #uses#, and Use Group 6A food stores, including supermarkets, grocery stores, or delicatessen stores, shall not be limited to #floor area# per establishment.

**142-112
Special provisions for transient hotels**

The #development# or #enlargement# of a #building# containing a #transient hotel#, as listed in Section 32-14 (Use Group 5), or the #conversion# or change of #use# within an existing #building# to a #transient hotel#, shall only be allowed in C2 Districts, subject to the locational criteria set forth in the double-asterisked footnote of Use Group 5 in Section 32-14, and in C4, C6 or M1 Districts:

- (c) upon certification by the Chairperson of the City Planning Commission to the Commissioner of Buildings that the residential development goal, as set forth in this Section, has been met, or
- (d) where such residential development goal has not been met, by special permit by the City Planning Commission. To permit such a #transient hotel#, the Commission shall find that:
 - (3) sufficient sites are available in the area to meet the residential development goal; or
 - (4) a harmonious mix of #residential# and non-#residential# uses has been established in the area, and the #transient hotel# is consistent with the character of the surrounding area.

The Commission may prescribe additional conditions and safeguards to minimize adverse effects on the character of the surrounding area.

For the purpose of applying the provisions of this Section, the residential development goal shall be met when at least 3,860

#dwelling units# within the #Special Inwood District# have received temporary or final certificates of occupancy subsequent to [date of adoption].

**142-113
Regulations for manufacturing uses in Subareas B2 and B3**

In Subareas B2 and B3, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, the #manufacturing uses# permitted in M1 Districts shall be subject to the modifications set forth in Section 123-22 (Modification of Use Groups 16, 17 and 18), inclusive.

**142-12
Location of Uses**

In C2 Districts mapped within R7 or R8 Districts, for #buildings# constructed after [date of adoption], the underlying provisions of Section 32-421 (Limitation on floors occupied by commercial uses) shall be modified to permit #commercial uses# listed in Use Groups 6, 7, 8, 9 or 14 on the second #story# of a #building# occupied on one or more of its upper #stories# by #residential uses# or by #community facility uses#, and provided no #commercial uses# are located directly over any #dwelling units#.

Within the portion of the C2-4 District mapped within an R8A District and the portion of the C2-4 District mapped within an R9A District, where located east of Tenth Avenue, south of West 207th Street, west of Ninth Avenue and north of West 206th Street, the underlying provisions of Section 32-421 (Limitation on floors occupied by commercial uses) shall be inapplicable. In lieu thereof, Section 32-422 (Location of floors occupied by commercial uses) shall apply.

In C4 or C6 Districts, the underlying provisions of Section 32-422 (Location of floors occupied by commercial uses) shall be modified for #mixed buildings# to permit #dwelling units# on the same #story# as a #commercial use# provided no access exists between such #uses# at any level containing #dwelling units#, and provided no #commercial uses# are located directly over any #dwelling units#. However, such #commercial uses# may be located over #dwelling units# by authorization of the City Planning Commission upon a finding that sufficient separation of #residential uses# from #commercial uses# exists within the #building#.

In Subareas A1, B2 and B3, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, no #uses# listed in Use Group 6A, 6C or 10A shall be permitted above the ground floor level.

**142-13
Enclosure Requirements in Subdistrict E**

In Subdistrict E, #commercial# and #manufacturing# activities and storage #uses# shall not be subject to the provisions of Section 42-41 (Enclosure of Commercial and Manufacturing Activities) or Section 42-42 (Enclosure or Screening of Storage).

**142-14
Ground Floor Level Requirements**

For the purposes of applying the special #ground floor level# streetscape provisions set forth in Section 37-30 to this Chapter, any portion of a #ground floor level street# frontage along #streets# designated on Map 2 (Ground Floor Use and Curb Cut Regulations) in the Appendix to this Chapter shall be considered #primary street frontages#, and shall consist of Type 1, Type 2 and Type 3 #primary street frontages#. A #ground floor level street# frontage along any other #street# shall be considered a #secondary street frontage#. For the purposes of this Section, defined terms shall include those in Sections 12-10 and 37-311.

The provisions of this Section shall apply to #developments# or #ground floor level enlargements#.

(d) Along #primary street frontages#

(3) Type 1 #primary street frontages#

For #buildings#, or portions thereof, with Type 1 #primary street frontage#, #uses# on the #ground floor level#, to the minimum depth set forth in Section 37-32 (Ground Floor Depth Requirements for Certain Uses), shall be limited to non-#residential uses#, except for Type 1 lobbies and entrances and exits to #accessory# parking spaces provided in accordance with the applicable provisions of Section 37-33 (Maximum Width of Certain Uses). Group parking facilities located on the #ground floor level# shall be wrapped by #floor area# in accordance with the provisions of paragraph (a) of Section 37-35 (Parking Wrap and Screening Requirements). #Ground floor level street walls# shall be glazed in accordance with the provisions set forth in Section 37-34 (Minimum Transparency Requirements), except that in M1 Districts in Subdistrict B, where the #ground floor level# is occupied by #uses# in Use Groups 16, 17 or 18, up to 50 percent of the #ground floor level street wall# width may be exempt from such regulations.

(4) Type 2 #primary street frontages#

For #buildings#, or portions thereof, with Type 2 #primary street frontage#, all #uses# permitted by the underlying district shall be permitted on the #ground floor level#, provided that group parking facilities located on the #ground floor level# shall be wrapped by #floor area# in accordance with the provisions of Paragraph (a) of Section 37-35.

(5) Type 3 #primary street frontages#

For #buildings#, or portions thereof, with Type 3 #primary street frontage#, #uses# on the #ground floor level# shall comply with the regulations applicable to Type 1 #primary street frontages#. In addition, the following regulations shall apply to the #ground floor level# to a depth of 30 feet from the #street line#:

- (i) an aggregate width equal to at least 50 percent of a #building's street wall# shall be occupied by #commercial uses# listed in Use Groups 5, 6A, 6C excluding banks and loan offices, 7B, 8A, 8B, 9A, 10 or 12; and
- (ii) the maximum #street wall# width of a bank or loan office, as listed in Use Group 6C, shall not exceed 25 feet.

However, in Subarea A1 or B1, as shown on Map 1, for #buildings# containing predominantly commercial or public utility vehicle storage, including #accessory# fuel pumps, as listed in Use Group 16C, the screening provisions of Paragraph (b) of Section 37-35 may be utilized as an alternative to such wrapping requirement and any transparency requirements need not apply.

(e) Along #secondary street frontages#

For #buildings#, or portions thereof, with #secondary street frontage#, all #uses# permitted by the underlying district shall be permitted on the #ground floor level#, provided that any off-street parking spaces on the #ground floor level# shall be wrapped or screened in accordance with Section 37-35. Entrances and exits to accessory parking facilities shall be subject to the provisions of Paragraph (b) of Section 37-33.

(f) For blank walls

In #Commercial Districts# or #Manufacturing Districts#, any #street wall# width exceeding 50 feet with no transparent elements on the #ground floor level# shall provide planting or wall treatment in accordance with the provisions of Section 142-141 (Special Streetscape Provisions for Blank Walls).

The level of the finished floor of such ground floor shall be located not higher than five feet above nor lower than five feet below the as-built level of the adjoining #street#.

In C4-5D Districts, and in C2 Districts mapped within R7D Districts, the provisions of Section 32-434 (Ground floor use in C4-5D and C6-3D Districts and in certain C2 Districts) shall not apply. In lieu thereof, the provisions of this Section shall apply.

**142-141
Special Streetscape Provisions for Blank Walls**

Where visual mitigation elements are required on a blank wall along the #ground floor level street wall#, pursuant to the provisions of Section 142-14 (Ground Floor Level Requirements), at least 75 percent of the linear footage of any such blank wall shall be treated by any of the following visual mitigation elements, or both.

(a) Planting

When planting is provided as a visual mitigation element, any combination of perennials, annuals, decorative grasses or shrubs shall be provided in planting beds, raised planting beds or planter boxes in front of the #street wall#. Each foot in width of a planting bed, raised planting bed or planter box, as measured parallel to the #street wall#, shall satisfy one linear foot of frontage mitigation requirement. Such planting bed shall extend to a depth of at least three feet, inclusive of any structure containing the planted material. Any individual planted area shall have a width of at least five feet, and the height of such planting, inclusive of any structure containing the planted materials, shall be at least three feet.

At least 25 percent of such #street wall# width shall be planted in accordance with the provisions of this paragraph.

(b) Wall treatment

When a wall treatment is provided as a visual mitigation element, permitted signs, graphic or sculptural art, rustication, decorative screening or latticework, or living plant material, shall be provided along the #street wall#. Each linear foot of wall treatment shall constitute one linear foot of frontage mitigation requirement. Such wall treatment shall extend to a height of at least 10 feet, as measured from the level of the adjoining sidewalk or grade, and have a minimum width of 10 feet, as measured parallel to the #street wall#.

142-20**SPECIAL FLOOR AREA REGULATIONS**

The underlying #floor area# regulations are modified by the provisions of this Section, inclusive.

142-21**Floor Area Regulations on Waterfront Blocks**

On #waterfront blocks#, the provisions of Section 62-31 (Bulk Computations on Waterfront Zoning Lots) shall be modified so that #lot area# that is seaward of the #shoreline# shall not be included for the purpose of determining allowable #floor area# or to satisfy any other #bulk# regulation.

142-22**Floor Area Regulations in Subareas A2, A3 and B1**

In Subareas A2, A3 and B1, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, the #floor area# regulations shall be modified as follows:

For #zoning lots# without a #shoreline#, or for #zoning lots# with a #shoreline# length of 100 feet or less, the maximum #residential floor area ratio# shall be 4.6. For #zoning lots# with a #shoreline# length of more than 100 feet, the maximum #residential floor area ratio# shall be as set forth in Paragraph (d) of Section 23-154 (Inclusionary Housing) for the particular district.

For #zoning lots# that are divided by zoning district boundary lines, #floor area# may be distributed within a #zoning lot# without regard to zoning district boundary lines.

#Accessory# parking located below a height of 33 feet shall be exempt from the definition of #floor area#.

142-23**Floor Area Regulations in Subarea B2 and B3**

In Subarea B2, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, all permitted #uses# shall have a permitted #floor area ratio# of 2.0. In Subarea B3, as shown on Map 1, the base #floor area ratio# shall be 5.0, and may be increased only in accordance with the provisions of this Section.

The Chairperson of the City Planning Commission shall allow, by certification, a transfer of #floor area# from a #zoning lot# located in Subarea B2 to a #zoning lot# located in Subarea B3 provided that the provisions of this Section are met. For the purpose of this Section, a “granting lot” shall mean a #zoning lot# within Subarea B2 that transfers #floor area#, pursuant to this Section, and a “receiving lot” shall mean a #zoning lot# within Subarea B3 that receives additional #floor area#, pursuant to this Section.

Such certification for a transfer of #floor area# shall be subject to the following conditions:

- (a) the maximum amount of #floor area# that may be transferred from a granting lot shall be based on a #floor area ratio# of 2.0, less the total #floor area# of all existing #buildings# on the granting lot and any previously transferred #floor area#;
- (b) each transfer, once completed, shall irrevocably reduce the amount of #floor area# that may be #developed# or #enlarged# on the granting lot by the amount of #floor area# transferred;
- (c) for #developments# or #enlargements#, which in the aggregate for both the granting lot and the receiving lot, involve an increase in the #floor area# of more than 20,000 square feet of the amount existing on [date of adoption], a waterfront certification, pursuant to Section 62-811 (Waterfront public access and visual corridors) has been granted; and
- (d) prior to the issuance of a building permit, as set forth in this Section, the owners of the granting lot and the receiving lot shall submit to the Chairperson a copy of the transfer instrument legally sufficient in both form and content to effect such a transfer. Notice of the restrictions upon further #development# or #enlargement# of the granting lot and the receiving lot shall be filed by the owners of the respective lots in the Office of the Register of the City of New York (County of New York). Proof of recordation shall be submitted to the Chairperson.

Both the transfer instrument and the notices of restrictions shall specify the total amount of #floor area# transferred and shall specify, by #block# and lot numbers, the granting lot and the receiving lot that are a party to such transfer.

An application filed with the Chairperson for certification, pursuant to this Section shall be made jointly by the owners of the granting lot and the receiving lot, and shall include site plans and zoning calculations for the granting lot and receiving lot showing the additional #floor area# associated with the transfer, and any such other information as may be required by the Chairperson.

The Chairperson shall certify to the Department of Buildings that a #development# is in compliance with the provisions of this Section only

after the transfer instrument and notice of restrictions required by this Section have been executed and recorded with proof of recordation provided to the Chairperson. Such certification shall be a precondition to the filing for or issuing of any building permit allowing more than the basic maximum #floor area ratio# for such #development#.

A separate application shall be filed for each transfer of #floor area# to any #zoning lot#, pursuant to this Section.

142-24 Floor Area Regulations in Subdistrict D

For #zoning lots# that are located partially in a #Commercial District# mapped within an R8A District and partially in a #Commercial District# mapped within an R9A District, #residential floor area# may transfer across the zoning district boundary from the #Commercial District# mapped within an R8A District to the #Commercial District# mapped within an R9A District.

142-25 Special Commercial and Community Facility Floor Area Regulations in Subdistricts C and D

Within Subdistricts C and D, the maximum #floor area ratio# permitted for #commercial# and #community facility uses# shall be modified as follows:

- (a) Within Subdistrict C
- (1) within the C4-4D District mapped around the intersection of Broadway and 207th Street, the maximum #community facility floor area ratio# shall be 4.2;
 - (2) within the portion of the C4-4D District mapped around the intersection of Broadway and Dyckman Street that is west of Broadway, the maximum #community facility floor area ratio# and #commercial floor area ratio# shall be 4.2; and
 - (3) within the portion of the C4-4D District mapped around the intersection of Broadway and Dyckman Street that is east of Broadway and that is within 100 feet of Dyckman Street, the maximum #community facility floor area ratio# and #commercial floor area ratio# shall be 4.2.
- (b) Within Subdistrict D
- (1) within the C2-4 District mapped within an R7D District to the west of Broadway, the maximum #community facility floor area ratio# shall be 4.0;
 - (2) within the C4-4D Districts mapped to the west of Tenth Avenue, the maximum #community facility floor area ratio# and #commercial floor area ratio# shall be 4.2; and
 - (3) within the portion of the C2-4 District mapped within an R8A District or the portion of the C2-4 District mapped within an R9A District, where located east of Tenth Avenue, south of West 207th Street, west of Ninth Avenue and north of West 206th Street, the #commercial floor area ratio# shall be 3.5.

142-30 SPECIAL YARD REGULATIONS

The underlying #yard# regulations are modified by the provisions of this Section.

In M1-4/R7A and M1-4/R9A Districts in Subareas A1 and B3 as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, and in the portion of the C2-4 District mapped within an R8A District or the portion of the C2-4 District mapped within an R9A District, where located east of Tenth Avenue, south of West 207th Street, west of Ninth Avenue, and north of West 206th Street, no #rear yard equivalents# are required for #through lots# or #through lot# portions of a #zoning lot#.

In Subdistrict D, no #rear yard# is required along any portion of a #rear lot line# that is coincident with a #lot line# of the rail yard for the Metropolitan Transportation Authority located east of Tenth Avenue between West 207th Street and West 215th Street.

A #waterfront yard#, as defined in Section 62-11 (Definitions), shall be provided on any portion of a #zoning lot# located within 40 feet of the #shoreline#. Any other #yard# regulations shall be inapplicable within such portion of a #zoning lot#.

142-40 SPECIAL HEIGHT AND SETBACK REGULATIONS

In Subareas A1 and B2, and in Subdistrict E, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, the height and setback regulations of the underlying districts shall apply.

In Subareas A2, A3, B1, B3 and B4, the height and setback regulations of the underlying district regulations are modified by Sections 142-41 through 142-47 shall apply, and all heights shall be measured from the #base plane#.

In Subdistricts C and D, the height and setback regulations of the

underlying district regulations are modified by Sections 142-48 (Special Regulations for Certain Sites in Subdistrict C) and 142-49 (Height and Setback for Certain Sites in Subdistricts C and D), as applicable.

142-41 Permitted Obstructions in Subareas A2, A3, B1, B3 and B4

In Subareas A2, A3, B1, B3 and B4, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, the provisions of Section 33-42 (Permitted Obstructions) shall apply to all #buildings#. In addition, along all #street# frontages, dormers may penetrate a maximum base height in accordance with the provisions of Paragraph (c)(1) of Section 23-621 (Permitted obstructions in certain districts), and balconies shall be permitted in conjunction with #residential uses# as set forth in Section 23-132 (Balconies in R6 through R10 Districts).

142-42 Height and Setback for Zoning Lots in Subareas A2, A3 and B1 With 100 Feet or Less of Shoreline

In Subareas A2, A3 and B1, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, for #zoning lots# that do not have a #shoreline# or that have a #shoreline# with a length of 100 feet or less, the height and setback regulations for R7A Districts set forth in Sections 23-662 (Maximum height of buildings and setback regulations) and 23-664 (Modified height and setback regulations for certain Inclusionary Housing buildings or affordable independent residences for seniors), as applicable, shall apply.

The #street wall# location requirements of Paragraph (b) of Section 35-651 shall apply to #street# frontages along and within 50 feet of Ninth Avenue, and the #street wall# requirements of paragraphs (a)(1) and (2) of Section 35-651 shall apply along all other #street# frontages of the #zoning lot#. The #street wall# articulation provisions of Paragraph (e) of Section 35-651 shall apply along all #street# frontages.

142-43 Height and Setback for Zoning Lots in Subarea A2 With More Than 100 Feet of Shoreline

In Subarea A2, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, for #zoning lots# that have a #shoreline# with a length of more than 100 feet, the following height and setback regulations shall apply:

(f) #Street wall# location

The #street wall# location requirements of Paragraph (b) of Section 35-651 shall apply to #street# frontages along and within 50 feet of Ninth Avenue, and the #street wall# requirements of Paragraphs (a)(1) and (2) of Section 35-651 shall apply along all other #street# frontages of the #zoning lot#. For the purposes of applying such regulations, all #street walls# shall extend to at least the minimum base height set forth in Paragraph (b) of this Section, or the height of the #building#, whichever is less. The #street wall# articulation provisions of Paragraph (e) of Section 35-651 shall apply along all #street# frontages.

(g) Base height and setbacks

The minimum base height shall be 60 feet on all #street# frontages. Within R9A Districts, or C1 or C2 Districts mapped within R9A Districts, the maximum base height shall be 105 feet. Within R8 Districts, or C1 or C2 Districts mapped within R8 Districts, the maximum base height before setback shall be 105 feet if the #building's# maximum overall height does not exceed 155 feet, or 85 feet if a #building# is developed with a tower in accordance with the regulations of Paragraph (e) of this Section.

At a height not lower than the minimum base height nor higher than the maximum base height specified for the applicable district, a setback with a minimum depth of 10 feet shall be provided from the #street wall# of the base. The provisions of Paragraphs (c)(2) through (c)(4) of Section 23-662 (Maximum height of buildings and setback regulations) shall apply to such setbacks.

(h) Within 70 feet of the #shoreline#

Within 70 feet of the #shoreline#, the height of a #building# along 30 percent of the length of a #zoning lot#, as measured parallel to Ninth Avenue, shall be limited to a maximum height of 30 feet, and the height along the remaining 70 percent may rise to a maximum height of 85 feet.

(i) Maximum #building# height

The maximum #building# height shall be 155 feet, except where towers are provided in accordance with Paragraph (e) of this Section.

(j) Optional tower regulations

For #zoning lots# that have a #lot area# of more than one acre, a "tower" shall be permitted above a height of 125 feet, provided that:

- (6) the gross area of any #story# shall not exceed 9,000 square feet, except that any dormers provided within the setback area shall not be included in such gross area;
- (7) the gross area of any #story# above 205 feet shall not exceed 90 percent of the gross area of the highest #story# that is located entirely below a height of 205 feet;
- (8) no portion of such tower shall be located within 80 feet of the #shoreline#;
- (9) the width of such tower shall not exceed 100 feet, as measured parallel to Ninth Avenue. Such width shall be measured in plan and shall include the total width of the combined #lot coverage# of all #stories# above 125 feet; and
- (10) The maximum height of such tower shall not exceed 245 feet.
#Zoning lots# with a #lot area# in excess of 1.5 acres may contain a second tower, provided that the heights of the two towers differ by at least 50 feet from each other, and provided that the combined width of the towers does not exceed 140 feet, as measured parallel to Ninth Avenue. Such width shall be measured in plan and shall include the total width of the combined #lot coverage# of all #stories# above 125 feet.

142-44 Height and Setback for Zoning Lots in Subarea A3 With More Than 100 Feet of Shoreline

In Subarea A3, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, for #zoning lots# that have a #shoreline# with a length of more than 100 feet, the height and setback regulations of this Section shall apply:

- (e) Base along West 207th Street and Ninth Avenue

Along the West 207th Street and Ninth Avenue frontages, all #buildings# shall have a minimum base height of 60 feet, or the height of the #building#, whichever is less, and a maximum base height of 105 feet. The #street wall# location requirements of Paragraph (a)(1) and (2) of Section 35-651 shall apply along both #streets#. The boundary of any easement required for a #street# or sidewalk widening, pursuant to Section 142-64 shall be considered the #street line# for the purpose of this Section.

At a height not lower than the minimum base height nor higher than the maximum base height, a setback with a minimum depth of 10 feet shall be provided from the #street wall# of the base. The provisions of Paragraphs (c)(2) through (c)(4) of Section 23-662 (Maximum height of buildings and setback regulations) shall apply to such setbacks.

- (f) Within 70 feet of the #shoreline#

Within 70 feet of the #shoreline#, the maximum #building# height shall be 85 feet.

- (g) Within 30 feet of former West 208th Street

Within 30 feet of Former West 208th Street, as shown on Map 1 in the Appendix to this Chapter, the height of a #building# along 30 percent of the length of a #zoning lot#, as measured along the former extent of West 208th Street, shall not exceed 30 feet, and the height of the remaining 70 percent may rise to a maximum height of 85 feet.

- (h) Maximum #building# height

Within the portion of the #zoning lot# that is beyond 100 feet of West 207th Street, the maximum #building# height shall be limited to 145 feet. Within the portion of the #zoning lot# that is within 100 feet of West 207th Street, the maximum #building# height shall be 175 feet, except where towers are provided in accordance with Paragraph (e) of this Section.

- (f) Optional tower regulations

For #zoning lots# that have a #lot area# of more than one acre, a “tower” shall be permitted above a height of 175 feet within the portion of the #zoning lot# that is within 100 feet of West 207th Street, provided that:

- (4) the gross area of any #story# shall not exceed 10,000 square feet, except that any dormers provided within the setback area shall not be included in such gross area;
- (5) the gross area of any #story# above 255 feet shall not exceed 90 percent of the gross area of the highest #story# that is located entirely below a height of 255 feet; and
- (6) The maximum height of such tower shall not exceed 295 feet.

142-45 Height and Setback for Zoning Lots in Subarea B1 With More Than 100 Feet of Shoreline

In Subarea B1, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, for

#zoning lots# that have a #shoreline# with a length of more than 100 feet, the height and setback regulations of Section 142-43 (Height and Setback for Sites in Subarea A2 With More Than 100 Feet of Shoreline) shall apply, except that paragraph (e) of such Section shall be modified to allow the gross area of any #story# in a tower to be up to 10,000 square feet and to rise to a height of 265 feet, provided that the gross area of any #story# above 225 feet shall not exceed 90 percent of the gross area of the highest #story# that is located entirely below 225 feet. The #visual corridor# located between a line parallel to and 20 feet south of the prolongation of the centerline of West 218th Street and a line parallel to and 30 feet north of such centerline established by Section 142-60 (INWOOD WATERFRONT ACCESS PLAN) shall be treated as a narrow #street line# for the purposes of applying all height and setback regulations.

142-46 Height and Setback in Subarea B3

In Subarea B3, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, the maximum #building# height shall be 125 feet within 10 feet of a #street line#. Beyond 10 feet of a #street line#, the maximum #building# height shall be 265 feet.

142-47 Height and Setback in Subarea B4

In Subarea B4, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, the height of a #building# within 10 feet of a #street line# shall not exceed 125 feet. Portions of #buildings# located beyond 10 feet of a #street line# may rise to a maximum height of 210 feet. Any #development# or #enlargement# with frontage on West 218th Street must provide a sidewalk widening with a minimum depth of five feet along such frontage. Any #development# or #enlargement# with frontage on Ninth Avenue must provide a sidewalk widening with a minimum depth of five feet along such frontage.

142-48 Special Regulations for Certain Sites in Subdistrict C

In Subdistrict C, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, for #zoning lots# that share a #side lot line# with an adjacent #zoning lot# that is #developed# with a #building# constructed prior to December 15, 1961 that contains #residences# with #legally required windows# facing and located within 15 feet of the shared #side lot line#, the underlying height and setback provisions shall be modified by the provisions of this Section.

The #street wall# location provisions of Paragraph (b)(1) of Section 35-651 shall apply except that where an adjoining #zoning lot# contains #residences# with #legally required windows# facing and within 15 feet of a shared #side lot line#, the #street wall# of a #building# need not extend along the entire #street# frontage of such a #zoning lot# if an open area is provided above the level of the first #story# or a height of 15 feet, whichever is lower, along the entire shared #side lot line#. Where such an open area is provided, the #street# frontage of such open area may be excluded for the purpose of applying the #street wall# location provisions of Paragraph (b)(2) of Section 35-651.

In addition, where an open area with a depth of at least 15 feet, as measured perpendicular from the shared #side lot line#, and is provided in the form of a recess, #court# or other open area is provided along shared #side lot line#, and such open area is provided adjacent to all portions of a #building# on an adjoining #zoning lot# that contain #legally required windows# facing and located within 15 feet of the shared #side lot line#, the maximum height for the #building# set forth in Section 23-662, 23-664, 35-652 or 35-654, as applicable, may be increased by 10 feet; and the maximum number of #stories#, if applicable, may be increased by one.

#Zoning lots# may apply the regulations of this Section along multiple #side lot lines# where applicable, but in no case shall the permitted #building# height be increased by more than one #story# or 10 feet, whichever is lower.

142-49 Height and Setback for Certain Zoning Lots in Subdistricts C and D

In Subdistricts C and D, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, all #non-residential buildings# in C4 and C6 Districts shall follow the height and setback regulations of Paragraph (b) of Section 23-664 (Modified height and setback regulations for certain Inclusionary Housing buildings or affordable independent residences for seniors) for the applicable residential equivalent.

In Subdistrict D, all #developments# or #enlargements# on zoning lots# within M1-4/R7A and M1-4/R9A Districts shall follow the height and setback regulations of Paragraph (b) of Section 23-664, for the applicable #Residence District#, except portions of #zoning lots# that are located within 30 feet of West 201st Street shall be limited to a maximum #building# height to 85 feet.

In Subdistricts C and D, for portions of #zoning lots# located within 100 feet of a #street# that contains an elevated rail line, the underlying height and setback regulations shall be modified as follows:

- (d) the minimum required base height shall be 25 feet;
- (e) the maximum permitted #building# height shall be 165 feet and the maximum number of #stories# shall be 16; and
- (f) along the frontage of a #street# that contains an elevated rail line, the #street wall# location regulations of Paragraph (a)(1) of Section 35-651 shall apply.

**142-50
SPECIAL OFF-STREET PARKING AND LOADING REGULATIONS**

The underlying off-street parking and loading regulations are modified by the provisions of this Section, inclusive.

**142-51
Required Accessory Parking Spaces for Residences**

The requirements of Sections 25-23 (Requirements Where Group Parking Facilities Are Provided) are modified to require #accessory residential# off-street parking spaces for a minimum of 20 percent of new #residences#. The number of #accessory# off-street parking spaces required may be reduced or waived as set forth in the underlying district regulations.

**142-52
Required Accessory Parking Spaces for Commercial or Community Facility Uses in Certain Districts**

No #accessory# parking is required for new #commercial# or #community facility uses# in #mixed buildings# in C2-4, C4-4D, or C4-5D Districts.

**142-53
Public Use of Accessory Parking**

All required or permitted #accessory# off-street parking spaces may be made available for public use. However, any such space shall be made available to the occupant of a #residence# to which it is #accessory# within 30 days after written request for such space is made to the landlord.

**142-54
Accessory Parking on a Roof in Subarea A1**

In Subarea A1, the underlying off-street parking regulations of Section 44-11 (General Provisions) are modified to permit #accessory# parking to be located on the roof of any #story# of a #building#.

**142-55
Curb Cuts**

Curb cuts accessing off-street parking facilities or loading berths shall not be permitted along the #streets# specified as a Type 1 or Type 2 primary street on Map 2 (Special Inwood District –Ground Floor Use and Curb Cut Regulations) in the Appendix to this Chapter on #zoning lots# that also have frontage on a #street# that is not specified on Map 2.

**142-60
INWOOD WATERFRONT ACCESS PLAN**

The provisions of Article VI, Chapter 2, (Special Regulations Applying in the Waterfront Area), shall apply, except as superseded, supplemented or modified by the provisions of this Section, inclusive.

Map 4 (Waterfront Access Plan: Parcel Designation), Map 5 (Waterfront Access Plan: Public Access Areas), and Map 6 (Waterfront Access Plan: Visual Corridors) in the Appendix to this Chapter show the boundaries of the area comprising the Inwood Waterfront Access Plan, boundaries of parcels within the Plan, and the location of certain features mandated or permitted by the Plan.

The Plan has been divided into parcels consisting of tax blocks and lots and other lands as established on [date of adoption], as follows:

- Parcel 1: block 2215, lots 877 and 885; and block 2197, lots 67, 71, 74 and 174
- Parcel 2/3: block 2197, lot 47 and 75
- Parcel 4: block 2197, portion of lot 1
- Parcel 5: block 2188, lot 1
- Parcel 6: block 2187, lots 1, 5, 7 and 20
- Parcel 7: block 2185, lots 25, 36 and 51
- Parcel 8: block 2185, lots 1 and 10
- Parcel 9: block 2184, lots 20 and 40

Within the #Special Inwood District#, the parcels of land designated in this Section need not be contiguous for the area to be considered to be a Waterfront Access Plan, pursuant to Section 62-911.

For the purposes of this Section, inclusive, defined terms shall include those listed in Section 12-10 (DEFINITIONS) and Section 62-11 (Definitions).

**142-61
Lot area and waterfront public access area requirements**

For the purposes of determining requirements for #waterfront public access areas#, #lot area# shall not include any portion of a #zoning# lot that is seaward of the #shoreline#. For the purposes of determining the applicability of #waterfront public access area# requirements, pursuant to Section 62-52, all #zoning lots# with portions located within 40 feet of the #shoreline# shall be considered #waterfront zoning lots#.

On Parcel 1, as shown on Map 4 (Waterfront Access Plan: Parcel Designation) in the Appendix to this Chapter, for the purposes of calculating the total #waterfront public access area# requirements on a “granting lot,” as described in Section 142-23 (Floor Regulations in Subarea B2 and B3), #lot area# shall be the combined #lot area# of all “granting lots” and all “receiving lots.”

**142-62
Tip of Manhattan, Subdistrict B**

In Tip of Manhattan Subdistrict B, for Parcels 1 and 2/3, as shown on Map 4 (Waterfront Access Plan: Parcel Designation) in the Appendix to this Chapter, the following regulations shall apply.

- (b) Applicability of #waterfront public access area requirements# to Use Group 16
 - In Subarea B1, as shown on Map 1, #developments# of #buildings# containing exclusively commercial or public utility vehicle storage, including #accessory# fuel pumps, as listed in Use Group 16C, shall be exempted from #waterfront public access area# requirements.
- (c) #Shore public walkways#
 - (4) the minimum width of a #shore public walkway# set forth in Section 62-53 (Shore Public Walkways) shall be reduced to 20 feet;
 - (5) the minimum width of the screening buffer shall be five feet;
 - (6) on Parcel 1, no #shore public walkway# shall be required.
- (f) #Upland connections#

On Parcel 2/3, #upland connections# shall be provided along the shared boundary between Parcels 1 and Parcel 2/3, and within the area located between a line parallel to and 20 feet south of the prolongation of the centerline of West 218th Street and a line parallel to and 30 feet north of such centerline.

- (g) #Supplemental public access areas#
 - (1) on Parcel 1, #supplemental public access area# shall be bounded by Ninth Avenue to the west, the shared boundary of Parcels 1 and 2/3 to the south, and the stabilized shore to the east. Section 62-571 (Location and area requirements for supplemental public access areas) shall not apply to such #supplemental public access area#;
 - (2) on Parcel 2/3, #supplemental public access area#, if required, shall be located at the intersection of the #upland connection# and the #shore public walkway#. Section 62-571 shall be modified to allow the longest side of such #supplemental public access area# to adjoin the #upland connection# provided that the maximum depth measured perpendicular to the #upland connection# does not exceed 1.5 times the width measured parallel to the #upland connection#.
- (h) #Visual corridors#
 - #Visual corridors# shall be provided at three locations as shown on Map 6 (Waterfront Access Plan: Visual Corridors) in the Appendix to this Chapter:
 - (1) within the prolongation of the #street lines# of West 220th Street;
 - (2) within the prolongation of the #street lines# of Ninth Avenue;

- (3) within the area located between a line parallel to and 20 feet south of the prolongation of the centerline of West 218th Street and a line parallel to and 30 feet north of such centerline. In the event that such #visual corridor abuts# an open area with a minimum depth of 20 feet along the entire length of such #visual corridor#, and an easement for such open area has been recorded against the property, the minimum dimension of a #visual corridor# set forth in 62-512 (Dimensions of visual corridors) may be reduced to 30 feet.

142-63

Sherman Creek Subdistrict A

In the Sherman Creek Subdistrict A, Parcels 5, 6, 7, 8 and 9, as shown on Map 4 (Waterfront Access Plan: Parcel Designation) in the Appendix to this Chapter, the following regulations shall apply.

(c) **#Shore public walkways#**

- (1) #Waterfront zoning lots# that have a #shoreline# measuring more than 100 feet shall provide a #shore public walkway# as required by Section 62-53 (Requirements for Shore Public Walkways).
- (2) #Zoning lots# within or partially within 40 feet of the #shoreline# that do not #abut# the #shoreline#, or that contain a #shoreline# measuring 100 feet or less shall provide either:
 - (i) a #shore public walkway#, located partly on the #zoning lot# and partly on an adjoining #waterfront zoning lot#; or
 - (ii) a #shore public walkway# on any portion of the #zoning lot# within 40 feet of the #shoreline#. Such #shore public walkway# shall have a minimum width of 14 feet, and its pedestrian circulation path shall connect to and provide access from adjoining public #streets#, parks or public places. Such #shore public walkway# shall extend beyond 40 feet of the #shoreline# as necessary to satisfy the minimum dimensional requirements, but the total area of the #shore public walkway# need not exceed an area equivalent to that portion of the #zoning lot# within 40 feet of the #shoreline#. The provisions of Section 62-62 (Design Requirements for Shore Public Walkways and Supplemental Public Access Areas) shall be modified to allow the circulation path to have a minimum width of 10 feet and to be located entirely beyond 10 feet from the #shoreline#. In addition, for Parcels 6, 7 or 8, the planting requirements set forth in paragraph (c)(1) of Section 62-62 need not apply.

Where the #zoning lot# does not include all of the adjacent #shoreline#, the design of the #shore public walkway# shall be compatible with the future improvement of public access areas on the land between the #zoning lot# and the #shoreline#.

- (3) The primary circulation path required, pursuant to Section 62-62 shall be provided at a minimum elevation of 7.5 feet above the #shoreline#, except that such requirement need not include portions of a circulation path that slope downward to meet the elevation of an existing publicly accessible sidewalk.

(d) **#Supplemental public access areas#**

On Parcel 5, no #supplemental public access area# shall be required.

142-64

Special Regulations on Parcel 5

- (b) Section 62-811 (Waterfront public access and visual corridors) shall not apply to Parcel 5, as shown on Map 4 (Waterfront Access Plan: Parcel Designation) in the Appendix to this Chapter. In lieu thereof, the following regulations shall apply. Required Certification

No excavation or building permit shall be issued for any #development# on Parcel 5 until the Chairperson of the City Planning Commission has certified to the Department of Buildings, that:

- (1) a site plan has been submitted showing compliance with the provisions of Sections 62-50 (GENERAL REQUIREMENTS FOR VISUAL CORRIDORS AND WATERFRONT PUBLIC ACCESS AREAS) and 62-60 (DESIGN REQUIREMENTS FOR WATERFRONT PUBLIC ACCESS AREAS) as modified by Section 142-60 (INWOOD WATERFRONT ACCESS PLAN);
- (2) the Chairperson has certified that an easement, the requirements for which shall be determined in consultation with the Department of Transportation, has been provided to

enlarge the adjoining mapped #streets#, an instrument creating such easement has been recorded in the Office of the City Register, and a certified copy of such easement has been submitted to the Department of City Planning; and

- (3) an acceptable restrictive declaration is executed and filed, pursuant to Section 62-74 (Requirements for Recordation).


(c) **Buildout of Adjoining #Streets#**


No certificate of occupancy for any #development# on Parcel 5 shall be issued until the Department of Buildings has been furnished with a certification by the Department of Transportation that adjoining mapped #streets# have been built out to Department of Transportation standards.

Within 45 days of receipt of a complete application, the Chairperson shall either certify that the proposed #development# complies with the requirements of this Section or disapprove such application, citing the nature of any failure to comply. Failure to certify or disapprove such application within the 45 day period will release the Department of Buildings or the Department of Business Services from any obligation to withhold the excavation or building permit and authorize such agency to determine compliance with the provisions of this Section.


**APPENDIX
Special Inwood District Plan**

Map 1. Special Inwood District – Subdistricts and Subareas






Map 3. Special Inwood District – Transit Easement Zones




Map 4. Waterfront Access Plan: Parcel Designation



Parcel Designation

- WAP boundary
- Parcel line
- 2185 / 1, 10 Tax Block / Lot numbers


Map 5. Waterfront Access Plan: Public Access Areas



Public Access Areas

- Parcel line
- - - - - Shore Public Walkway - 20-ft minimum required
- - - - - Shore Public Walkway - 40-ft minimum required, or as modified by Section 142-63(a)
- Supplemental Public Access Area
- Upland Connection (Designated Location)

Map 6. Waterfront Access Plan: Visual Corridors



Visual Corridors

- Parcel line
- Visual Corridor

* * *

APPENDIX F

Inclusionary Housing Designated Areas and Mandatory Inclusionary Housing Areas

* * *

MANHATTAN

* * *

Manhattan Community District 12

Map 1 – (date of adoption)

3. changing from a C6-3X District to a C6-4 District property, bounded by East 14th Street, a line 325 feet westerly of Third Avenue, a line midway between East 14th Street and East 13th Street, and the southerly centerline prolongation of Irving Place; as shown on a diagram (for illustrative purposes only) dated January 29, 2018, and subject to the conditions of the CEQR Declaration E-457.

No. 10

CD 3 N 180202 ZRM

IN THE MATTER OF an application submitted by Fourteenth at Irving, LLC and New York City Economic Development Corporation, pursuant to Section 201 of the New York City Charter, for an amendment of the Zoning Resolution of the City of New York, modifying Article VII, Chapter 4 (Special Permits by the City Planning Commission) and modifying Appendix F for the purpose of establishing a Mandatory Inclusionary Housing area.

Matter underlined is new, to be added;
 Matter ~~struck out~~ is to be deleted;
 Matter within # # is defined in Section 12-10;
 * * * indicates where unchanged text appears in the Zoning Resolution

ARTICLE VII – ADMINISTRATION

Chapter 4 – Special Permits by the City Planning Commission

* * *

74-72

Bulk Modification

74-721

Height and setback and yard regulations

(a) In C4-7, C5-2, C5-3, C5-4, C6-1A, C6-4, C6-5, C6-6, C6-7 or M1-6 Districts, the City Planning Commission may permit modification of the height and setback regulations, including tower coverage controls, for #developments# or #enlargements# located on a #zoning lot# having a minimum #lot area# of 40,000 square feet or occupying an entire #block#.

In C5-3, C6-6 and C6-7 Districts on such #zoning lots#, and in C6-4 Districts as set forth in Paragraph (e) of this Section, the Commission also may modify #yard# and court regulations, and regulations governing the minimum required distance between #buildings# and/or the minimum required distance between #legally required windows# and walls or #lot lines#, provided that the Commission finds that such modifications:

- (1) provide a better distribution of #bulk# on the #zoning lot#;
- (2) result in a better relationship of the #building# to open areas, adjacent #streets# and surrounding development; and
- (3) provide adequate light and air for #buildings# on the #zoning lot# and neither impair access to light and air to #legally required windows# in adjacent #buildings# nor adversely affect adjacent #zoning lots# by unduly restricting access to light and air to surrounding #streets# and properties.

As a condition of this special permit, if any open area extending along a #side lot line# is provided at any level, such open area shall be at least eight feet in width.

* * *

(e) The City Planning Commission may also permit modification of all #bulk# regulations as set forth in paragraph (a) of this Section on #zoning lots# with a minimum #lot area# of 30,000 square feet, where such #zoning lot# is located in a C6-4 District in Manhattan Community District 3, has frontage on a #wide street# and existed on [date of adoption].

* * *

APPENDIX F

Inclusionary Housing Designated Areas and Mandatory Inclusionary Housing Areas

* * *

MANHATTAN

* * *

Manhattan Community District 3

* * *

Map 2 – [date of adoption]

[PROPOSED MAP]



Inclusionary Housing Designated Area

Mandatory Inclusionary Housing Program Area see Section 23-154(d)(3)

Area 1 — [date of adoption] MIH Program Option 1 and Option 2

Portion of Community District 3, Borough of Manhattan

* * *

No. 11

CD 3

C 180203 ZSM

IN THE MATTER OF an application submitted by Fourteenth at Irving, LLC, pursuant to Sections 197-c and 201 of the New York City Charter for the grant of a special permit, pursuant to Section 74-721* of the Zoning Resolution to modify the rear yard regulations of Section 23-53 (Rear Yards) and the height and setback regulations of Section 33-43 (Maximum Height of Walls and Required Setbacks) to facilitate the development of a 21-story commercial building on property, located at 124 East 14th Street (Block 559, Lots 16 & 55), in a C6-4** District, partially within the Special Union Square District, Borough of Manhattan, Community District 3.

* Note: Section 74-721 of the Zoning Resolution is proposed to be changed under a concurrent related application for a Zoning Text amendment (N 180202 ZRM).

** Note: The site is proposed to be rezoned from existing C6-1, C6-2A and C6-3X Districts to a C6-4 District under a concurrent related application for a Zoning Map change (C 180201 ZMM).

Plans for this proposal are on file with the City Planning Commission, and may be seen, at 120 Broadway, 31st Floor, New York, NY 10271-0001.

BOROUGH OF BROOKLYN

No. 12

CD 13

N 180317 PXK

IN THE MATTER OF a Notice of Intent to acquire office space submitted by the Department of Citywide Administrative Services, pursuant to Section 195 of the New York City Charter for use of property, located at 2926 West 19th Street (entirety of Block 7060) (Human Resources Administration offices).

YVETTE V. GRUEL, Calendar Officer
 City Planning Commission
 120 Broadway, 31st Floor, New York, NY 10271
 Telephone (212) 720-3370



a25-m9

COMPTROLLER

MEETING

The City of New York Audit Committee Meeting is scheduled for Wednesday, April 25, 2018, from 9:30 A.M. to NOON, at 1 Centre Street, Room 1005 North. Meeting is open to the general public.

CONSUMER AFFAIRS

■ PUBLIC HEARINGS

NOTICE IS HEREBY GIVEN, PURSUANT TO LAW, that the New York City Department of Consumer Affairs, will hold a Public Hearing on Wednesday, May 2, 2018, at 2:00 P.M., at 42 Broadway, 5th Floor, in the Borough of Manhattan, on the following petitions for sidewalk café revocable consent:

1. Sange Rest, Inc.
168 West 4th Street in the Borough of Manhattan
(To establish, maintain, and operate an enclosed sidewalk café for a term of two years.)
2. Uncle Biagio, LLC
103 Greenwich Avenue in the Borough of Manhattan
(To establish, maintain, and operate an unenclosed sidewalk café for a term of two years.)
3. Spiegel Inc.
26 1st Avenue in the Borough of Manhattan
(To establish, maintain, and operate an unenclosed sidewalk café for a term of two years.)
4. Denis Ayda LLC
3301 36th Avenue in the Borough of Queens
(To establish, maintain, and operate an unenclosed sidewalk café for a term of two years.)
5. Lenox 127 St Rest Corp.
329 Lenox Avenue in the Borough of Manhattan
(To establish, maintain, and operate an unenclosed sidewalk café for a term of two years.)
6. Madera Pizza & Grill Inc.
4729 Vernon Boulevard in the Borough of Queens
(To establish, maintain, and operate an unenclosed sidewalk café for a term of two years.)
7. Michel Ge Inc.
483 Columbus Avenue in the Borough of Manhattan
(To establish, maintain, and operate an unenclosed sidewalk café for a term of two years.)
8. 390 Broome Restaurant LLC
390 Broome Street in the Borough of Manhattan
(To establish, maintain, and operate a regular unenclosed/small unenclosed sidewalk café for a term of two years.)
9. Dez Mulberry LLC
227 Mulberry Street in the Borough of Manhattan
(To establish, maintain, and operate an unenclosed sidewalk café for a term of two years.)

Accessibility questions: Monique Hamler (212) 436-0038, mhamler@dca.nyc.gov, by: Wednesday, May 2, 2018, 12:00 P.M.



← a25

BOARD OF EDUCATION RETIREMENT SYSTEM

■ MEETING

The Board of Trustees of the Board of Education Retirement System, will be meeting, at 5:00 P.M., on Wednesday, April 25, 2018, at Murry Bergtraum High School, 411 Pearl Street, New York, NY 10038.

Accessibility questions: Leslie Kearns (929) 305-3742, lkearns2@bers.nyc.gov, by: Tuesday, April 24, 2018, 3:00 P.M.



a19-25

HOUSING AUTHORITY

■ MEETING

The next Board Meeting of the New York City Housing Authority is scheduled for Wednesday, April 25, 2018, at 10:00 A.M., in the Board Room, on the 12th Floor of 250 Broadway, New York, NY (unless otherwise noted). Copies of the Calendar are available on NYCHA's website or can be picked up at the Office of the Corporate Secretary, at 250 Broadway, 12th Floor, New York, NY, no earlier than 24 hours before the upcoming Board Meeting. Copies of the Minutes are also available on NYCHA's website or can be picked up at the Office of the Corporate Secretary, no earlier than

3:00 P.M., on the Thursday after the Board Meeting.

Any changes to the schedule will be posted here and on NYCHA's website, at <http://www1.nyc.gov/site/nycha/about/board-calendar>, page, to the extent practicable at a reasonable time before the meeting.

The meeting is open to the public. Pre-Registration at least 45 minutes before the scheduled Board Meeting is required by all speakers. Comments are limited to the items on the Calendar. Speaking time will be limited to three minutes. The public comment period will conclude upon all speakers being heard or at the expiration of 30 minutes allotted by law for public comment, whichever occurs first.

For additional information, please visit NYCHA's website or contact (212) 306-6088.

Accessibility questions: Office of the Corporate Secretary by phone at (212) 306-6088 or by email at corporate.secretary@nycha.nyc.gov, by: Wednesday, April 11, 2018, 5:00 P.M.



a4-25

HOUSING PRESERVATION AND DEVELOPMENT

■ PUBLIC HEARINGS

PLEASE TAKE NOTICE that a public hearing, will be held on May 23, 2018, at 1 Centre Street, Manhattan at 10:00 A.M., or as soon thereafter, as the matter may be reached on the calendar, at which time and place those wishing to be heard, will be given an opportunity to be heard concerning the proposed sale of the Disposition Area, pursuant to Section 695(2)(b) of the General Municipal Law and Section 1802(6)(j) of the Charter.

Pursuant to Section 695(2)(b) of the General Municipal Law and Section 1802(6)(j) of the Charter, notice hereby is given that the Department of Housing Preservation and Development ("HPD") of the City of New York ("City") has proposed the sale of the following City-Owned property (collectively, "Disposition Area") in the Borough of Manhattan:

Block	Lot	Address
2007	46	118 West 139 Street
2007	47	120 West 139 Street
2007	48	122 West 139 Street
1822	15	123 West 112 Street a.k.a 45 St. Nicholas Avenue
1924	104	281 West 118 Street
1729	49	30 West 132 Street

Under HPD's Multifamily Preservation Loan Program, sponsors purchase and rehabilitate City-Owned vacant and/or occupied multifamily buildings, in order to create affordable rental housing units with a range of affordability. Construction and permanent financing is provided through loans from private institutional lenders and from public sources, including HPD.

HPD has designated MPLP 6 Housing Development Fund Company, Inc. ("Sponsor") as qualified and eligible to purchase and redevelop the Disposition Area under the Multifamily Preservation Loan Program. HPD proposes to sell the Disposition Area to the Sponsor at the nominal price of one dollar (\$1) per tax lot. The Sponsor will deliver an enforcement note and mortgage to the City for the remainder of the Disposition Area's appraised value ("Land Debt"). The Sponsor will rehabilitate six (6) multiple dwellings in the Disposition Area. Upon completion, the project will provide approximately eighty-two (82) dwelling units, including two (2) superintendent units, and five (5) commercial units.

The appraisal and the proposed Land Disposition Agreement and Project Summary, are available for public examination at the office of HPD, Room 5-I, 100 Gold Street, New York, NY on business days during business hours.

Individuals requesting sign language interpreters should contact the Mayor's Office of Contract Services, Public Hearings Unit, Room 915, 253 Broadway, New York, NY 10007, (212) 788-7490, no later than ten (10) business days prior to the public hearing. TDD users should call Verizon relay services.



← a25

**CHANGE IN LOCATION
PUBLIC NOTICE**

Pursuant to Section 695(2)(b) of the General Municipal Law and Section 1802(6)(j) of the Charter, notice is hereby given that the Department of Housing Preservation and Development (“HPD”) of the City of New York (“City”) has proposed the sale of the following City-Owned property (collectively, “Disposition Area”) in the Borough of Bronx:

<u>Address</u>	<u>Block/Lot(s)</u>
425 Grand Concourse	2346/1

Under HPD’s Mixed Income Program: Mix and Match, sponsors purchase City-Owned or privately owned land or vacant buildings, and construct multifamily buildings in order to create affordable rental housing units with a range of affordability, in which at least half of the units are affordable to low income households earning up to 60 percent of the Area Median Income (“AMI”), and the remaining units are affordable to other low income households. Construction and permanent financing is provided through loans from private institutional lenders and from public sources including HPD, the New York City Housing Development Corporation, the State of New York, and the federal government. Additional funding may also be provided from the syndication of low-income housing tax credits.

Under the proposed project, the City will sell the Disposition Area to PH425 Housing Development Fund Corporation (“Sponsor”), for the nominal price of one dollar per tax lot, and the Sponsor will convey beneficial ownership of the Disposition Area to Trinity Mid Bronx Residential Limited Partnership (“Partnership” and collectively with Sponsor, “Owner”). The Partnership will deliver an enforcement note and the Owner will deliver an enforcement mortgage for the remainder of the appraised value. The Owner will then construct one building containing a total of approximately 276 rental dwelling units, plus one unit for a superintendent, and approximately 12,103 square feet of commercial space and approximately 41,625 square feet of community facility space on the Disposition Area.

The Land Debt will be repayable out of resale or refinancing profits for a period of at least thirty (30) years following completion of construction. The remaining balance, if any, may be forgiven at the end of the term.

The appraisal and the proposed Land Disposition Agreement and Project Summary are available for public examination at the office of HPD, 100 Gold Street, Room 5-I, New York, NY, on business days during business hours.

PLEASE TAKE NOTICE that a public hearing, will be held on April 25, 2018, at 1 Centre Street, Manhattan, Mezzanine, at 10:00 A.M., or as soon thereafter as the matter may be reached on the calendar, at which time and place those wishing to be heard, will be given an opportunity to be heard concerning the proposed sale of the Disposition Area, pursuant to Section 695(2)(b) of the General Municipal Law and Section 1802(6)(j) of the Charter. **Please note that the location has been changed from 1 Centre Street to 22 Reade Street, Main Floor, Manhattan, at 10:00 A.M.**

Individuals requesting sign language interpreters should contact the Mayor’s Office of Contract Services, Public Hearings Unit, 253 Broadway, Room 915, New York, NY 10007, (212) 788-7490, no later than five (5) business days prior to the public hearing. TDD users should call Verizon relay services.

Accessibility questions: Jackie Galory (212) 788-7490, by: Friday, April 20, 2018, 10:00 A.M.

 **a20-25**

**CHANGE OF LOCATION
PUBLIC NOTICE**

Pursuant to Section 695(2)(b) of the General Municipal Law and Section 1802(6)(j) of the Charter, notice hereby is given that the Department of Housing Preservation and Development (“HPD”) of the City of New York (“City”) has proposed the sale of the following City-Owned property (collectively, “Disposition Area”) in the Borough of Manhattan:

<u>Block</u>	<u>Lot</u>	<u>Address</u>
1211	07	165 West 80th Street

Under HPD’s Special Projects Loan Program, sponsors purchase and rehabilitate City-Owned and privately owned vacant and/or occupied multifamily buildings in order to create affordable housing units with a range of affordability. Construction and permanent financing is provided through loans from private institutional lenders and from public sources, including HPD.

HPD has designated 165 West 80th Street Housing Development Fund Company, Inc. (“Sponsor”) as qualified and eligible to purchase and redevelop the Disposition Area under the Special Projects Loan Program. HPD proposes to sell the Disposition Area to the Sponsor at the nominal price of one dollar (\$1) per tax lot. The Sponsor will deliver

an enforcement note and mortgage to the City for the remainder of the Disposition Area’s appraised value (“Land Debt”). The Sponsor will rehabilitate one (1) multiple dwelling in the Disposition Area, which includes one (1) commercial space/community facility space. Upon completion of co-operative milestones, the project will provide approximately twenty-eight (28) affordable co-operative dwelling units, plus one (1) superintendent unit.

The appraisal and the proposed Land Disposition Agreement and Project Summary are available for public examination at the office of HPD, Room 5-I, 100 Gold Street, New York, NY, on business days during business hours.

PLEASE TAKE NOTICE that the public hearing, scheduled on April 11, 2018, at 1 Centre Street, Manhattan, at 10:00 A.M., was continued to April 25, 2018. Those wishing to be heard will be given an opportunity to be heard concerning the proposed sale of the Disposition Area, pursuant to Section 695(2)(b) of the General Municipal Law, and Section 1802(6)(j) of the Charter. **Please note that the hearing location has been changed from 1 Centre Street, Manhattan to 22 Reade Street, Manhattan, Main Floor, at 10:00 A.M.**

Individuals requesting sign language interpreters should contact the Mayor’s Office of Contract Services, Public Hearings Unit, Room 915, 253 Broadway, New York, NY 10007, (212) 788-7490, no later than ten (10) business days prior to the public hearing. TDD users should call Verizon relay services.

Accessibility questions: Jackie Galory (212) 788-7490, by: Friday, April 20, 2018, 10:00 A.M.

 **a20-25**

**INFORMATION TECHNOLOGY AND
TELECOMMUNICATIONS**

■ PUBLIC HEARINGS

NOTICE OF A FRANCHISE AND CONCESSION REVIEW COMMITTEE (“FCRC”) PUBLIC HEARING, to be held on Monday, May 7, 2018, commencing at 2:30 P.M., at 2 Lafayette Street, 14th Floor Auditorium, Borough of Manhattan, relating to: A proposed second amendment to a public communications structure franchise agreement between the City of New York and CityBridge, LLC (“CityBridge”), that will modify (1) the schedule and deployment of Structures to be installed, (2) the criteria applicable to siting of each Structure, (3) the provision of ancillary services, and (4) the timing of franchise compensation payments.

A copy of the proposed second amendment may be viewed by appointment at the Department of Information Technology and Telecommunications, 2 Metrotech Center, 4th Floor, Brooklyn, NY 11201, commencing April 16, 2018, through May 7, 2018, excluding Saturdays, Sundays and holidays. Paper copies of the proposed second amendment may be obtained, by appointment, at a cost of \$.25 per page. All payments shall be made at the time of pickup by check or money order made payable to the New York City Department of Finance. The proposed second amendment may also be obtained in PDF form at no cost, by email request. Interested parties should contact franchiseinfo@doitt.nyc.gov, to request an appointment or a PDF of the amendment.

NOTE: Individuals requesting sign language interpreters or any other accommodation of disability at the public hearing should contact the Mayor’s Office of Contract Services, Public Hearing Unit, 253 Broadway, 9th Floor, New York, NY 10007, (212) 788-0010, no later than SEVEN (7) BUSINESS DAYS PRIOR TO THE PUBLIC HEARING. TDD users should call Verizon relay service.

The Hearing may be cablecast on NYCMedia channels.

Accessibility questions: (212) 788-0010, by: Thursday, April 26, 2018, 5:00 P.M.

 **a16-m7**

LANDMARKS PRESERVATION COMMISSION

■ PUBLIC HEARINGS

NOTICE IS HEREBY GIVEN that, pursuant to the provisions of Title 25, Chapter 3 of the Administrative Code of the City of New York (Sections 25-303, 25-307, 25-308, 25-309, 25-313, 25-318, 25-320) on Tuesday, May 8, 2018, a public hearing will be held, at 1 Centre Street, 9th Floor, Borough of Manhattan, with respect to the following properties and then followed by a public meeting. The final order and estimated times for each application will be posted on the Landmarks Preservation Commission website, the Friday before the hearing. Any person requiring reasonable accommodation in order to participate in

the hearing or attend the meeting, should contact the Landmarks Commission no later than five (5) business days before the hearing or meeting.

**454 Fulton Street - Individual Landmark
LPC-19-18814 - Block 157 - Lot 9 - Zoning: C5-4
CERTIFICATE OF APPROPRIATENESS**

A department store designed by Robert D. Kohn and Charles Butler and built in 1924-1925, and expanded in 1928-1929. Application is to install signage.

**565A Carlton Avenue - Prospect Heights Historic District
LPC-19-17675 - Block 1137 - Lot 6 - Zoning: R6B
CERTIFICATE OF APPROPRIATENESS**

An Italianate style rowhouse built c. 1869-1880. Application is to construct rear yard and rooftop additions.

**17 Bleecker Street - NoHo East Historic District
LPC-19-20186 - Block 529 - Lot 50 - Zoning: M1-5B
CERTIFICATE OF APPROPRIATENESS**

A Neo-Classical style store and loft building, designed by Frederick Ebeling and built in 1909. Application is to legalize the installation of storefront infill, in non-compliance with Certificate of No Effect 19-11252.

**75 Bank Street - Greenwich Village Historic District
LPC-19-23183 - Block 624 - Lot 7504 - Zoning: C1-6
CERTIFICATE OF APPROPRIATENESS**

An apartment house, designed by Irving Margon and built in 1938. Application is to legalize the removal of stairs and the installation of a service ramp and security cameras and conduit without Landmarks Preservation Commission permit(s).

**428 Lafayette Street - NoHo Historic District
LPC-19-22891 - Block 545 - Lot 40 - Zoning: M1-5B
CERTIFICATE OF APPROPRIATENESS**

A Greek Revival style townhouse, designed by Seth Geer and built in 1832-33. Application is to alter an entrance bay and install a through-window louver.

**89 Greene Street - SoHo-Cast Iron Historic District
LPC-19-20018 - Block 500 - Lot 7507 - Zoning: M1-5A
CERTIFICATE OF APPROPRIATENESS**

A store and loft building, designed by J.B. Snook and built in 1886-87. Application is to install a bracket sign.

**120 Prince Street - SoHo-Cast Iron Historic District
LPC-19-17979 - Block 500 - Lot 16 - Zoning: M1-5A
CERTIFICATE OF APPROPRIATENESS**

A store and light manufacturing building, designed by Fred S. Schlesinger and built in 1892-93. Application is to legalize the installation of a flagpole without Landmarks Preservation Commission permit(s).

**30 East 21st Street - Ladies' Mile Historic District
LPC-19-18706 - Block 849 - Lot 55 - Zoning: M1-5M
CERTIFICATE OF APPROPRIATENESS**

A Neo-Renaissance style store and loft building, designed by Ralph Samuel Townsend and built in 1897-98. Application is to install a barrier-free access ramp.

**950 Park Avenue - Park Avenue Historic District
LPC-19-19188 - Block 1493 - Lot 37 - Zoning: R10
CERTIFICATE OF APPROPRIATENESS**

A Renaissance Revival style apartment building, designed by J.E.R. Carpenter and built in 1919-20. Application is to replace windows.

**1065 Park Avenue - Park Avenue Historic District
LPC-19-13316 - Block 1516 - Lot 1 - Zoning: R10
CERTIFICATE OF APPROPRIATENESS**

A Modern style apartment building, designed by Stephen C. Lyras and built in 1969-73. Application is to establish a master plan governing the future installation of windows.

**157 East 70th Street - Upper East Side Historic District
LPC-19-22629 - Block 1405 - Lot 24 - Zoning: R8B R9X
CERTIFICATE OF APPROPRIATENESS**

An altered rowhouse originally built c. 1879, with the current façade built, pursuant to Certificate of Appropriateness 95-0132. Application is to alter the façade, ironwork and areaway.

**2633 Adam Clayton Powell Jr. Boulevard - Individual Landmark
LPC-19-21410 - Block 2016 - Lot 60- Zoning: R7-2
ADVISORY REPORT**

A housing project designed by Archibald Manning Brown, and built in 1936-1937. Application is to replace storefront infill, install new window and door openings, a skylight, a canopy, and signage.

**1680 Lexington Avenue - Individual Landmark
LPC-19-23899 - Block 1633 - Lot 13 - Zoning: R7-2
BINDING REPORT**

A Neo-Grec style public school building, designed by David I. Stagg and built in 1879-82. Application is to install signage in the yard and an air conditioning unit in the alley.

**799 Fort Washington Avenue - Individual Landmark
LPC-19-20929 - Block 2179 - Lot 701 - Zoning: R7-2
CERTIFICATE OF APPROPRIATENESS**

A museum complex composed of portions of medieval buildings and modern structures, designed by Charles Collens and built between 1934 and 1938. Application is to replace a window.

☛ a25-m8

NOTICE IS HEREBY GIVEN that, pursuant to the provisions of Title 25, Chapter 3 of the Administrative Code of the City of New York (Sections 25-303, 25-307, 25-308, 25-309, 25-313, 25-318, 25-320) on **Tuesday, May 8, 2018, at 9:30 A.M.**, a public hearing will be held, at 1 Centre Street, 9th Floor, Borough of Manhattan, with respect to the following properties and then followed by a public meeting. The final order and estimated times for each application will be posted on the Landmarks Preservation Commission website, the Friday before the hearing. Please note that the order and estimated times are subject to change. Any person requiring reasonable accommodation in order to participate in the hearing or attend the meeting, should contact the Landmarks Commission no later than five (5) business days before the hearing or meeting.

ITEM TO BE HEARD

ITEM No. 1
LP-2599

Proposed Boerum Hill Historic District Extension,
Borough of Brooklyn

AREA I

Area I of the proposed Boerum Hill Historic District Extension consists of the property, bounded by a line beginning on the southern curblin of Dean Street at a point on a line extending northerly from a portion of the western property line of 86 Dean Street, then extending southerly along the western property line of 86 Dean Street, southerly along the western property line of 90 Bergen Street to the southern curblin of Bergen Street easterly to a point on a line extending northerly from the western property line of 90 Bergen Street, then extending southerly along the western property line of 90 Bergen Street, easterly along the southern property line of 90 Bergen Street to 134 Bergen Street, northerly along the eastern property line of 134 Bergen Street to the centerline of Bergen Street easterly along said centerline to its intersection with the centerline of Hoyt Street, then along said centerline of Hoyt Street to a point formed by its intersection with a line extending easterly from the southern curblin of Dean Street, then following the curblin of Dean Street to the point extending northerly from the western property line of 86 Dean Street.

AREA II

Area II of the proposed Boerum Hill Historic District Extension consists of the property, bounded by a line beginning on the eastern curblin of Nevins Street at a point on a line extending westerly from the northern property line of 245 Bergen Street, then extending southerly along the curblin of Nevins Street to a point on a line extending westerly along the southern property lines of 258 Wyckoff Street then extending westerly along the southern property line of 258 Wyckoff Street to 196 Wyckoff Street aka 169 Bond Street, the extending northerly along the centerline of Bond Street to the intersection of a line extending westerly from the northern property line of 143 Bond Street, then easterly along the northern property line of 143 Bond Street, southerly along a portion of the eastern property line of 143 Bond Street, then easterly along the northern property line of 199 Bergen Street to the point of beginning.

AREA III

Area III of the proposed Boerum Hill Historic District Extension consists of the property, bounded by a line beginning on the southern curblin of Atlantic Avenue at a point on a line extending northerly from the eastern property line of 428 Atlantic Avenue then following southerly the eastern property line of 428 Atlantic Avenue, then westerly along the southern property line of 428 Atlantic Avenue to 426 Atlantic Avenue, northerly along a portion of the western property line of 426 Atlantic Avenue, then westerly along the southern property line of 424 Atlantic Avenue to 414 Atlantic Avenue, then southerly along a portion of the eastern property line of 414 Atlantic Avenue, then westerly to the intersection of the centerline of Bond Street, then southerly along the centerline of Bond Street to the intersection of the center line of Pacific Street, then following westerly along the centerline of Pacific Street to the intersection of a line extending northerly from the eastern property line of 358 Pacific Street, then southerly along the eastern property line of 358 Pacific Street, then westerly along the southern property line of 358 Pacific Street, northerly along the western property line of 358 Pacific Street to the southern curblin of Pacific Street, then westerly to the intersection of a line extending southerly from the western property line of 351 Pacific Street, following the western property line of 351 Pacific Street to the southern property line of 368 Atlantic Avenue, then westerly along the southern property line of 368 Atlantic Avenue to the eastern curblin of Hoyt Street, then northerly along the western property line of 348 Atlantic Avenue to the intersection of the southern curblin of Atlantic Avenue, then westerly along the southern curblin of Atlantic Avenue to the intersection of a line extending southerly from the western property line of 365 Atlantic Avenue, then northerly along the western property

line of 365 Atlantic Avenue, then westerly along the northern property line of 365 Atlantic Avenue, northerly along a portion of the western property line of 367 Atlantic Avenue then easterly along the northern property line of 367 Atlantic Avenue, then southerly along a portion of the eastern property line of 367 Atlantic Avenue, then easterly along the northern property line of 369 Atlantic Avenue to 389 Atlantic Ave, southerly along the eastern property line of 389 Atlantic Avenue to the southern curbline of Atlantic Avenue easterly to the point of beginning.

Accessibility questions: Lorraine Roach-Steele (212) 669-7815, lroach-steele@lpc.nyc.gov, by: Thursday, April 26, 2018, 4:00 P.M.



a24-m7

MAYOR'S OFFICE OF CONTRACT SERVICES

MEETING

On Tuesday, May 1, 2018, at 2:00 P.M., the New York City Procurement Policy Board, will hold a meeting in the Rockaway Conference Room, of 253 Broadway, 9th Floor, in the Borough of Manhattan. For more information, please contact the Mayor's Office of Contract Services ("MOCS") at (212) 788-0010. If you wish to observe this meeting and require the services of a sign language interpreter, please call the number listed above or contact MOCS via email, at Michael.Smilowitz@mocs.nyc.gov, no later than April 27, 2018.

Accessibility questions: michael.smilowitz@mocs.nyc.gov, by: Friday, April 27, 2018, 1:00 P.M.



a24-m1

BOARD OF STANDARDS AND APPEALS

PUBLIC HEARINGS

May 15, 2018, 10:00 A.M.

NOTICE IS HEREBY GIVEN of a public hearing, Tuesday morning, May 15, 2018, 10:00 A.M., in Spector Hall, 22 Reade Street, New York, NY 10007, on the following matters:

SPECIAL ORDER CALENDAR

933-28-BZ

APPLICANT – Gerard J. Caliendo, R.A., AIA, for RB Auto Repair/Roger Budhu, owner.

SUBJECT – Application October 16, 2015 – Extension of Term, Amendment & Waiver (11-413) for an extension of the term of a variance which permitted the operation of an automotive repair facility and gasoline service station (UG 16) and an Amendment for the legalization of the enlargement with an insulated corrugated metal enclosure. R5 zoning district.

PREMISES AFFECTED – 125-24 Metropolitan Avenue, Block 9271, Lot 4, Borough of Queens.

COMMUNITY BOARD #9Q

APPEALS CALENDAR

257-15-A

APPLICANT – Rothkrug Rothkrug & Spector LLP, for ESL8 Properties LLC, owner.

SUBJECT – Application November 18, 2015 – Proposed construction within the bed of a mapped street is contrary to Article 3 Section 35 of the General City Law and related bulk waivers under ZR 72-01-(g). R3-2(NA-1) zoning district.

PREMISES AFFECTED – 1221 Forest Hill Road, Block 1965, Lot 59, Borough of Staten Island.

COMMUNITY BOARD #2SI

2017-5-A through 2017-7-A

APPLICANT – Eric Palatnik, P.C., for Cetka Mersimovski, owner. SUBJECT – Application January 6, 2017 – Proposed construction of three buildings, two buildings with retail and office space and one warehouse, not fronting on a legally mapped street, contrary to General City Law 36. M1-1 zoning district.

PREMISES AFFECTED – 620A, 620B, 620C Sharrots Road, Block 7400, Lot 40, Borough of Staten Island.

COMMUNITY BOARD #3SI

2017-234-A

APPLICANT – Rothkrug Rothkrug & Spector LLP

SUBJECT – Application August 8, 2017 – Proposed construction of a self-storage facility not fronting a legally mapped street contrary to General City Law 36. M1-1 zoning district.

PREMISES AFFECTED – 266 Wild Avenue, Block 2645, Lot 1, Borough of Staten Island.

COMMUNITY BOARD #2SI

May 15, 2018, 1:00 P.M.

NOTICE IS HEREBY GIVEN of a public hearing, Tuesday afternoon, May 15, 2018, 1:00 P.M., in Spector Hall, 22 Reade Street, New York, NY 10007, on the following matters:

ZONING CALENDAR

2016-4265-BZ

APPLICANT – Law Office of Fredrick A. Becker, for 25 Bleecker Street, LLC, owner.

SUBJECT – Application October 6, 2016 – Variance (§72-21) to permit the development of a six-story and penthouse structure containing commercial retail (UG 6) on the first and cellar floors contrary to ZR §42-14(D)(2)(B) and residential (UG 2) in the upper floors contrary to ZR §42-10. The proposed rear yard does not comply with ZR §§43-26 & 43-27. M1-5B (NOHO Historic District) zoning district.

PREMISES AFFECTED – 25 Bleecker Street, Block 529, Lot 54, Borough of Manhattan.

COMMUNITY BOARD #2M

2016-4275-BZ

APPLICANT – Gerald J. Caliendo, R.A., AIA, for Joseph G. Ciampa/Ciampa North Co., owner; Push Fitness Club, lessee.

SUBJECT – Application October 31, 2016 – Special Permit (§73-36) to permit the legalization of a physical cultural establishment (*Push Fitness Club*), located on the first floor, basement and mezzanine levels of the existing commercial building contrary to ZR §42-10. M1-1 zoning district.

PREMISES AFFECTED – 132-15 14th Avenue, Block 4012, Lot(s) 45 & 30, Borough of Queens.

COMMUNITY BOARD #7Q

2017-149-BZ

APPLICANT – Sheldon Lobel, P.C., for Willard J. Price Associates LLC, owner.

SUBJECT – Application May 15, 2017 – Special Permit (§73-433) to permit the reduction of 88 accessory off-street parking spaces required for existing income-restricted housing units. C2-4/R6A, C2-4/R6B, R6A & R6B zoning district.

PREMISES AFFECTED – 510 Quincy Street & 651-671 Gates Avenue, Block 1811, Lot 19, Borough of Brooklyn.

COMMUNITY BOARD #3BK

2017-209-BZ

APPLICANT – Eric Palatnik, P.C., for Yoel Zagelbaum, owner.

SUBJECT – Application June 9, 2017 – Special Permit (§73-622) to permit the enlargement of an existing single family home, contrary to floor area, open space and lot coverage (ZR §23-142); perimeter wall height (ZR §23-631) and less than the required rear yard (ZR §23-47). R3-2 zoning district.

PREMISES AFFECTED – 1622 East 29th Street, Block 679, Block 8, Borough of Brooklyn.

COMMUNITY BOARD #15BK

2017-304-BZ

APPLICANT – Simons & Wright LLC, for 160 17th Street, LLC, owner; Brooklyn Prospect Charter School, lessee.

SUBJECT – Application November 21, 2017 – Special Permit (§73-19) to permit the construction of a school (UG 3) (*Brooklyn Prospect Charter School*), contrary to use regulation (ZR §42-10). M1-2D zoning district.

PREMISES AFFECTED – 160 17th Street, Block 630, Lot 22, Borough of Brooklyn.

COMMUNITY BOARD #7BK

Margery Perlmutter, Chair/Commissioner

Accessibility questions: Mireille Milfort (212) 386-0078, mmilfort@bsa.nyc.gov, by: Friday, May 11, 2018, 4:00 P.M.



a24-25

TRANSPORTATION

PUBLIC HEARINGS

NOTICE IS HEREBY GIVEN, pursuant to law, that the following proposed revocable consents, have been scheduled for a public hearing by the New York City Department of Transportation. The hearing will be held, at 55 Water Street, 9th Floor, Room 945, commencing at 2:00 P.M., on Wednesday, April 25, 2018. Interested parties can obtain copies of proposed agreements or request sign-language interpreters (with at least seven days prior notice), at 55 Water Street, 9th Floor SW, New York, NY 10041, or by calling (212) 839-6550.

#1 IN THE MATTER OF a proposed revocable consent authorizing 347 Greene Holdings LLC, to construct, maintain and use a wheelchair lift, new stoop and fenced-in area with steps on the north sidewalk of Greene Avenue between Franklin Avenue and Classon Avenue, in the

Borough of Brooklyn. The proposed revocable consent is for a term of ten years from Approval by the Mayor and provides among other terms and conditions for compensation payable to the City according to the following schedule: **R.P. # 2434**

- From the Approval Date to June 30, 2018 - \$3,000/per annum
- For the period July 1, 2018 to June 30, 2019 - \$3,053
- For the period July 1, 2019 to June 30, 2020 - \$3,106
- For the period July 1, 2020 to June 30, 2021 - \$3,159
- For the period July 1, 2021 to June 30, 2022 - \$3,212
- For the period July 1, 2022 to June 30, 2023 - \$3,265
- For the period July 1, 2023 to June 30, 2024 - \$3,318
- For the period July 1, 2024 to June 30, 2025 - \$3,371
- For the period July 1, 2025 to June 30, 2026 - \$3,424
- For the period July 1, 2026 to June 30, 2027 - \$3,477
- For the period July 1, 2027 to June 30, 2028 - \$3,530

the maintenance of a security deposit in the sum of \$5,000 and the insurance shall be in the amount of Two Million Dollars (\$2,000,000) per occurrence for bodily injury and property damage, One Million Dollars (\$1,000,000) for personal and advertising injury, Two Million Dollars (\$2,000,000) aggregate, and Two Million Dollars (\$2,000,000) products/completed operations.

#2 IN THE MATTER OF a proposed revocable consent authorizing Christopher Harland, to continue to maintain and use a stoop and planted area on the south sidewalk of West 12th Street, west of Fifth Avenue, in the Borough of Manhattan. The proposed revocable consent is for a term of ten years from July 1, 2017 to June 30, 2027 and provides among other terms and conditions for compensation payable to the City according to the following schedule: **R.P. #1590**

- For the period July 1, 2017 to June 30, 2018 - \$1,002
- For the period July 1, 2018 to June 30, 2019 - \$1,020
- For the period July 1, 2019 to June 30, 2020 - \$1,038
- For the period July 1, 2020 to June 30, 2021 - \$1,056
- For the period July 1, 2021 to June 30, 2022 - \$1,074
- For the period July 1, 2022 to June 30, 2023 - \$1,092
- For the period July 1, 2023 to June 30, 2024 - \$1,110
- For the period July 1, 2024 to June 30, 2025 - \$1,128
- For the period July 1, 2025 to June 30, 2026 - \$1,146
- For the period July 1, 2026 to June 30, 2027 - \$1,164

the maintenance of a security deposit in the sum of \$2,500 and the insurance shall be in the amount of Two Million Dollars (\$2,000,000) per occurrence for bodily injury and property damage, One Million Dollars (\$1,000,000) for personal and advertising injury, Two Million Dollars (\$2,000,000) aggregate, and Two Million Dollars (\$2,000,000) products/completed operations.

#3 IN THE MATTER OF a proposed revocable consent authorizing David B. Poor, to construct, maintain and use a fenced-in area on the north sidewalk of West 94th Street, between Central Park West and Columbus Avenue, in the Borough of Manhattan. The proposed revocable consent is for a term of ten years from Approval Date by the Mayor and provides among other terms and conditions for compensation payable to the City according to the following schedule: **R.P. # 2435**

- From the Approval Date by the Mayor to June 30, 2018- \$1,500/per annum
- For the period July 1, 2018 to June 30, 2019 - \$1,526
- For the period July 1, 2019 to June 30, 2020 - \$1,552
- For the period July 1, 2020 to June 30, 2021 - \$1,578
- For the period July 1, 2021 to June 30, 2022 - \$1,604
- For the period July 1, 2022 to June 30, 2023 - \$1,630
- For the period July 1, 2023 to June 30, 2024 - \$1,656
- For the period July 1, 2024 to June 30, 2025 - \$1,682
- For the period July 1, 2025 to June 30, 2026 - \$1,708
- For the period July 1, 2026 to June 30, 2027 - \$1,734
- For the period July 1, 2027 to June 30, 2028 - \$1,760

the maintenance of a security deposit in the sum of \$5,000 and the insurance shall be in the amount of Two Million Dollars (\$2,000,000) per occurrence for bodily injury and property damage, One Million Dollars (\$1,000,000) for personal and advertising injury, Two Million Dollars (\$2,000,000) aggregate, and Two Million Dollars (\$2,000,000) products/completed operations.

#4 IN THE MATTER OF a proposed revocable consent authorizing Igor Vagayev, to construct, maintain and use a stoop and planted areas on the north sidewalk of Dooley Street, between Voorhies Avenue and Shore Parkway, in the Borough of Brooklyn. The proposed revocable consent is for a term of ten years from the Approval Date by the Mayor and provides among other terms and conditions for compensation payable to the City according to the following schedule: **R.P. #2430**

- From the Approval Date by the Mayor to July 1, 2018 - \$3,000/per annum
- For the period July 1, 2018 to June 30, 2019 - \$3,053
- For the period July 1, 2019 to June 30, 2020 - \$3,106
- For the period July 1, 2020 to June 30, 2021 - \$3,159
- For the period July 1, 2021 to June 30, 2022 - \$3,212
- For the period July 1, 2022 to June 30, 2023 - \$3,265
- For the period July 1, 2023 to June 30, 2024 - \$3,318
- For the period July 1, 2024 to June 30, 2025 - \$3,371
- For the period July 1, 2025 to June 30, 2026 - \$3,424
- For the period July 1, 2026 to June 30, 2027 - \$3,477
- For the period July 1, 2027 to June 30, 2028 - \$3,530

the maintenance of a security deposit in the sum of \$3,500 and the insurance shall be in the amount of Two Million Dollars (\$2,000,000) per occurrence for bodily injury and property damage, One Million Dollars (\$1,000,000) for personal and advertising injury, Two Million Dollars (\$2,000,000) aggregate, and Two Million Dollars (\$2,000,000) products/completed operations.

#5 IN THE MATTER OF a proposed revocable consent authorizing Noble Street LLC, to construct, maintain and use a snowmelt system in the north sidewalk of Noble Street, between Franklin Street and Manhattan Avenue, in the Borough of Brooklyn. The proposed revocable consent is for a term of ten years from July 1, 2017 to June 30, 2027, and provides among other terms and conditions for compensation payable to the City according to the following schedule: **R.P. #2432**

- From the Approval Date to June 30, 2028 - \$25/per annum

the maintenance of a security deposit in the sum of \$5,000 and the insurance shall be in the amount of Two Million Dollars (\$2,000,000) per occurrence for bodily injury and property damage, One Million Dollars (\$1,000,000) for personal and advertising injury, Two Million Dollars (\$2,000,000) aggregate, and Two Million Dollars (\$2,000,000) products/completed operations.

#6 IN THE MATTER OF a proposed revocable consent authorizing Process Studio Theatre, Inc., to continue to maintain and use a stairway on the east sidewalk of Church Street, south of Franklin Street, in the Borough of Manhattan. The proposed revocable consent is for a term of ten years from July 1, 2016 to June 30, 2026 and provides among other terms and conditions for compensation payable to the City according to the following schedule: **R.P. #1532**

- For the period July 1, 2016 to June 30, 2026 - \$25/per annum

the maintenance of a security deposit in the sum of \$1,500 and the insurance shall be in the amount of Two Million Dollars (\$2,000,000) per occurrence for bodily injury and property damage, One Million Dollars (\$1,000,000) for personal and advertising injury, Two Million Dollars (\$2,000,000) aggregate, and Two Million Dollars (\$2,000,000) products/completed operations.

#7 IN THE MATTER OF a proposed revocable consent authorizing Sadek Wahba and Suzy Wahba, to continue to maintain and use a stoop on the south sidewalk of East 95th Street, east of Park Avenue, in the Borough of Manhattan. The proposed revocable consent is for a term of ten years from July 1, 2016 to June 30, 2026 and provides among other terms and conditions for compensation payable to the City according to the following schedule: **R.P. #1978**

- For the period July 1, 2017 to June 30, 2018 - \$2,711
- For the period July 1, 2018 to June 30, 2019 - \$2,772
- For the period July 1, 2019 to June 30, 2020 - \$2,833
- For the period July 1, 2020 to June 30, 2021 - \$2,894
- For the period July 1, 2021 to June 30, 2022 - \$2,955
- For the period July 1, 2022 to June 30, 2023 - \$3,016
- For the period July 1, 2023 to June 30, 2024 - \$3,077
- For the period July 1, 2024 to June 30, 2025 - \$3,138
- For the period July 1, 2025 to June 30, 2026 - \$3,199
- For the period July 1, 2026 to June 30, 2027 - \$3,260

the maintenance of a security deposit in the sum of \$3,300 and the insurance shall be in the amount of Two Million Dollars (\$2,000,000) per occurrence for bodily injury and property damage, One Million Dollars (\$1,000,000) for personal and advertising injury, Two Million Dollars (\$2,000,000) aggregate, and Two Million Dollars (\$2,000,000) products/completed operations.

#8 IN THE MATTER OF a proposed revocable consent authorizing Shay & Young LLC, to continue to maintain and use a fenced-in area on the north sidewalk of 85th Avenue, between Bell Boulevard and 217th Street, in the Borough of Queens. The proposed revocable consent is for a term of ten years from July 1, 2017 to June 30, 2027 and provides among other terms and conditions for compensation payable to the City according to the following schedule: **R.P. #1988**

- For the period from July 1, 2017 to June 30, 2027 - \$100/per annum

the maintenance of a security deposit in the sum of \$1,500 and the insurance shall be in the amount of Two Million Dollars (\$2,000,000) per occurrence for bodily injury and property damage, One Million Dollars (\$1,000,000) for personal and advertising injury, Two Million Dollars (\$2,000,000) aggregate, and Two Million Dollars (\$2,000,000) products/completed operations.

#9 IN THE MATTER OF a proposed revocable consent authorizing the Church of Grace to Fujianese, New York, to continue to maintain and use a cellar entrance stairway, together with railing on the west sidewalk of Allen Street, south of Rivington Street, in the Borough of Manhattan. The proposed revocable consent is for a term of ten years from July 1, 2017 to June 30, 2027, and provides among other terms and conditions for compensation payable to the City according to the following schedule: **R.P. #1604**

- For the period July 1, 2017 to June 30, 2018 - \$2,118
- For the period July 1, 2018 to June 30, 2019 - \$2,155
- For the period July 1, 2019 to June 30, 2020 - \$2,192
- For the period July 1, 2020 to June 30, 2021 - \$2,229

- For the period July 1, 2021 to June 30, 2022 - \$2,266
- For the period July 1, 2022 to June 30, 2023 - \$2,303
- For the period July 1, 2023 to June 30, 2024 - \$2,340
- For the period July 1, 2024 to June 30, 2025 - \$2,377
- For the period July 1, 2025 to June 30, 2026 - \$2,414
- For the period July 1, 2026 to June 30, 2027 - \$2,451

the maintenance of a security deposit in the sum of \$2,500 and the insurance shall be in the amount of Two Million Dollars (\$2,000,000) per occurrence for bodily injury and property damage, One Million Dollars (\$1,000,000) for personal and advertising injury, Two Million Dollars (\$2,000,000) aggregate, and Two Million Dollars (\$2,000,000) products/completed operations.

#10 IN THE MATTER OF a proposed revocable consent authorizing Times Warner Center Condominium, to continue to maintain and use bollards on the sidewalks of the site bounded by West 60th Street, Broadway, Columbus Circle and West 58th Street, in the Borough of Manhattan. The proposed revocable consent is for a term of ten years from July 1, 2018 to June 30, 2028, and provides among other terms and conditions for compensation payable to the City according to the following schedule: **R.P. #1879**

For the period from July 1, 2018 to June 30, 2028 - \$28,125/ per annum

the maintenance of a security deposit in the sum of \$60,000 and the insurance shall be in the amount of Two Million Dollars (\$2,000,000) per occurrence for bodily injury and property damage, One Million Dollars (\$1,000,000) for personal and advertising injury, Two Million Dollars (\$2,000,000) aggregate, and Two Million Dollars (\$2,000,000) products/completed operations.

a5-25

PROPERTY DISPOSITION

CITYWIDE ADMINISTRATIVE SERVICES

■ SALE

The City of New York in partnership with PropertyRoom.com posts vehicle and heavy machinery auctions online every week at: <https://www.propertyroom.com/s/nyc+fleet>

All auctions are open to the public and registration is free.

Vehicles can be viewed in person by appointment at: Kenben Industries Ltd., 1908 Shore Parkway, Brooklyn, NY 11214. Phone: (718) 802-0022

m30-s11

OFFICE OF CITYWIDE PROCUREMENT

■ NOTICE

The Department of Citywide Administrative Services, Office of Citywide Procurement is currently selling surplus assets on the internet. Visit <http://www.publicsurplus.com/sms/nycdcas.ny/browse/home>

To begin bidding, simply click on 'Register' on the home page.

There are no fees to register. Offerings may include but are not limited to: office supplies/equipment, furniture, building supplies, machine tools, HVAC/plumbing/electrical equipment, lab equipment, marine equipment, and more.

Public access to computer workstations and assistance with placing bids is available at the following locations:

- DCAS Central Storehouse, 66-26 Metropolitan Avenue, Middle Village, NY 11379
- DCAS, Office of Citywide Procurement, 1 Centre Street, 18th Floor, New York, NY 10007

j2-d31

POLICE

■ NOTICE

OWNERS ARE WANTED BY THE PROPERTY CLERK DIVISION OF THE NEW YORK CITY POLICE DEPARTMENT

The following list of properties is in the custody of the Property Clerk Division without claimants:

Motor vehicles, boats, bicycles, business machines, cameras, calculating machines, electrical and optical property, furniture, furs, handbags, hardware, jewelry, photographic equipment, radios, robes, sound systems, surgical and musical instruments, tools, wearing apparel, communications equipment, computers, and other miscellaneous articles.

Items are recovered, lost, abandoned property obtained from prisoners, emotionally disturbed, intoxicated and deceased persons; and property obtained from persons incapable of caring for themselves.

INQUIRIES

Inquiries relating to such property should be made in the Borough concerned, at the following office of the Property Clerk.

FOR MOTOR VEHICLES (All Boroughs):

- Springfield Gardens Auto Pound, 174-20 North Boundary Road, Queens, NY 11430, (718) 553-9555
- Erie Basin Auto Pound, 700 Columbia Street, Brooklyn, NY 11231, (718) 246-2030

FOR ALL OTHER PROPERTY

- Manhattan - 1 Police Plaza, New York, NY 10038, (646) 610-5906
- Brooklyn - 84th Precinct, 301 Gold Street, Brooklyn, NY 11201, (718) 875-6675
- Bronx Property Clerk - 215 East 161 Street, Bronx, NY 10451, (718) 590-2806
- Queens Property Clerk - 47-07 Pearson Place, Long Island City, NY 11101, (718) 433-2678
- Staten Island Property Clerk - 1 Edgewater Plaza, Staten Island, NY 10301, (718) 876-8484

j2-d31

PROCUREMENT

“Compete To Win” More Contracts!

Thanks to a new City initiative - “Compete To Win” - the NYC Department of Small Business Services offers a new set of FREE services to help create more opportunities for minority and women-owned businesses to compete, connect and grow their business with the City. With NYC Construction Loan, Technical Assistance, NYC Construction Mentorship, Bond Readiness, and NYC Teaming services, the City will be able to help even more small businesses than before.

- *Win More Contracts at nyc.gov/competetowin*

“The City of New York is committed to achieving excellence in the design and construction of its capital program, and building on the tradition of innovation in architecture and engineering that has contributed to the City’s prestige as a global destination. The contracting opportunities for construction/construction services and construction-related services that appear in the individual agency listings below reflect that commitment to excellence.”

HHS ACCELERATOR

To respond to human services Requests for Proposals (RFPs), in accordance with Section 3-16 of the Procurement Policy Board Rules of the City of New York (“PPB Rules”), vendors must first complete and submit an electronic prequalification application using the City’s Health and Human Services (HHS) Accelerator System. The HHS Accelerator System is a web-based system maintained by the City of New York for use by its human services Agencies to manage procurement. The process removes redundancy by capturing information about boards, filings, policies, and general

service experience centrally. As a result, specific proposals for funding are more focused on program design, scope, and budget.

Important information about the new method

- Prequalification applications are required every three years.
- Documents related to annual corporate filings must be submitted on an annual basis to remain eligible to compete.
- Prequalification applications will be reviewed to validate compliance with corporate filings, organizational capacity, and relevant service experience.
- Approved organizations will be eligible to compete and would submit electronic proposals through the system.

The Client and Community Service Catalog, which lists all Prequalification service categories and the NYC Procurement Roadmap, which lists all RFPs to be managed by HHS Accelerator may be viewed at <http://www.nyc.gov/html/hhsaccelerator/html/roadmap/roadmap.shtml>. All current and prospective vendors should frequently review information listed on roadmap to take full advantage of upcoming opportunities for funding.

Participating NYC Agencies

HHS Accelerator, led by the Office of the Mayor, is governed by an Executive Steering Committee of Agency Heads who represent the following NYC Agencies:

- Administration for Children's Services (ACS)
- Department for the Aging (DFTA)
- Department of Consumer Affairs (DCA)
- Department of Corrections (DOC)
- Department of Health and Mental Hygiene (DOHMH)
- Department of Homeless Services (DHS)
- Department of Probation (DOP)
- Department of Small Business Services (SBS)
- Department of Youth and Community Development (DYCD)
- Housing and Preservation Department (HPD)
- Human Resources Administration (HRA)
- Office of the Criminal Justice Coordinator (CJC)

To sign up for training on the new system, and for additional information about HHS Accelerator, including background materials, user guides and video tutorials, please visit www.nyc.gov/hhsaccelerator

ADMINISTRATION FOR CHILDREN'S SERVICES

■ INTENT TO AWARD

Human Services/Client Services

FAMILY FOSTER CARE SERVICES - Negotiated Acquisition - Available only from a single source - PIN#06818N0004 - Due 5-8-18 at 4:00 P.M.

The New York City Administration for Children's Services Office of Procurement, in accordance with Section 3-04(b)(2)(i)(D) of the Procurement Policy Board Rules, intends to enter into a negotiated acquisition with Cumberland Hospital, for the provision of Extraordinary Needs foster care services. The term of the contract is projected to be from October 31, 2018 to June 30, 2020, with one three year renewal option from July 1, 2020 to June 30, 2023. This notice is for information purposes only. Organizations interested in future solicitation for these services, are invited to do so by submitting a simple, electronic prequalification application using the City's new Health and Human Services (HHS) Accelerator System. To prequalify or for additional information about HHS Accelerator, including background materials, user guides and video tutorials, please visit www.nyc.gov/hhsaccelerator.

Use the following address unless otherwise specified in notice, to secure, examine or submit bid/proposal documents, vendor pre-qualification and other forms; specifications/blueprints; other information; and for opening and reading of bids at date and time specified above. Administration for Children's Services, 150 William Street, 9th Floor, New York, NY 10038. Rafael Asusta (212) 341-3511; Fax: (212) 551-7113; rafael.asusta@acs.nyc.gov

a19-25

OFFICE OF PROCUREMENT

■ INTENT TO AWARD

Human Services/Client Services

LIMITED SECURE PLACEMENT SERVICES - Renewal - Due 5-8-18 at 10:00 A.M.

PIN#06813N0007004R001, 06813N0007006R001, 06813N0007001R001.

The Administration for Children's Services (ACS), intends to enter into a contract renewal with the following providers, for the provision of Limited-Secure Placement services. The program service locations are

listed below. The renewal term for each contract will be for four (4) years from September 11, 2018 thru September 10, 2022. Any information concerning the providers' performance as well as any other relevant factors, may be expressed by contacting the listed contact person via email.

Provider	Program Location	Contract Renewal Amount	EPIN
Leake and Watts Services	2250 Ryer Avenue, Bronx, NY 10457	\$21,130,229	06813N0007004R001
Sheltering Arms Children and Family Services	133-23 127th Street, Ozone Park, NY 11783	\$23,092,094	06813N0007006R001
The Children's Village, Inc.	One Echo Hills, Dobbs Ferry, NY 10522	\$15,814,235	06813N0007001R001

Use the following address unless otherwise specified in notice, to secure, examine or submit bid/proposal documents, vendor pre-qualification and other forms; specifications/blueprints; other information; and for opening and reading of bids at date and time specified above. Administration for Children's Services, 150 William Street, 9th Floor, New York, NY 10009. Peter Pabon (212) 341-3450; Fax: (212) 341-3504; peter.pabon@acs.nyc.gov

◀ a25

LIMITED SECURE PLACEMENT SERVICES - Renewal - PIN#06813N0004001R001 - Due 5-8-18 at 10:00 A.M.

The Administration for Children's Services (ACS), intends to enter into a contract renewal with Leake and Watts Services, for the provision of Limited-Secure Placement services. The program service facility is located at, 1125 Carroll Street, Brooklyn, NY 11225. The renewal term for this contract, will be for approximately three (3) years and ten (10) months from November 1, 2018 thru September 10, 2022. The EPIN for this procurement is 06813N0004001R001.

Any information concerning the providers' performance as well as any other relevant factors may be expressed by contacting the listed contact person via email.

Use the following address unless otherwise specified in notice, to secure, examine or submit bid/proposal documents, vendor pre-qualification and other forms; specifications/blueprints; other information; and for opening and reading of bids at date and time specified above.

Administration for Children's Services, 150 William Street, 9th Floor, New York, NY 10009. Peter Pabon (212) 341-3450; Fax: (212) 341-3504; peter.pabon@acs.nyc.gov

◀ a25

CITYWIDE ADMINISTRATIVE SERVICES

OFFICE OF CITYWIDE PROCUREMENT

■ AWARD

Goods

CAR SERVICE, VOUCHER BASED, CITYWIDE - Competitive Sealed Bids - PIN#8571800061 - AMT: \$7,362,639.35 - TO: Corporate Transportation Group Ltd., 335 Bond Street, Brooklyn, NY 11231.

◀ a25

EDUCATION

CONTRACTS AND PURCHASING

■ SOLICITATION

Goods and Services

ASBESTOS BULK AND AIR SAMPLING, ANALYSIS AND PROJECT MONITORING - Competitive Sealed Bids - PIN#B3158040 - Due 6-12-18 at 4:00 P.M.

The Contractor shall provide all labor, material and supervision required and necessary to inspect for asbestos, monitor asbestos projects, report on and describe Asbestos Containing Materials and suspected Asbestos Containing Materials and their condition, approximate the quantity of damaged material, analyze thermal and miscellaneous ACM materials, collect bulk/air samples and analyze and prepare reports and ACP-5 forms as requested, signed and sealed by the NYC DEP certified Asbestos investigator. There will be a Pre-Bid Conference, on Monday, May 7, 2018, at 1:30

P.M., at 65 Court Street, 12th Floor, Conference Room 1201, Brooklyn, NY 11201.

● **REPAIR AND INSTALLATION OF ELECTRICAL FEEDERS - Competitive Sealed Bids - PIN# B3215040 - Due 6-11-18 at 4:00 P.M.** The Contractor shall provide all labor, instruments, materials, equipment, services and supervision required and necessary to service, repair, modify, make additions to and/or install electric feeders and related electrical repair work.

There will be a Pre-Bid Conference, on Monday, May 7, 2018, at 11:30 A.M., at 65 Court Street, 12th Floor, Conference Room 1201, Brooklyn, NY 11201.

● **DELIVERING PARTS AND MATERIALS FOR BOILER REPAIRS AND MAINTENANCE - Competitive Sealed Bids - PIN# B3227040 - Due 6-13-18 at 4:00 P.M.**

The Contractor shall provide all labor, material and supervision required and necessary to provide and deliver boiler parts for repair and maintenance, cleaning materials and tools, and other repair items or equipment.

There will be a Pre-Bid Conference, on Monday, May 7, 2018, at 3:00 P.M., at 65 Court Street, 12th Floor, Conference Room 1201, Brooklyn, NY 11201.

To download description, please go to <http://schools.nyc.gov/Offices/DCP/Vendor/RFB/Default.htm>. If you cannot download, send an email to vendorhotline@schools.nyc.gov, with the RFB number and title in the subject line.

For all questions related to this RFB, please email krdrig7@schools.nyc.gov, with the RFB number and title in the subject line of your email.

The New York City Department of Education (DOE) strives to give all businesses, including Minority and Women-Owned Business Enterprises (MWBES), an equal opportunity to compete for DOE procurements. The DOE's mission is to provide equal access to procurement opportunities for all qualified vendors, including MWBES, from all segments of the community. The DOE works to enhance the ability of MWBES to compete for contracts. DOE is committed to ensuring that MWBES fully participate in the procurement process.

Use the following address unless otherwise specified in notice, to secure, examine or submit bid/proposal documents, vendor pre-qualification and other forms; specifications/blueprints; other information; and for opening and reading of bids at date and time specified above.

Education, 65 Court Street, Room 1201, Brooklyn, NY 11201. Vendor Hotline (718) 935-2300; vendorhotline@schools.nyc.gov



← a25

ENVIRONMENTAL PROTECTION

PURCHASING MANAGEMENT

■ **AWARD**

Goods

MICROSOFT SURFACE HUB AND ACCESSORIES - Innovative Procurement - Other - PIN# 8040109 - AMT: \$41,783.45 - TO: GT Business Supplies LLC, 115-13 Linden Boulevard, South Ozone Park, NY 11420. MWBE Innovative Procurement.

← a25

HUMAN RESOURCES ADMINISTRATION

■ **INTENT TO AWARD**

Human Services/Client Services

NON-EMERGENCY SCATTER SITE HOUSING AND SUPPORTIVE SERVICES FOR PLWAS - Negotiated Acquisition - Other - PIN# 06907P0027CNVN002 - Due 4-26-18 at 2:00 P.M.

For Informational Purposes Only

The Human Resources Administration/HIV/AIDS Services Administration (HASA), intends to enter into a Negotiated Acquisition Extension with the following vendors for the provision of Non-Emergency Scatter Site Housing for PLWAs:

Vendors: Camba, FACES NY, Harlem Congregation, Harlem United (2), Iris House, St. Nicks Alliance (2) Unique People Services (3), and University Consultation and Treatment.
EPIN#: 06907P0027CNVN002
Contract Term: July 1, 2018 to June 30, 2019
Contract Amount: \$19,595,838.00

Under this Negotiated Acquisition Extension, the vendors will continue to provide Housing and Supportive Services for PLWAs.

Vendors interested in responding to this or other future solicitations for these types of services, should contact the New York City Vendor Enrollment Center at (212) 857-1680, or at www.nyc.gov/selltonyc

Use the following address unless otherwise specified in notice, to secure, examine or submit bid/proposal documents, vendor pre-qualification and other forms; specifications/blueprints; other information; and for opening and reading of bids at date and time specified above.

Human Resources Administration, 150 Greenwich Street, 37th Floor, New York, NY 10007. Jacques Fraizer (929) 221-5554; frazierjac@hira.nyc.gov

← a25

PARKS AND RECREATION

■ **VENDOR LIST**

Construction Related Services

PREQUALIFIED VENDOR LIST: GENERAL CONSTRUCTION, NON-COMPLEX GENERAL CONSTRUCTION SITE WORK ASSOCIATED WITH NEW YORK CITY DEPARTMENT OF PARKS AND RECREATION ("DPR" AND/OR "PARKS") PARKS AND PLAYGROUNDS CONSTRUCTION AND RECONSTRUCTION PROJECTS.

DPR is seeking to evaluate and pre-qualify a list of general contractors (a "PQL") exclusively to conduct non-complex general construction site work involving the construction and reconstruction of DPR parks and playgrounds projects not exceeding \$3 million per contract ("General Construction").

By establishing contractor's qualification and experience in advance, DPR will have a pool of competent contractors from which it can draw to promptly and effectively reconstruct and construct its parks, playgrounds, beaches, gardens and green-streets. DPR will select contractors from the General Construction PQL for non-complex general construction site work of up to \$3,000,000.00 per contract, through the use of a Competitive Sealed Bid solicited from the PQL generated from this RFQ.

The vendors selected for inclusion in the General Construction PQL will be invited to participate in the NYC Construction Mentorship. NYC Construction Mentorship focuses on increasing the use of small NYC contracts, and winning larger contracts with larger values. Firms participating in NYC Construction Mentorship will have the opportunity to take management classes and receive on-the-job training provided by a construction management firm.

DPR will only consider applications for this General Construction PQL from contractors who meet any one of the following criteria:

- 1) The submitting entity must be a Certified Minority/Woman Business enterprise (M/WBE)*;
- 2) The submitting entity must be a registered joint venture or have a valid legal agreement as a joint venture, with at least one of the entities in the joint venture being a certified M/WBE*;
- 3) The submitting entity must indicate a commitment to sub-contract no less than 50 percent of any awarded job to a certified M/WBE for every work order awarded.

* Firms that are in the process of becoming a New York City-Certified M/WBE, may submit a PQL application and submit a M/WBE Acknowledgement Letter, which states the Department of Small Business Services has begun the Certification process.

Application documents may also be obtained online at: <http://a856-internet.nyc.gov/nycvendronline/home.asap>; or <http://www.nycgovparks.org/opportunities/business>.

Use the following address unless otherwise specified in notice, to secure, examine or submit bid/proposal documents, vendor pre-qualification and other forms; specifications/blueprints; other information; and for opening and reading of bids at date and time specified above.

Parks and Recreation, Olmsted Center Annex, Flushing Meadows-Corona Park, Flushing, NY 11368. Alicia H. Williams (718) 760-6925; Fax: (718) 760-6885; dmwbe.capital@parks.nyc.gov

j2-d31

■ **SOLICITATION**

Construction/Construction Services

RECONSTRUCTION OF SEWARD PARK - Competitive Sealed Bids - PIN# M082-117M - Due 5-17-18 at 10:30 A.M.

Located at East Broadway, Canal and Essex Streets, Borough of Manhattan. EPIN#: 84618B0124.

This procurement is subject to participation goals for MBEs and/or WBEs as required by Local Law 1 of 2013. This Contract is subject to Apprenticeship Requirements.

Bid Security: Bid Deposit in the amount of 5 percent of Bid Amount or Bid Bond in the amount of 10 percent of Bid Amount. The Cost Estimate Range is: \$3,000,000.00 - \$5,000,000.00

To Request the Plan Holder's List, please call the Blue Print Room, at (718) 760-6576.

Bid documents are available for a fee of \$25.00 in the Blueprint Room, Room #64, Olmsted Center, from 8:00 A.M. to 3:00 P.M. The fee is payable by company check or money order to the City of New York, Parks and Recreation. A separate check/money order is required for each project. The company name, address and telephone number as well as the project contract number must appear on the check/money order. Bidders should ensure that the correct company name, address, telephone and fax numbers are submitted by your company/messenger service when picking up bid documents.

Use the following address unless otherwise specified in notice, to secure, examine or submit bid/proposal documents, vendor pre-qualification and other forms; specifications/blueprints; other information; and for opening and reading of bids at date and time specified above.

Parks and Recreation, Olmsted Center Annex, Flushing Meadows-Corona Park, Flushing, NY 11368. Susana Hersh (718) 760-6855; susana.hersh@parks.nyc.gov

◀ a25

■ INTENT TO AWARD

Goods and Services

SUBWAY ADVERTISEMENT FOR NYC PARKS - Sole Source - Available only from a single source - PIN#84618S0003 - Due 5-17-18 at 11:00 A.M.

The Department of Parks and Recreation intends to enter into a Sole Source Negotiation, with Outfront Media Group, LLC., having an office, located at 405 Lexington Avenue, 14th Floor, New York, NY 10174, to provide advertisement on the Metropolitan Transportation Authority (MTA) subways and buses for special events at various sites.

Any firm that would like to express their interest in providing services for similar projects in the future, may do so by phone and joining the City Bidder's list, by filling out the NYC-FMS Vendor Enrollment form at https://a127-pip.nyc.gov/webapp/PRDPCW/SelfService to enroll your organization with the City of New York.

Use the following address unless otherwise specified in notice, to secure, examine or submit bid/proposal documents, vendor pre-qualification and other forms; specifications/blueprints; other information; and for opening and reading of bids at date and time specified above.

Parks and Recreation, 24 West 61st Street, 3rd Floor, New York, NY 10023. Christopher Miao (212) 830-7983; christopher.miao@parks.nyc.gov

a20-26

CONTRACT AWARD HEARINGS

NOTE: INDIVIDUALS REQUESTING SIGN LANGUAGE INTERPRETERS/TRANSLATORS SHOULD CONTACT THE MAYOR'S OFFICE OF CONTRACT SERVICES, PUBLIC HEARINGS UNIT, 253 BROADWAY, 9TH FLOOR, NEW YORK, NY 10007, (212) 788-7490, NO LATER THAN TEN (10) BUSINESS DAYS PRIOR TO THE PUBLIC HEARING. TDD USERS SHOULD CALL VERIZON RELAY SERVICES.

ENVIRONMENTAL PROTECTION

■ PUBLIC HEARINGS

THIS PUBLIC HEARING HAS BEEN CANCELED

NOTICE IS HEREBY GIVEN that a Public Hearing, will be held, at the Department of Environmental Protection Offices, at 59-17 Junction Boulevard, 17th Floor Conference Room, Flushing, NY, on April 26, 2018 commencing at 10:00 A.M. on the following:

IN THE MATTER OF a proposed contract between the Department of Environmental Protection and G&F Supply, 42 Richmond Terrace, Suite 201, Staten Island, NY 10301, for Electric Actuator: Purchase of 30 Rotork IQ20, Nema4 Enclosure, 460/3/60 Voltage. The Contract amount shall be \$126,746.00 — Location: Borough of Staten Island: Pin 8030615

Contract was selected by Innovative Procurement Method, pursuant to Section 3-12 of the PPB Rules.

Pursuant to Section 2-11(c)(3) of the Procurement Policy Board Rules, if DEP does not receive, by April 18, 2018, from any individual a written request to speak at this hearing, then DEP need not conduct this hearing. Written notice should be sent to Ms. Debra Butlien, NYCDEP, 59-17 Junction Boulevard, 17th Floor, Flushing, NY 11373, or via email to dbutlien@dep.nyc.gov.

A copy of the Contracts may be inspected at the Department of Environmental Protection, 59-17 Junction Boulevard, Flushing, NY 11373, on the 17th Floor Bid Room, on business days from April 13, 2018 to April 26, 2018 between the hours of 9:30 A.M. - 12:00 P.M. and from 1:00 P.M. - 4:00 P.M.

Note: Individuals requesting Sign Language Interpreters should contact Ms. Debra Butlien, Office of the Agency Chief Contracting Officer, 59-17 Junction Boulevard, 17th Floor, Flushing, NY 11373, (718) 595-3423, no later than FIVE (5) BUSINESS DAYS PRIOR TO THE PUBLIC HEARING.

◀ a25

SPECIAL MATERIALS

TRANSPORTATION

■ NOTICE

PUBLIC NOTICE OF A CONCESSION OPPORTUNITY FOR THE OPERATION, MANAGEMENT AND MAINTENANCE OF A PEDESTRIAN PLAZA, LOCATED AT PARK AVENUE (WEST) AND PERSHING SQUARE EAST BETWEEN EAST 41ST STREET AND EAST 42ND STREET, IN THE BOROUGH OF MANHATTAN

Pursuant to the Concession Rules of the City of New York, the Department of Transportation ("DOT"), intends to enter into a concession for the operation, management, and maintenance of a pedestrian plaza located at Park Avenue (West) and Pershing Square East between East 41st Street and East 42nd Street, in the borough of Manhattan ("Licensed Plaza"), including through DOT-approved events, sponsorships, and subconcessions, including but not limited to providing for the sale of any of the following: prepared food, flowers, locally grown produce or locally manufactured products, merchandise (such as souvenirs or T-shirts) that promotes the neighborhood or the concessionaire, or other similar merchandise within the Licensed Plaza.

Subconcessions would be awarded based on solicitations issued by the concessionaire in the basic form of Request for Proposals or Request for Bids, subject to DOT's prior written approval of both solicitation and award.

DOT has identified the Grand Central District Management Association, Inc. as a potential concessionaire, but DOT will consider additional expressions of interest from other potential concessionaires for the operation, management, and maintenance of the Licensed Plaza. In order to qualify, interested organizations should be active in the neighborhood of the Licensed Plaza and have demonstrated experience in the management, operation and maintenance of publicly-accessible facilities, including but not limited to programming/ events management and concession or retail operation/management.

Organizations may express interest in the proposed concession by contacting Emily Weidenhof, Director of Public Space by email at plazas@dot.nyc.gov, or in writing at, 55 Water Street, 6th Floor, New York, NY 10041, by May 7, 2018. Ms. Weidenhof may also be contacted with any questions relating to the proposed concession by email or by telephone at (212) 839-4325.

Please note that the New York City Comptroller is charged with the audit of concession agreements in New York City. Any person or entity that believes that there has been unfairness, favoritism or impropriety in the concession process should inform the Comptroller, Office of Contract Administration, 1 Centre Street, New York, NY 10007, telephone number (212) 669-2323.

◀ a25-m8

PUBLIC NOTICE OF A CONCESSION OPPORTUNITY FOR THE OPERATION, MANAGEMENT AND MAINTENANCE OF A

PEDESTRIAN PLAZA, LOCATED AT THIRD AVENUE, EAST 149TH STREET, WILLIS AVENUE AND EAST 148TH STREET, IN THE BOROUGH OF THE BRONX

Pursuant to the Concession Rules of the City of New York, the Department of Transportation ("DOT") intends to enter into a concession for the operation, management, and maintenance of a pedestrian plaza located at Third Avenue, East 149th Street, Willis Avenue and East 148th Street, in the borough of the Bronx ("Licensed Plaza"), including through DOT-approved events, sponsorships, and subconcessions, including but not limited to providing for the sale of any of the following: prepared food, flowers, locally grown produce or locally manufactured products, merchandise (such as souvenirs or T-shirts) that promotes the neighborhood or the concessionaire, or other similar merchandise within the Licensed Plaza.

Subconcessions would be awarded based on solicitations issued by the concessionaire in the basic form of Request for Proposals or Request for Bids, subject to DOT's prior written approval of both solicitation and award.

It should be noted that the Licensed Plaza previously received FCRC Step 1 approval on September 8, 2010 to enter into negotiations with the South Bronx Overall Economic Development Corporation ("SoBro"). However, in recent years as this Licensed Plaza has been developed and constructed, SoBro has indicated to DOT that it is no longer interested nor has the capacity to undertake the overall management of the Licensed Plaza.

DOT has now identified the HUB-Third Avenue Merchants District Management Association, Inc. as a potential concessionaire, but DOT will consider additional expressions of interest from other potential concessionaires for the operation, management, and maintenance of the Licensed Plaza. In order to qualify, interested organizations should be active in the neighborhood of the Licensed Plaza and have demonstrated experience in the management, operation and maintenance of publicly-accessible facilities, including but not limited to programming/events management and concession or retail operation/management.

Organizations may express interest in the proposed concession by contacting Emily Weidenhof, Director of Public Space by email at plazas@dot.nyc.gov, or in writing at, 55 Water Street, 6th Floor, New York, NY 10041 by May 7, 2018. Ms. Weidenhof may also be contacted with any questions relating to the proposed concession by email or by telephone at (212) 839-4325.

Please note that the New York City Comptroller, is charged with the audit of concession agreements in New York City. Any person or entity that believes that there has been unfairness, favoritism or impropriety in the concession process should inform the Comptroller, Office of Contract Administration, 1 Centre Street, New York, NY 10007, telephone number (212) 669-2323.

• a25-m8

CHANGES IN PERSONNEL

NYC DEPT OF VETERANS' SERVICES FOR PERIOD ENDING 04/06/18

Table with columns: NAME, TITLE, NUM, SALARY, ACTION, PROV EFF DATE, AGENCY. Row: OSTROWSKI, EMILY, S, 56058, \$51840.0000, INCREASE, YES, 03/18/18, 063

ADMIN FOR CHILDREN'S SVCS FOR PERIOD ENDING 04/06/18

Table with columns: NAME, TITLE, NUM, SALARY, ACTION, PROV EFF DATE, AGENCY. Rows include ADAMS, AIRD, AKINYEMI, ARCHBALD, ARGENTIANO, AUDAIN, AYKAN, AZAD, BACHAS, BANKS, BARRIOS, BENON, BERNARD, BISHOP, BOLDEN, BOURGEOIS, BROWN, DENNIS, BURKES-OLUDIPE, CARMODY, CERRETA, COLLINS, CORONEL, DONAHUE, DORSET, ETIENNE.

Table with columns: NAME, TITLE, NUM, SALARY, ACTION, PROV EFF DATE, AGENCY. Rows include EZEIGBO, FARAG, FICALORA, FLAHERTY, FORRESTER, GAINES, GALLOWAY, GARCIA, GAUTIER, GOULD-AIKAWA, GUERRIERA, GUEVARA-BALASSI, GUYEY, HERNANDEZ, HINES, JACKSON, JANVIER, JOHN, KELLER, KING, KNIGHT, LESANE, LINDSAY, LONDON, LOUALLEN.

ADMIN FOR CHILDREN'S SVCS FOR PERIOD ENDING 04/06/18

Table with columns: NAME, TITLE, NUM, SALARY, ACTION, PROV EFF DATE, AGENCY. Rows include MALDONADO, MANIGAULT, MARTINEZ, MAYE JR, MELO, MOSES-KABBA, MOSS-COKER, MOTA, OLMOS, PAGE, PARKES, PATRICK MCDOWAL, PATRISSI, PEPPER, PETERS, PORRAS, POWELL-JOHN, RABBANI, RANDALL, REID, REYES, RIVERA JR, SANTARPIA, SANTOS, SASSO, SAVORY, SETO, SHARIFF, SINGLETON, TAYLOR, THOMAS, TRAMMELL, TUCCI, VILLALOBOS, WADE, WALTON, WARDE, WATTS, WILLIAMS, WILLIAMS, WINNS, ZAMBRANO-ROSADO, ZENG.

HRA/DEPT OF SOCIAL SERVICES FOR PERIOD ENDING 04/06/18

Table with columns: NAME, TITLE, NUM, SALARY, ACTION, PROV EFF DATE, AGENCY. Rows include ADLER, ADONIA, ALFORD, BEAUFORD, BECK, BISHOP, BONET, BRAGINSKY, BROWN, BUSSUE, CANDELLARIO, CARR, CLAUDIO, CROWDER, DALY, DAVALOS, EMEZU, FINK, GREEN, GREENE, HAURON, HEATH, INGRAM.

JEAN	GERALD	52304	\$44492.0000	RETIRED	NO	03/27/18	069
LEWIS	LORETTA	52311	\$55080.0000	RETIRED	NO	03/28/18	069
LIAO	BAOCHENG	40526	\$40369.0000	APPOINTED	NO	03/18/18	069
LOMBAY	JOSHUA A	1002C	\$63929.0000	TRANSFER	NO	03/18/18	069
LOPEZ	DAVID E	52304	\$45378.0000	RESIGNED	NO	03/25/18	069
LOVETT	JEANETTE	56058	\$50362.0000	APPOINTED	YES	03/18/18	069
MAHESE	ZININGI Z	31113	\$54681.0000	INCREASE	NO	03/18/18	069
MCKIVER	SCHINNET	10104	\$40411.0000	DECEASED	NO	03/24/18	069
MEZA	KATHERIN	56057	\$35683.0000	APPOINTED	YES	03/18/18	069
MONTAUBAN	RUTH	31113	\$44409.0000	RESIGNED	NO	01/01/17	069
MURDEN	CYNTHIA L	52316	\$65080.0000	INCREASE	NO	03/18/18	069
MURGUIA	BERENICE M	56057	\$52788.0000	RESIGNED	YES	03/10/18	069
MURRAY	ARETHA	10124	\$56911.0000	DECREASE	NO	04/06/17	069
NOEL	ZOILA V	52314	\$39459.0000	APPOINTED	NO	03/18/18	069
OJI	CHINYERE P	52304	\$44409.0000	DISMISSED	NO	03/30/18	069
OLMSTEAD	FRANCIS	13632	\$91511.0000	RETIRED	NO	03/24/18	069
OWUSU SAFO	GLADYS	10124	\$56911.0000	DECREASE	NO	04/06/17	069
OZERSKAYA	BELLA	13632	\$87731.0000	PROMOTED	NO	03/25/18	069
PARKER	DAVID T	80609	\$36071.0000	APPOINTED	NO	03/18/18	069
PASSANISI	KATHLEEN	10251	\$32087.0000	INCREASE	NO	12/14/14	069
PENA	NADINA H	51110	\$56387.0000	RESIGNED	YES	03/18/18	069
POLAKOVICH	ALEXANDE	92105	\$35480.0000	APPOINTED	YES	03/18/18	069
PULIDO	ALBERT D	10095	\$97408.0000	RESIGNED	YES	03/18/18	069
REID	RONALD A	80609	\$31921.0000	APPOINTED	NO	03/18/18	069
RICHARDSON	SHANNON	40526	\$40369.0000	APPOINTED	NO	03/18/18	069
RUCKER	DESIREE E	12626	\$58152.0000	APPOINTED	NO	03/18/18	069
SARMIENTO	TESSA M	12626	\$58152.0000	APPOINTED	NO	03/18/18	069
SCHREIBER	KURT	95005	\$102000.0000	INCREASE	YES	03/18/18	069

HRA/DEPT OF SOCIAL SERVICES
FOR PERIOD ENDING 04/06/18

TITLE	
NAME	NUM
SCIORTINO	RICHARD A 80609
SCOTT	SONIA 13632
SEN	MALOBKA 52314
SETTLES	FREDRICK S 52314
SHEDRICK	AKILAH N 52314
SILVA	CATHERIN C 13632
SINCLAIR	CAROLINE 52314
SINGLETARY	MITCHELL 10124
STAPLETON	SHARRITA L 52314
TAN	BELMA F 52314
TANG	BRIAN 40526
THOMAS	KAY-TRIN M 31113
THOMPSON	CATHERIN 10251
THORPE	DOMONIQ 52316
TRIVELL	CHRISTOP P 50910
TSOLAKIS	VASILEIO K 40526
USATIN	ANNA 52304
VALENTIN	JERRY S 56057
VASSELL	DIONNE S 12626
WANG	XIRU 12627
WASHINGTON	BEVERLY D 10248
WASHINGTON	BEVERLY D 52316
WEBB	ROBERT 13621
WILLIAMS	CARLENE A 56057
WOODSON	KENNETH H 40526

DEPT. OF HOMELESS SERVICES
FOR PERIOD ENDING 04/06/18

TITLE	
NAME	NUM
ABEDIN	JOYNUL M 70810
AGULAR	MIRIAM 10124
ALBRIGHT	PERNELLE K 70810
ALLEN	LATISHIA B 70810
ARROYO	EDWIN A 31113
BAIN	SANJIB K 70810
BARIN	ADAM H 60860
BARKSDALE	JAMAL L 70810
BASTARDO	RODOLFO N 90698
BRIJLALL	DEVI 70810

LATE NOTICE

CITYWIDE ADMINISTRATIVE SERVICES

OFFICE OF CITYWIDE PROCUREMENT

■ SOLICITATION

Goods

OEM MEALS READY TO EAT (MRE) - Competitive Sealed Bids - PIN# 8571800286 - Due 5-9-18 at 10:00 A.M.

A copy of the bid can be downloaded from the City Record Online site at www.nyc.gov/cityrecord. Enrollment is free. Vendors may also request the bid by contacting Vendor Relations via email at dcasdmssbids@dcas.nyc.gov, by telephone (212) 386-0044, or by fax at (212) 669-7585.

Use the following address unless otherwise specified in notice, to secure, examine or submit bid/proposal documents, vendor pre-qualification and other forms; specifications/blueprints; other information; and for opening and reading of bids at date and time specified above.

Citywide Administrative Services, 1 Centre Street, 18th Floor, New York, NY 10007-1602. Fa-tai Shieh (212) 386-0537, fshieh@dcas.nyc.gov

☛ a25

HOUSING AUTHORITY

PROCUREMENT

■ SOLICITATION

Goods and Services

PROGRAM MANAGEMENT SERVICES - Request for Proposals - PIN# 67062 - Due 5-8-18 at 2:00 P.M.

Provide NYCHA with program management services for the Ideas Marketplace, as detailed more fully within Section II of this Solicitation.

Prospective Proposers may submit, via email, written questions concerning this Solicitation to NYCHA's Coordinator Meddy Ghabaee at meddy.ghabaee@nycha.nyc.gov, and copy Jacques Barbot, at Jacques.barbot@nycha.nyc.gov, by 2:00 P.M., on April 30, 2018. Questions submitted in writing must include the Proposer's name, the name, title, address, telephone number and email address of the individual to whom responses to the Proposer's question should be provided.

Interested firms are invited to obtain a copy on NYCHA's website. To conduct a search for the RFP number; vendors are instructed to open the link: <http://www1.nyc.gov/site/nycha/business/isupplier-vendor-registration.page>. Once on that page, please make a selection from the first three links highlighted in red: New suppliers for those who have never registered with iSupplier, current NYCHA suppliers and vendors for those who have supplied goods or services to NYCHA in the past but never requested a login ID for iSupplier, and Login for registered suppliers if you already have an iSupplier ID and password. Once you are logged into iSupplier, select "Sourcing Supplier," then "Sourcing" followed by "Sourcing Homepage" and then reference the applicable RFP/Solicitation number.

Proposer shall electronically upload a single .pdf containing its Proposal, which may not exceed 4G, into iSupplier. Instructions for registering for iSupplier can be found at <http://www1.nyc.gov/site/nycha/business/isupplier-vendor-registration.page>. After a Proposer registers for iSupplier, it typically takes 24 to 72 hours for Proposer's iSupplier profile to be approved. It is Proposer's sole responsibility to leave ample time to complete iSupplier registration and submit its Proposal through iSupplier before the Proposal Submission Deadline. NYCHA is not responsible for delays caused by technical difficulty or caused by any other occurrence. NYCHA will not accept Proposals via email or facsimile. The submission of attachments containing embedded documents or proprietary file extensions is prohibited.

Each Proposer is required to submit one (1) signed original. In addition to the original of the Proposal, Proposers shall submit one (1) complete and exact copy of the Proposal on CD-ROM or Flash drive in Microsoft Office (2010 version or later) or Adobe pdf format.

Use the following address unless otherwise specified in notice, to secure, examine or submit bid/proposal documents, vendor pre-qualification and other forms; specifications/blueprints; other information; and for opening and reading of bids at date and time specified above.

Housing Authority, 90 Church Street, New York, NY 10007. Meddy Ghabaee (212) 306-4539; meddy.ghabaee@nycha.nyc.gov

☛ a25